



GREEN

G E O T E C H N I C S

GEOTECHNICAL ASSESSMENT

FOR

GRANNY FLAT SOLUTIONS PTY LIMITED

56 CENTRAL ROAD, AVALON BEACH

**REPORT GG10035.081
15 NOVEMBER 2022**

Geotechnical Assessment for a proposed new granny flat to be constructed at 56 Central Road, Avalon Beach

Prepared for

Granny Flat Solutions
90 Pacific Highway
Waitara NSW 2077

Prepared by

Green Geotechnics Pty Limited
PO Box 3244
Rouse Hill, NSW, 2155
ABN: 786 438 493 89
www.greengeo.com.au
matt@greengeo.com.au

15 November 2022

Document Authorisation

Our Ref: GG10035.081

For and on behalf of Green Geotechnics



Matthew Green

Principal Engineering Geologist
BSc Hons, RPGeo

Document Control

Revision	Description	Format	Date	Author	Distributed to
-	Final	PDF	15/11/2022	MG	Granny Flat Solutions (Client)

Table of Contents

1. INTRODUCTION	1
2. INVESTIGATION PROCEDURE.....	2
3. RESULTS OF INVESTIGATION	2
3.1 Site Description	2
3.2 Regional Geology & Subsurface Conditions.....	3
4. LANDSLIDE RISK ASSESSMENT.....	3
4.1 Introduction.....	3
4.2 Purpose of the Assessment.....	4
4.3 Risk Assessment Methodology	4
4.4 Hazard Identification.....	4
4.5 Risk Assessment to Property.....	5
4.6 Risk Assessment to Loss of Life	6
5. GEOTECHNICAL RECOMMENDATIONS.....	8
5.1 Site Classification to AS2870	8
5.2 Wind Classification to AS4055	9
5.3 Foundation Design	9
6 GENERAL RECOMMENDATIONS.....	10

FIGURES

FIGURE 10035.081A – Site Plan and Borehole Locations

FIGURE 10035.081B – Annotated Site Photographs

APPENDICES

Appendix A – Borehole logs and DCP Test Results

Appendix B – AGS 2007 Guidelines

Appendix C – Completed Form 1 & Form 1A

1. INTRODUCTION

This report presents the results of a geotechnical assessment undertaken by Green Geotechnics Pty Limited for a proposed new residential granny flat to be constructed in the rear garden area of 56 Central Road, Avalon Beach. The assessment was commissioned by Granny Flat Solutions Pty Limited.

We understand that it is proposed to construct a single storey granny flat in the rear garden area. As part of the development the existing clad building and deck will be demolished. The granny flat has plan dimensions of 9 metres by 7.5 metres. Construction of the granny flat and garage will require only minor excavations for site preparation, re-grading and foundation construction.

The site is located in an area of sloping ground, and the rear portion of the site is within a H1 Hazard Zone, and therefore Northern Beaches Council require a Landslip Risk Assessment for the site in accordance with Pittwater Councils Geotechnical Risk Management Policy and AGS 2007 Guidelines.

The purpose of the investigation was to

- assess the surface and subsurface conditions over the site,
- provide a Site Classification to AS2870,
- provide a Wind Classification to AS4055,
- provide recommendations regarding the appropriate foundation system for the site including design parameters,
- undertake a slope risk assessment in accordance with AGS2007 Guidelines, assigning both the risk to life and to property, and
- provide recommendations to address the outcomes of the slope risk assessment.

The author of this report is an accredited Slope Risk Assessor.

2. INVESTIGATION PROCEDURE

The fieldwork was carried out on 10 November 2022 and comprised a detailed site walkover together with the drilling of two (2) boreholes numbered BH1 and BH2. Due to restricted site access, the boreholes were drilled using hand auger equipment. The strength of the soils encountered in the borehole was assessed by undertaking a Dynamic Cone Penetrometer (DCP) test adjacent to each borehole. The strength of the weathered bedrock in was assessed by observation of the auger penetration resistance, together with examination of the recovered rock cuttings and nearby rock outcrops.

The test locations, as shown on Figure A, were determined by taped measurements from existing surface features shown on the provided site architectural drawings. Photographs of the site are also attached as Figure B.

Groundwater observations were made in all boreholes during drilling, on completion of drilling and a short time after completion of drilling. No longer term groundwater monitoring was carried out.

The fieldwork was completed in the full-time presence of our senior geologist who set out the test locations, nominated the sampling and testing, and prepared the field logs. The logs are attached to this report, together with a glossary of the terms and symbols used in the logs.

For further details of the investigation techniques adopted, reference should be made to the attached explanation notes.

Environmental and contamination testing of the soils was beyond the agreed scope of the works

3. RESULTS OF INVESTIGATION

3.1 Site Description

The site comprises a roughly rectangular shaped parcel of land with an area of approximately 872m². The site is located on gently to moderately sloping terrain and is located on the northern side of Central Road. At the time of the fieldwork the site was occupied by a two storey brick rendered residential dwelling with tile roof and concrete driveway. There is a small building/garage in the rear garden area with timber deck which we understand will be removed.

The ground surface over the site falls approximately 12 metres to the south from Reduced Level (RL) 28 metres Australian Height Datum (AHD) at the rear site boundary to RL16 metres AHD at the front boundary. The ground surface over the footprint of the proposed granny flat falls approximately 1.2 metres to the south.

The existing dwelling on the subject appears in good condition with no evidence of cracking or deformation in the external walls.

Site vegetation comprised grass, shrubs and trees, with large mature trees growing in the area of the proposed granny flat. There are outcrops of sandstone bedrock in the rear garden area. The outcrops comprise low to medium strength fine to medium grained sandstone bedrock. There are also large detached boulders of bedrock on the site.

To the south of the site is Central Road and to the north, east and west are double storey residential dwellings similar to that on the subject site. The adjoining boundaries are mostly at-grade with the subject site.

No evidence of slope instability was noted during our site inspection.

3.2 Regional Geology & Subsurface Conditions

The 1:100,000 series geological map of the Sydney region (Geological Survey of NSW, Geological Series Sheet 9131) indicates that the site is underlain by Triassic Age bedrock belonging to the Newport formation of the Narrabeen Group. Bedrock within this formation comprises interbedded laminite, shale and quartz to quartz lithic sandstone shale.

The subsurface conditions generally consist of topsoil overlying silty clays and weathered sandstone bedrock. Topsoil materials were encountered to a depth of 0.1 metres. Natural silty clays and residual sandy silty clays were encountered below the topsoil to depths of 0.6 to 0.7 metres. The consistency of the clays varies from firm to stiff to very stiff. Weathered sandstone underlies the soils to the depth of hand auger refusal, 0.64 to 0.8 metres.

Groundwater seepage was not observed during auger drilling of the boreholes

4. LANDSLIDE RISK ASSESSMENT

4.1 Introduction

A landslide risk assessment has been undertaken for 56 Central Road, Avalon Beach. It is not technically feasible to assess the stability of a particular site in absolute terms such as stable or unstable, and it must be recognised by the reader that all sites have a risk of land sliding, however small. However, a risk assessment can be undertaken by the recognition of surface features supplemented by limited information on the regional and local subsurface profile, and with the benefit of experience gained in similar geological environments.

Natural hill slopes are formed by processes that reflect the site geology, environment and climate. These processes include down slope movement of the near surface soil and rock. In geological time all slopes are 'unstable'. The area of influence of these down slope movements may range from local to regional and are rarely related to property boundaries. The natural processes may be affected by human intervention in the form of construction, drainage, fill placement and other activities.

4.2 Purpose of the Assessment

The purpose of this assessment is to enable the owner, potential owner or other parties interested in the site in question, to be aware of the level of risk associated with potential slope movements within the property, and within the area immediately surrounding the property. The risk is assessed considering the existing development of the property and proposed developments of which we have been informed of and which are summarised in this report. The onus is on the owner, potential owner or other party to decide whether the level of risk presented in this report is acceptable in the light of the possible economic consequence of such risk.

4.3 Risk Assessment Methodology

The risk assessment in this report is based on the guidelines on Landslide Risk Management (LRM) as presented in the Australian Geomechanics publication, Volume 42, Number 1, dated March 2007. This issue presents a series of LRM guidelines and further understanding on the application of the risk assessments for the recommended use by all practitioners nationwide.

Definition of the terms used in this report with respect to the slope risk assessment and management are given in Appendix B.

It must be accepted that the risks associated with hillside construction are greater than construction on level ground in the same geological environment. The impact of development may be adverse, and imprudent construction techniques can increase the potential for movement. Areas of instability rarely respect property boundaries and poor practices on one property can trigger instability in the surrounding area.

4.4 Hazard Identification

A landslide is defined as “the movement of a mass of rock, debris or earth down a slope”. Apart from ground subsidence and collapse, this definition is open to the movement of material types including rock, earth and debris down slope. The causes of landslides can be complex. However, two common factors include the occurrence of a failure of part of the soil or rock material on a slope and the resulting movement is driven by gravity. The actual motion of a landslide is subdivided into the five kinematically distinctive types of material movement including fall, topple, slide, spread, and flow. For further information regarding types of landslides please refer to Appendix B – Landslide Terminology from Australian Geomechanics Practice Note Guidelines For Landslide Risk Management 2007.

The frequency of landslides are difficult to quantify and typically dependant on the inter-relationship between the factors influencing the stability of the slope. Some of the common factors affecting the stability of slopes include the weather (prolonged rainfall with water percolating into rock mass defects can cause washout of fines and reduction of rock mass strength), land development, vegetation removal, changes in drainage and earthquakes. One or a combination of these conditions could result in a landslide failure event.

For the site of 56 Central Road, the following landslide hazards have been considered in the risk assessment.

TABLE 4.1 – Landslide Hazard Identification

Position	Hazard Description	Estimated Volume (m ³)	Comment
Above the site	Nil	-	-
Next to the site	Nil	-	-
On the site	Soil Creep	10-20 over the building footprint	Soil Creep can occur where residual clayey soils overlie shallow bedrock. The slope angles on the subject site are however low, and most likely too shallow for soil creep movements to develop
Below the site	Nil	-	-

4.5 Risk Assessment to Property

The Risk to property has been estimated by assessing the likelihood of an event and the consequences if such an event takes place. The relationship between likelihood, consequence and risk is determined by a risk matrix. The risk categories and implications are shown in Attachment 3 (taken from Practice Note Guidelines for Landslide Risk Management 2007, Appendix B).

The assessment process involved the following:

- Risk estimation (comparative analysis of likelihood of a slope failure versus consequence of the failure).
- Evaluation of the estimated (assessed) risk by comparing against acceptance criteria.

The following factors observed during the site walkover were taken into consideration when undertaking the slope risk assessment:

- Topography: The site is situated on gently to moderately sloping ground with low height landscaping retaining walls.
- Geology: The surface soils comprise minor amounts of topsoil overlying residual clays and weathered sandstone bedrock.

- **Drainage:** The site in general is reasonably drained. Groundwater seepage was not observed on the site.
- **Slope stability:** There were no signs of active slope instability noted during the site walkover. There was no evidence of soil creep and there is no historical evidence of deep-seated movements within the shale bedrock within the local area.

Based on the above factors and site observations, an assessment of risk to property have been carried out as shown in Table 4.2 below.

TABLE 4.2 – Risk to Property

Hazard		Soil Creep
Likelihood	Descriptor	Rare
	Approximate Annual Probability	1×10^{-5}
Consequence		Medium
Risk Category		Low

The assessed risk to property is assessed to be low risk. Based on the information provided by the AGS and presented in Attachment 1, Appendix B, the implications for a risk level of low is it is usually acceptable to regulators.

4.6 Risk Assessment to Loss of Life

A risk assessment for the loss of life was undertaken for the identified geotechnical hazards for the site. The risk assessment and management process adopted for this study was carried out in general accordance with AGS (2007a).

In accordance with the AGS 2007c Landslide Risk Management Guidelines for loss of life, the individual risk for loss of life can be calculated from:

$$R_{(LoL)} = P_{(H)} \times P_{(S:H)} \times P_{(T:S)} \times V_{(D:T)}$$

Where

- $R_{(LoL)}$ is the risk - annual probability of loss of life (death) - of an individual.
- $P_{(H)}$ is the annual probability of the landslide.
- $P_{(S:H)}$ is the probability of spatial impact of the landslide impacting on a location potentially occupied by a person.
- $P_{(T:S)}$ is the temporal spatial probability (e.g. of the location being occupied by the individual) given the spatial impact and allowing for the possibility of evacuation given there is warning of the landslide occurrence.

- $V_{(D:T)}$ is the vulnerability of the individual (probability of loss of life of the individual given the impact).

In accordance with AGS 2007, the regulator should set risk acceptance criteria. In this case, Northern Beaches Council is the regulator, and requires the risk to life post development to be 'Tolerable' for existing areas of residential subdivision, provided risk control measures are put in place to control the risk

The risk acceptance criteria consider the occurrence of the potential geotechnical hazards identified for the site and evaluate the risk against a Tolerable Risk Criteria for loss of life. In this instance, the individual risk is accepted due to being tolerable or risk mitigation measures are undertaken to reduce the risk to more tolerable levels.

The AGS 2007 guidelines indicate that the regulator, with assistance from the practitioner where required, is the appropriate authority to set the standards for risk relating to perceived safety in relation to other risks and government policy. The importance of the implementation of levels of the tolerable risk should not be understated due to the wide ranging implications, both in terms of the relative risks or safety to the community and the potential economic impact to the community. The AGS provide recommendations in relation to tolerable risk for loss of life as shown below in Table 4.3.

TABLE 4.3 – AGS Recommendations – Risk to Life

Situation	Suggested Tolerable Loss of Life Risk for Person Most at Risk
Existing Slope ⁽¹⁾ / Existing Development ⁽²⁾	10^{-4} /annum
New Constructed Slope ⁽³⁾ / New Development ⁽⁴⁾ / Existing Landslide	10^{-5} /annum

Notes:

1. "Existing Slopes" in this context are slopes that are not part of a recognisable landslide and have demonstrated non-failure performance over at least several seasons or events of extended adverse weather, usually being a period of at least 10 to 20 years.

2. "Existing Development" includes existing structures, and slopes that have been modified by cut and fill, that are not located on or part of a recognisable landslide and have demonstrated non-failure performance over at least several seasons or events of extended adverse weather, usually being a period of at least 10 to 20 years.

3. "New Constructed Slope" includes any change to existing slopes by cut or fill or changes to existing slopes by new stabilisation works (including replacement of existing retaining walls or replacement of existing stabilisation measures, such as rock bolts or catch fences).

4. "New Development" includes any new structure or change to an existing slope or structure. Where changes to an existing structure or slope result in any cut or fill of less than 1.0m vertical height from the toe to the crest and this change does not increase the risk, then the Existing Slope/Existing Structure criterion may be adopted. Where changes to an existing structure do not increase the building footprint or do not result in an overall change in footing loads, then the Existing Development criterion may be adopted.

5. "Existing Landslides" have been considered likely to require remedial works and hence would become a New Constructed Slope and require the lower risk. Even where remedial works are not required per se, it would be reasonable expectation of the public for a known landslide to be assessed to the lower risk category as a matter of "public safety".

Given the limited depth of proposed earthworks, the development at 56 Central Road may be considered an Existing Development. The AGS risk threshold provided in Table 3.3 for new developments suggests the 'Tolerable Loss of Life for the person most at risk' is 10^{-4} per annum.

The risk assessment has been based on observations made during the site visit by an experienced engineering geologist, and by reviewing available geotechnical data and the future geotechnical requirements for development as outlined elsewhere in this report. Departures from the recommendations in this report may change the quantification of the hazard risk. A risk assessment has been carried out for the identified geotechnical hazards and is presented in Section 4.4 of this report.

The annual probability of a failure occurring has been calculated based on engineering judgement and observations made during the site visit. The probability of spatial impact is calculated by dividing the size of the estimated landslide by the size of the building area, 100m².

The temporal spatial probability has been calculated based on the assumption that someone will be present in the house for 16 hours a day. This is then divided by the number of hours in a day. The vulnerability of an individual is based on values from Australian Geomechanics Vol. 42. If visitor numbers to the site were to increase, then this would change the risk to loss of life. This could affect whether the risk is considered tolerable or otherwise.

Any changes to the site will affect the risk assessment outcome, making it necessary to carry out the risk assessment again.

From our quantitative risk to life assessment, we have estimated the annual probability of risk to life to be in the order of 6.6×10^{-8} . This value is considered acceptable using the AGS risk acceptance criteria.

5. GEOTECHNICAL RECOMMENDATIONS

5.1 Site Classification to AS2870

The classification provided below has been prepared in accordance with the guidelines set out in the “Residential Slabs and Footings” Code, AS2870 – 2011.

Because there are trees and structures present, abnormal moisture conditions (AMC) prevail at the site. (Refer to Section 1.3.3 of AS2870).

Because of the AMC, the site is classified a **Problem Site (P)**. However, provided the recommendations provided in Section 4.3 of this report are incorporated into the structural design, the site may be re-classified as **Moderately Reactive (M)**.

Foundation design and construction consistent with this classification shall be adopted as specified in the above referenced standard and in accordance with the following design details.

5.2 Wind Classification to AS4055

The classification given below has been carried out in accordance with the guidelines set out in AS4055-2012 “Wind loads for housing”.

Region	A
Terrain Category	TC3
Topographic Classification	T1
Shielding	FS
Rating	N1

The classification given above reflects the condition of the site at the time of the investigation. For sites located in developing areas such as new subdivisions the Terrain Category has been based on the likely terrain 5 years after the design.

5.3 Foundation Design

Pad and/or strip footings founded in stiff or very stiff natural materials below any topsoil or fill, may be proportioned using an allowable bearing pressure of 100 kPa. The minimum depth of founding must comply with the requirements of AS2870. In order to overcome the presence of trees, the foundations are to be designed in accordance with Appendices H and CH of AS2870.

Should a higher bearing pressure be required then piles can be used. Piles founded in weathered sandstone may be proportioned using an allowable end bearing pressure of 700 kPa. For piled foundations, an allowable adhesion of 70 kPa may be adopted for the portion of the pile shaft within the weathered rock. When piles bear on weathered rock, adhesion in the overlying soils must be ignored.

A geotechnical engineer or engineering geologist (as defined by the Geotechnical Risk Management Policy for Pittwater) will be required to attend site and inspect the exposed foundations during construction. The inspection and report will need to be accompanied by a completed “Form 3”.

Based on the observations made during auger drilling, the sidewalls of bored piles are expected to remain stable during drilling. However, pile excavations should not be left open overnight. The possibility of some minor seepage at the soil/rock interface needs to be considered when drilling bored piles and pouring concrete.

In order to ensure the bearing values given can be achieved, care should be taken to ensure the base of the pile bores are free of all loose material prior to concreting.

During foundation construction, should the subsurface conditions vary to those inferred in this report, a suitably experienced geotechnical engineer should review the design and recommendations given above to determine if any alterations are required

6 GENERAL RECOMMENDATIONS

Any development on the site should follow good hillside building practices (refer to Attachment 4 for some examples).

Based on the observations made during the site walkover and the risk assessment undertaken, it has been determined that the site has a low risk of slope instability. The site is suitable for residential development provided good hillside building practices are followed. There are no geotechnical constraints for the proposed development of the site.

When assessing the subsurface conditions across a site from a limited number of boreholes, there is the possibility that variations may occur between test locations. The data derived from the site investigation programme are extrapolated across the site to form a geological model and an engineering opinion is rendered about overall subsurface conditions and their likely behaviour regarding the proposed development. The actual condition at the site may differ from those inferred, since no subsurface exploration programme, no matter how comprehensive, can reveal all subsurface details and anomalies.

During foundation construction, should the subsurface conditions vary to those inferred in this report, a suitably experienced geotechnical engineer should review the design and recommendations given above to determine if any alterations are required

Attention is drawn to Appendix B of AS2870 - 2011 regarding the need to properly maintain the foundations. Surface drainage should be provided to avoid the possibility of water ponding near the building and the finished ground surface should fall at least 50 mm over a distance of one metre away from the building.

If excavations for rainwater or detention tanks are to be made within 6 metres of the building foundations, advice should be sought regarding their effect on the foundations.

Placing absorption trenches on the high side of the property of sites underlain by reactive clay may create abnormal moisture conditions for the foundations (Refer to Section 1.3.3 of AS2870). This could have a negative effect on the foundation performance and more than likely alter the site classification provided above.

This report has been prepared assuming that no trees other than those noted will be present on the site. If future tree planting is planned, e.g. there is a landscaping plan, their effect on the foundation performance must be considered

The recommendations presented in this report include specific issues to be addressed during the construction phase of the project. In the event that any of the construction phase recommendations presented in this report are not implemented, the general recommendations may become inapplicable and Green Geotechnics accept no responsibility whatsoever for the performance of the structure where recommendations are not implemented in full and properly tested, inspected and documented.

This report provides advice on geotechnical aspects for the proposed civil and structural design. As part of the documentation stage of this project, Contract Documents and Specifications may be prepared based on our report. However, there may be design features we are not aware of or have not commented on for a variety of reasons. The designers should satisfy themselves that all the necessary advice has been obtained.

If required, we could be commissioned to review the geotechnical aspects of contract documents to confirm the intent of our recommendations has been correctly implemented.

This report has been prepared for the particular project described and no responsibility is accepted for the use of any part of this report in any other context or for any other purpose. If there is any change in the proposed development described in this report then all recommendations should be reviewed. Copyright in this report is the property of Green Geotechnics. We have used a degree of care, skill and diligence normally exercised by consulting engineers in similar circumstances and locality. No other warranty expressed or implied is made or intended. Subject to payment of all fees due for the investigation, the client alone shall have a licence to use this report. The report shall not be reproduced except in full.

REPORT INFORMATION

Introduction

These notes have been provided to amplify Green Geotechnics report in regard to classification methods, field procedures and the comments section. Not all are necessarily relevant to all reports.

Green Geotechnics reports are based on information gained from limited subsurface excavations and sampling, supplemented by knowledge of local geology and experience. For this reason, they must be regarded as interpretive rather than factual documents, limited to some extent by the scope of information on which they rely.

Borehole and Test Pit Logs

The borehole and test pit logs presented in this report are an engineering and/or geological interpretation of the subsurface conditions, and their reliability will depend to some extent on frequency of sampling and the method of drilling or excavation.

Interpretation of the information and its application to design and construction should therefore take into account the spacing of boreholes or pits, the frequency of sampling, and the possibility of other than 'straight line' variations between the test locations.

Groundwater

Where groundwater levels are measured in boreholes there are several limitations, namely:

- In low permeability soils groundwater may enter the hole very slowly or perhaps not at all during the time the hole is left open;
- A localised, perched water table may lead to an erroneous indication of the true water table;
- Water table levels will vary from time to time with seasons or recent weather changes. They may not be the same at the time of construction as are indicated in the report; and
- The use of water or mud as a drilling fluid will mask any groundwater inflow. The borehole must be flushed, and any water must be extracted from the hole if further water measurements are to be made.

More reliable measurements can be made by installing standpipes which are read at intervals over several days, or perhaps weeks for low permeability soils. Piezometers, sealed in a particular stratum, may be advisable in low permeability soils or where there may be interference from a perched water table.

Reports

The report has been prepared by qualified personnel, is based on the information obtained from field and laboratory testing, and has been undertaken to current engineering standards of interpretation and analysis. Where the report has been prepared for a specific design proposal, the information and interpretation may not be relevant if the design proposal is changed. If this happens, GG will be pleased to review the report and the sufficiency of the investigation work.

Every care is taken with the report as it relates to interpretation of subsurface conditions, discussion of geotechnical and environmental aspects, and recommendations or suggestions for design and construction. However, GG cannot always anticipate or assume responsibility for:

- Unexpected variations in ground conditions. The potential for this will depend partly on borehole or pit spacing and sampling frequency;
- Changes in policy or interpretations of policy by statutory authorities; or
- The actions of contractors responding to commercial pressures.

If these occur, Green Geotechnics will be pleased to assist with investigations or advice to resolve the matter.

Site Anomalies




In the event that conditions encountered on site during construction appear to vary from those which were expected from the information contained in the report, GG requests that it be immediately notified. Most problems are much more readily resolved when conditions are exposed rather than at some later stage, well after the event.

Copyright

This report is the property of Green Geotechnics Pty Ltd. The report may only be used for the purpose for which it was commissioned and in accordance with the Conditions of Engagement for the commission supplied at the time of proposal. Unauthorised use of this report in any form whatsoever is prohibited.

FIGURES

Legend:



Project No: GG10035.0081

Client: Granny Flat Solutions

Date: 15 November 2022

Geotechnical Investigation
56 Central Road, Avalon Beach

TEST LOCATION PLAN

Figure No: GG10035.0081A

Drawn By: MG

Scale: Unknown



Rear Garden Area with Rock Outcrops



Rear Garden Area with large detached boulder towards rear boudary



Project No: GG10035.0081

Client: Granny Flat Solutions

Photograph Date: 10th November 2022

Geotechnical Investigation
20 Melville Street, West Ryde

SITE PHOTOGRAPHS

Page: 1 of 2

Figure No: GG10035.0081B



Position of BH1



Position of BH2

APPENDIX A

BOREHOLE LOG AND DCP TEST RESULTS

GEOTECHNICAL LOG - NON CORED BOREHOLE



GREEN
GEOTECHNICS

Project No: GG10035.081
Address: 56 Central Road, Avalon Beach
Client: Granny Flat Solutions Pty Limited

Date Logged : 10/11/2022
Logged By: JK
Checked By: MG

BOREHOLE NO.: BH1

Sheet 1 of 1

W A T E R T A B L E	S A M P L E S	DEPTH (M)	DESCRIPTION (Soil type, colour, grain size, plasticity, minor components, observations)	U S C S Y M B O L	CONSISTENCY (cohesive soils) or RELATIVE DENSITY (sands and gravels)	M O I S T U R E
			TOPSOIL: Silty Sandy CLAY: Dark brown, low plasticity with fine grained sand	CL		D-M
			Silty CLAY: Orange brown, medium to high plasticity with a trace of sand	CI / CH	FIRM TO STIFF	M
		0.5	Silty Sandy CLAY: Light grey with orange brown, low plasticity with fine to medium grained sand (Residual)	CL	VERY STIFF	D-M
			SANDSTONE: Light grey with orange brown, fine to medium grained			D
		1.0	HAND AUGER REFUSAL AT 0.64m ON WEATHERED SANDSTONE BEDROCK			
		1.5				
		2.0				
		2.5				
D - Disturbed sample U - Undisturbed tube sample B - Bulk sample S - Chemical Sample SPT - Standard Penetration Test WT - Standing Water Table SP - Water Seepage Level				Contractor: Green Geotechnics Equipment: Hand Auger Hole Diameter (mm): 62		
NOTES: See explanation sheets for meaning of all descriptive terms and symbols				Angle from Vertical (°): 0 Drill Bit: Mild Steel		

GEOTECHNICAL LOG - NON CORED BOREHOLE



GREEN
GEOTECHNICS

BOREHOLE NO.: BH2

Sheet 1 of 1

Project No: GG10035.081
Address: 56 Central Road, Avalon Beach
Client: Granny Flat Solutions Pty Limited

Date Logged : 10/11/2022
Logged By: JK
Checked By: MG

W A T E R T A B L E	S A M P L E S	DEPTH (M)	DESCRIPTION (Soil type, colour, grain size, plasticity, minor components, observations)	U S C S Y M B O L	CONSISTENCY (cohesive soils) or RELATIVE DENSITY (sands and gravels)	M O I S T U R E
			TOPSOIL: Silty Sandy CLAY: Dark brown, low plasticity with fine grained sand	CL		D-M
			Silty CLAY: Orange brown, medium to high plasticity with a trace of sand	CI / CH	FIRM TO STIFF	M
		0.5	Silty Sandy CLAY: Light grey with orange brown, low plasticity with fine to medium grained sand (Residual)	CL	VERY STIFF	D-M
			SANDSTONE: Light grey with orange brown, fine to medium grained			D
		1.0	HAND AUGER REFUSAL AT 0.8m ON WEATHERED SANDSTONE BEDROCK			
		1.5				
		2.0				
		2.5				
D - Disturbed sample U - Undisturbed tube sample B - Bulk sample S - Chemical Sample SPT - Standard Penetration Test WT - Standing Water Table SP - Water Seepage Level				Contractor: Green Geotechnics Equipment: Hand Auger Hole Diameter (mm): 62		
NOTES: See explanation sheets for meaning of all descriptive terms and symbols				Angle from Vertical (°): 0 Drill Bit: Mild Steel		

Dynamic Cone Penetrometer Test Report



GREEN
GEOTECHNICS

Project No: GG10035.0081

Site Address: 56 Central Road, Avalon Beach

Test Date: 10/11/2022

Page: 1 of 1

Test Method: **AS1289.6.3.2**

Technician: JK

Test No	BH1 /P1	BH2 /P2				
Starting Level	Surface Level	Surface Level				
Depth (m)	Penetration Resistance (blows / 150mm)					
0.00 - 0.15	1	1				
0.15 - 0.30	3	3				
0.30 - 0.45	5	3				
0.45 - 0.60	10	6				
0.60 - 0.75	22	12				
0.75 - 0.90	Refusal	22				
0.90 - 1.05		Refusal				
1.05 - 1.20						
1.20 - 1.35						
1.35 - 1.50						
1.50 - 1.65						
1.65 - 1.80						
1.80 - 1.95						
1.95 - 2.10						
2.10 - 2.25						
2.25 - 2.40						
2.40 - 2.55						
2.55 - 2.70						
2.70 - 2.85						
2.85 - 3.00						

Remarks: * Pre drilled prior to testing

SAMPLING & IN-SITU TESTING

Sampling

Sampling is carried out during drilling or test pitting to allow engineering examination (and laboratory testing where required) of the soil or rock. Disturbed samples taken during drilling provide information on colour, type, inclusions and, depending upon the degree of disturbance, some information on strength and structure. Undisturbed samples are taken by pushing a thin walled sample tube into the soil and withdrawing it to obtain a sample of the soil in a relatively undisturbed state. Such samples yield information on structure and strength and are necessary for laboratory determination of shear strength and compressibility.

Test Pits

Test pits are usually excavated with a backhoe or an excavator, allowing close examination of the in-situ soil if it is safe to enter into the pit. The depth of excavation is limited to about 3 m for a backhoe and up to 6 m for a large excavator.

Large Diameter Augers

Boreholes can be drilled using a large diameter auger, typically up to 300 mm or larger in diameter mounted on a standard drilling rig. The cuttings are returned to the surface at intervals (generally not more than 0.5 m) and are disturbed but usually unchanged in moisture content.

Continuous Spiral Flight Augers

The borehole is advanced using 90-115 mm diameter continuous spiral flight augers which are withdrawn at intervals to allow sampling or in-situ testing. This is a relatively economical means of drilling in clays and sands above the water table. Samples are returned to the surface, or may be collected after withdrawal of the auger flights, but they are disturbed and may be mixed with soils from the sides of the hole.

Non-core Rotary Drilling

The borehole is advanced using a rotary bit, with water or drilling mud being pumped down the drill rods and returned up the annulus, carrying the drill cuttings. Only major changes in stratification can be determined from the cuttings, together with some information from the rate of penetration.

Diamond Core Rock Drilling

A continuous core sample of can be obtained using a diamond tipped core barrel, usually with a 50 mm internal diameter (NMLC). The borehole is advanced using a water or mud flush to lubricate the bit and removed cuttings.

Standard Penetration Tests

Standard penetration tests (SPT) are used as a means of estimating the density or strength of soils and of obtaining a relatively undisturbed sample. The test procedure is described in Australian Standard 1289, Methods of Testing Soils for Engineering Purposes - Test 6.3.1. The test is carried out in a borehole by driving a 50 mm diameter split sample tube under the impact of a 63 kg hammer with a free fall of 760 mm. It is normal for the tube to be driven in three successive 150 mm increments and the 'N' value is taken as the number of blows for the last 300 mm. In dense sands, very hard clays or weak rock, the full 450 mm penetration may not be practicable, and the test is discontinued.

The test results are reported in the following form.

- In the case where full penetration is obtained with successive blow counts for each 150 mm of, say, 4, 6 and 7 as:
4,6,7
N=13
- In the case where the test is discontinued before the full penetration depth, say after 15 blows for the first 150 mm and 30 blows for the next 40 mm as: 15, 30/40 mm.

The results of the SPT tests can be related empirically to the engineering properties of the soils.

Dynamic Cone Penetrometer Tests / Perth Sand Penetrometer Tests

Dynamic penetrometer tests (DCP or PSP) are carried out by driving a steel rod into the ground using a standard weight of hammer falling a specified distance. As the rod penetrates the soil the number of blows required to penetrate each successive 150 mm depth are recorded. Two types of penetrometer are commonly used.

- Perth sand penetrometer - a 16 mm diameter flat ended rod is driven using a 9 kg hammer dropping 600 mm (AS 1289, Test 6.3.3). This test was developed for testing the density of sands and is mainly used in granular soils and filling.
- Cone penetrometer - a 16 mm diameter rod with a 20 mm diameter cone end is driven using a 9 kg hammer dropping 510 mm (AS 1289, Test 6.3.2). This test was developed initially for pavement subgrade investigations, and correlations of the test results with California Bearing Ratio have been published by various road authorities.

SOIL DESCRIPTIONS

Description and Classification Methods

The methods of description and classification of soils and rocks used in this report are based on Australian Standard AS 1726, Geotechnical Site Investigations Code. In general, the descriptions include strength or density, colour, structure, soil or rock type and inclusions.

Soil Types

Soil types are described according to the predominant particle size, qualified by the grading of other particles present:

Type	Particle Size (mm)
Boulder >200	Boulder >200
Cobble 63 - 200	Cobble 63 - 200
Gravel 2.36 - 63	Gravel 2.36 - 63
Sand 0.075 - 2.36	Sand 0.075 - 2.36
Silt 0.002 - 0.075	Silt 0.002 - 0.075
Clay <0.002	Clay <0.002

The sand and gravel sizes can be further subdivided as follows:

Type	Particle Size (mm)
Coarse Gravel	20 – 63
Medium Gravel	6 – 20
Fine Sand	2.36 – 6
Coarse Sand	0.6 – 2.36
Medium Sand	0.2 – 0.6
Fine Sand	0.075 – 0.2

The proportions of secondary constituents of soils are described as:

Term	Proportion
And	Specify
Adjective	20 - 35%
Slightly	12 - 20%
With some	5 - 12%
With a trace of	0 - 5%

Definitions of grading terms used are:

- Well graded - a good representation of all particle sizes
- Poorly graded - an excess or deficiency of particular sizes within the specified range
- Uniformly graded - an excess of a particular particle size
- Gap graded - a deficiency of a particular particle size with the range

Cohesive Soils

Cohesive soils, such as clays, are classified on the basis of undrained shear strength. The strength may be measured by laboratory testing, or estimated by field tests or engineering examination. The strength terms are defined as follows:

Description	Abbreviation	Undrained Shear Strength (kPa)
Very soft	VS	<12
Soft	S	12 - 25
Firm	F	25 - 50
Stiff	ST	50 - 100
Very stiff	VST	100 - 200
Hard	H	200

Cohesionless Soils

Cohesionless soils, such as clean sands, are classified on the basis of relative density, generally from the results of standard penetration tests (SPT), cone penetration tests (CPT) or dynamic penetrometers (DCP). The relative density terms are given below:

Relative Density	Abbreviation	SPT N Value	CPT qc value (MPa)
Very loose	VL	<4	<2
Loose	L	4 - 10	2 - 5
Medium Dense	MD	10-30	5-15
Dense	D	30-50	15-25
Very Dense	VD	>50	>25

Soil Origin

It is often difficult to accurately determine the origin of a soil. Soils can generally be classified as:

- Residual soil - derived from in-situ weathering of the underlying rock;
- Transported soils - formed somewhere else and transported by nature to the site; or
- Filling - moved by man.

Transported soils may be further subdivided into:

- Alluvium - river deposits
- Lacustrine - lake deposits
- Aeolian - wind deposits
- Littoral - beach deposits
- Estuarine - tidal river deposits
- Talus - scree or coarse colluvium
- Slope wash or Colluvium - transported downslope by gravity assisted by water. Often includes angular rock fragments and boulders.

ROCK DESCRIPTIONS

Rock Strength

The Rock strength is defined by the Point Load Strength Index ($IS_{(50)}$) and refers to the strength of the rock substance and not the strength of the overall rock mass, which may be considerably weaker due to defects. The test procedure is described by Australian Standard 4133.4.1 - 1993. The terms used to describe rock strength are as follows:

Term	Abbreviation	Point Load Index $IS_{(50)}$ MPa	Approximate Unconfined Compressive Strength MPa*
Extremely low	EL	<0.03	<0.6
Very low	VL	0.03 - 0.1	0.6 - 2
Low	L	0.1 - 0.3	2 - 6
Medium	M	0.3 - 1.0	6 - 20
High	H	1 - 3	20 - 60
Very high	VH	3 - 10	60 - 200

* Assumes a ratio of 20:1 for UCS to $IS_{(50)}$

Degree of Weathering

The degree of weathering of rock is classified as follows:

Term	Abbreviation	Description
Extremely weathered	EW	Rock substance has soil properties, i.e. it can be remoulded and classified as a soil but the texture of the original rock is still evident.
Highly weathered	HW	Limonite staining or bleaching affects whole of rock substance and other signs of decomposition are evident. Porosity and strength may be altered as a result of iron leaching or deposition. Colour and strength of original fresh rock is not recognisable.
Moderately weathered	MW	Staining and discolouration of rock substance has taken Place.
Slightly weathered	SW	Rock substance is slightly discoloured but shows little or no change of strength from fresh rock.
Fresh stained	FS	Rock substance unaffected by weathering but staining visible along defects.
Fresh	FR	No signs of decomposition or staining.

Degree of Fracturing

The following classification applies to the spacing of natural fractures in core samples (bedding plane partings, joints and other defects, excluding drilling breaks

Term	Description
Fragmented	Fragments of <20 mm
Highly Fractured	Core lengths of 20-40 mm with some fragments
Fractured Core	Core lengths of 40-200 mm with some shorter and longer sections
Slightly Fractured	Core lengths of 200-1000 mm with some shorter and loner sections
Unbroken	Unbroken Core lengths mostly > 1000 mm

Stratification Spacing

For sedimentary rocks the following terms may be used to describe the spacing of bedding partings:

Term	Separation of Stratification Planes
Thinly laminated	6 mm
Laminated	6 mm to 20 mm
Very thinly bedded	20 mm to 60 mm
Thinly bedded	60 mm to 0.2 m
Medium bedded	0.2 m to 0.6 m
Thickly bedded	0.6 m to 2 m
Very thickly bedded	2 m

Rock Quality Designation

The quality of the cored rock can be measured using the Rock Quality Designation (RQD) index, defined as:

$$RQD \% = \frac{\text{cumulative length of 'sound' core sections} \geq 100 \text{ mm long}}{\text{total drilled length of section being assessed}}$$

'sound' rock is assessed to be rock of low strength or better. The RQD applies only to natural fractures. If the core is broken by drilling/handling, then the broken pieces are fitted back together and are not included in the calculation of RQD.

ABBREVIATIONS

Introduction

These notes summarise abbreviations commonly used on borehole logs and test pit reports.

Drilling or Excavation Methods

C	Core Drilling
R	Rotary drilling
SFA	Spiral flight augers
NMLC	Diamond core - 52 mm dia
NQ	Diamond core - 47 mm dia
HQ	Diamond core - 63 mm dia
PQ	Diamond core - 81 mm dia

Water

Z	Water seep
V	Water level

Sampling and Testing

A	Auger sample
B	Bulk sample
D	Disturbed sample
S	Chemical sample
U50	Undisturbed tube sample (50mm)
W	Water sample
PP	Pocket Penetrometer (kPa)
PL	Point load strength $I_s(50)$ MPa
S	Standard Penetration Test
V	Shear vane (kPa)

Description of Defects in Rock

The abbreviated descriptions of the defects should be in the following order: Depth, Type, Orientation, Coating, Shape, Roughness and Other. Drilling and handling breaks are not usually included on the logs.

Defect Type

B	Bedding plane
Cs	Clay seam
Cv	Cleavage
Cz	Crushed zone
Ds	Decomposed seam
F	Fault
J	Joint
Lam	lamination
Pt	Parting
Sz	Sheared Zone
V	Vein

Orientation

The inclination of defects is always measured from the perpendicular to the core axis.

h	horizontal
v	vertical
sh	sub-horizontal
sv	sub-vertical

Coating or Infilling Term

cln	clean
co	coating
he	healed
inf	infilled
stn	stained
ti	tight
vn	veneer

Coating Descriptor

ca	calcite
cbs	carbonaceous
cl	clay
fe	iron oxide
mn	manganese
slt	silty

Shape

cu	curved
ir	irregular
pl	planar
st	stepped
un	undulating

Roughness

po	polished
ro	rough
sl	slickensided
sm	smooth
vr	very rough

Other

fg	fragmented
bnd	band
qtz	quartz

UNIFIED SOIL CLASSIFICATION TABLE

Field Identification Procedures (Excluding particles larger than 75um and basing fractions on estimated weights)					Group Symbols	Typical Names	Information Required for Describing Soils	Laboratory Classification Criteria						
Coarse-grained soils More than half of the material is larger than 75um sieve size ^a	Gravels More than half of the coarse fraction is larger than a 4mm sieve	Clean gravels (little or no fines)	Wide range in grain size and substantial amounts of all intermediate particle sizes		GW	Well graded gravels, gravel-sand mixtures, little or no fines	Give typical name: indicative approximate percentages of sand and gravel; maximum size; angularity; surface condition, and hardness of the coarse grains; local of geologic name and other pertinent descriptive information; and symbols in parentheses For undisturbed soils add information on stratification, degree of compactness, cementation, moisture conditions and drainage characteristics Example: <i>Silty Sand</i> , gravelly; about 20% hard, angular gravel particles 12mm maximum size; rounded and subangular sand grains, coarse to fine, about 15% non-plastic fines low dry strength; well compacted and moist in place; alluvial sand; (<i>SM</i>)	Determine percentages of gravel and sand from grain size curve Depending on percentage of fines (fraction smaller than 75um sieve size) Less than 5% GW, GP, SW, SP More than 12% GM, GC, SM, SC 5 to 12% Borderline cases requiring use of dual symbol	$C_u = \frac{D_{60}}{D_{10}}$ Greater than 4 $C_c = \frac{(D_{30})^2}{D_{10} \times D_{60}}$ Between 1 and 3					
			Predominantly one size or range of sizes with some intermediate sizes missing		GP	Poorly graded gravels, grave-sand mixtures, little or no fines			Not meeting all gradation requirements for GW					
		Gravels with fines (appreciable amount of fines)	Nonplastic fines (for identification procedures see <i>ML</i> below)		GM	Silty gravels, poorly graded gravel-sand-silt mixtures			Atterberg limits below "A" line or <i>PI</i> less than 4	Above "A" line with <i>PI</i> between 4 and 7 are borderline cases of requiring use of dual symbols				
			Plastic fines (for identification procedures see <i>CL</i> below)		GC	Clayey gravels, poorly graded gravel-sand-clay mixtures			Atterberg limits above "A" line with <i>PI</i> greater than 7					
	Sands More than half of the coarse fraction is smaller than a 4mm sieve	Clean sands (little or no fines)	Wide range in grain size and substantial amounts of all intermediate particle sizes		SW	Well graded sands, gravelly sands, little or no fines			$C_u = \frac{D_{60}}{D_{10}}$ Greater than 6 $C_c = \frac{(D_{30})^2}{D_{10} \times D_{60}}$ Between 1 and 3					
			Predominantly one size or range of sizes with some intermediate sizes missing		SP	Poorly graded sands, gravelly sands, little or no fines			Not meeting all gradation requirements for SW					
		Sands with fines (appreciable amount of fines)	Nonplastic fines (for identification procedures see <i>ML</i> below)		SM	Silty sands, poorly graded sand-silt mixtures			Atterberg limits below "A" line or <i>PI</i> less than 5	Above "A" line with <i>PI</i> between 4 and 7 are borderline cases of requiring use of dual symbols				
			Plastic fines (for identification procedures see <i>CL</i> below)		SC	Clayey sands, poorly graded sand-clay mixtures			Atterberg limits above "A" line with <i>PI</i> greater than 7					
			Identification Procedures of Fractions Smaller than 380 um Sieve Size											
			Sils and clays liquid limit less than 50	Dry Strength (crushing characteristics)	Dilatancy (reaction to shaking)	Toughness (consistency near plastic limit)					Give typical name: indicative degree and character of plasticity, amount and maximum size of coarse grains; colour in wet condition, odour if any, local or geologic name, and other pertinent descriptive information, and symbol in parentheses For undisturbed soils add information on structure, stratification, consistency in undisturbed and remoulded states, moisture and drainage conditions Example: <i>Clayey Silt</i> , brown; slightly plastic; small percentage of fine sand; numerous vertical root holes; firm and dry in place; loess; (<i>ML</i>)	Use grain size curve in identifying the fractions as given under field identification	PLASTICITY CHART	
ML	Inorganic silts and very fine sands, rock flour, silty or clayey fine sands with silt plasticity													
CL	Inorganic clays of low to medium plasticity, gravelly clays, sandy clays, silty clays, lean clays													
OL	Organic silts and organic silt-clays of low plasticity													
Sils and clays liquid limit greater than 50	Slight to medium	Slow to none	Slight to medium	MH	Inorganic silts, micaceous or diatomaceous fine sandy or silty soils, clastic silts									
	High to very high	None	High	CH	Inorganic clays of high plasticity, fat clays									
	Medium to high	None to very slow	Slight to medium	OH	Organic clays of medium to high plasticity									
Highly Organic Soils			Readily identified by colour, odour, spongy feel and frequently by fibrous texture		Pt	Peat and other highly organic soils	Plasticity Chart For laboratory classification of fine-grained soils							

- Note:
- 1 Soils possessing characteristics of two groups are designated by combinations of group symbols (eg. GW-GC, well graded gravel-sand mixture with clay fines)
 - 2 Soils with liquid limits of the order of 35 to 50 may be visually classified as being of medium plasticity

APPENDIX B

AGS 2007 GUIDELINES

PRACTICE NOTE GUIDELINES FOR LANDSLIDE RISK MANAGEMENT 2007
ATTACHMENT 1: LANDSLIDE RISK ASSESSMENT
QUALITATIVE TERMINOLOGY FOR USE IN ASSESSING RISK TO PROPERTY

QUALITATIVE MEASURES OF LIKELIHOOD

Approximate Annual Probability		Implied Indicative Landslide Recurrence Interval		Description	Descriptor	Level
Indicative Value	Notional Boundary					
10 ⁻¹	5x10 ⁻²	10 years	20 years	The event is expected to occur over the design life.	ALMOST CERTAIN	A
10 ⁻²		100 years		The event will probably occur under adverse conditions over the design life.	LIKELY	B
10 ⁻³	5x10 ⁻³	1000 years	200 years	The event could occur under adverse conditions over the design life.	POSSIBLE	C
10 ⁻⁴	5x10 ⁻⁴	10,000 years	2000 years	The event might occur under very adverse circumstances over the design life.	UNLIKELY	D
10 ⁻⁵	5x10 ⁻⁵	100,000 years	20,000 years	The event is conceivable but only under exceptional circumstances over the design life.	RARE	E
10 ⁻⁶	5x10 ⁻⁶	1,000,000 years	200,000 years	The event is inconceivable or fanciful over the design life.	BARELY CREDIBLE	F

Note: (1) The table should be used from left to right; use Approximate Annual Probability or Description to assign Descriptor, not *vice versa*.

QUALITATIVE MEASURES OF CONSEQUENCES TO PROPERTY

Approximate Cost of Damage		Description	Descriptor	Level
Indicative Value	Notional Boundary			
200%	100%	Structure(s) completely destroyed and/or large scale damage requiring major engineering works for stabilisation. Could cause at least one adjacent property major consequence damage.	CATASTROPHIC	1
60%		Extensive damage to most of structure, and/or extending beyond site boundaries requiring significant stabilisation works. Could cause at least one adjacent property medium consequence damage.	MAJOR	2
20%	40%	Moderate damage to some of structure, and/or significant part of site requiring large stabilisation works. Could cause at least one adjacent property minor consequence damage.	MEDIUM	3
5%	10%	Limited damage to part of structure, and/or part of site requiring some reinstatement stabilisation works.	MINOR	4
0.5%	1%	Little damage. (Note for high probability event (Almost Certain), this category may be subdivided at a notional boundary of 0.1%. See Risk Matrix.)	INSIGNIFICANT	5

- Notes:** (2) The Approximate Cost of Damage is expressed as a percentage of market value, being the cost of the improved value of the unaffected property which includes the land plus the unaffected structures.
- (3) The Approximate Cost is to be an estimate of the direct cost of the damage, such as the cost of reinstatement of the damaged portion of the property (land plus structures), stabilisation works required to render the site to tolerable risk level for the landslide which has occurred and professional design fees, and consequential costs such as legal fees, temporary accommodation. It does not include additional stabilisation works to address other landslides which may affect the property.
- (4) The table should be used from left to right; use Approximate Cost of Damage or Description to assign Descriptor, not *vice versa*

PRACTICE NOTE GUIDELINES FOR LANDSLIDE RISK MANAGEMENT 2007

ATTACHMENT 1: – QUALITATIVE TERMINOLOGY FOR USE IN ASSESSING RISK TO PROPERTY (CONTINUED)

QUALITATIVE RISK ANALYSIS MATRIX – LEVEL OF RISK TO PROPERTY

LIKELIHOOD		CONSEQUENCES TO PROPERTY (With Indicative Approximate Cost of Damage)				
	Indicative Value of Approximate Annual Probability	1: CATASTROPHIC 200%	2: MAJOR 60%	3: MEDIUM 20%	4: MINOR 5%	5: INSIGNIFICANT 0.5%
A – ALMOST CERTAIN	10 ⁻¹	VH	VH	VH	H	M or L (5)
B – LIKELY	10 ⁻²	VH	VH	H	M	L
C – POSSIBLE	10 ⁻³	VH	H	M	M	VL
D – UNLIKELY	10 ⁻⁴	H	M	L	L	VL
E – RARE	10 ⁻⁵	M	L	L	VL	VL
F – BARELY CREDIBLE	10 ⁻⁶	L	VL	VL	VL	VL

Notes: (5) For Cell A5, may be subdivided such that a consequence of less than 0.1% is Low Risk.

(6) When considering a risk assessment it must be clearly stated whether it is for existing conditions or with risk control measures which may not be implemented at the current time.

RISK LEVEL IMPLICATIONS

Risk Level		Example Implications (7)
VH	VERY HIGH RISK	Unacceptable without treatment. Extensive detailed investigation and research, planning and implementation of treatment options essential to reduce risk to Low; may be too expensive and not practical. Work likely to cost more than value of the property.
H	HIGH RISK	Unacceptable without treatment. Detailed investigation, planning and implementation of treatment options required to reduce risk to Low. Work would cost a substantial sum in relation to the value of the property.
M	MODERATE RISK	May be tolerated in certain circumstances (subject to regulator's approval) but requires investigation, planning and implementation of treatment options to reduce the risk to Low. Treatment options to reduce to Low risk should be implemented as soon as practicable.
L	LOW RISK	Usually acceptable to regulators. Where treatment has been required to reduce the risk to this level, ongoing maintenance is required.
VL	VERY LOW RISK	Acceptable. Manage by normal slope maintenance procedures.

Note: (7) The implications for a particular situation are to be determined by all parties to the risk assessment and may depend on the nature of the property at risk; these are only given as a general guide.

ATTACHMENT 2 - DEFINITION OF TERMS AND LANDSLIDE RISK

(Australian Geomechanics Vol 42 No 1 March 2007)

Acceptable Risk – A risk for which, for the purposes of life or work, we are prepared to accept as it is with no regard to its management. Society does not generally consider expenditure in further reducing such risks justifiable.

Annual Exceedance Probability (AEP) – The estimated probability that an event of specified magnitude will be exceeded in any year.

Consequence – The outcomes or potential outcomes arising from the occurrence of a landslide expressed qualitatively or quantitatively, in terms of loss, disadvantage or gain, damage, injury or loss of life.

Elements at Risk – The population, buildings and engineering works, economic activities, public services utilities, infrastructure and environmental features in the area potentially affected by landslides.

Frequency – A measure of likelihood expressed as the number of occurrences of an event in a given time. See also Likelihood and Probability.

Hazard – A condition with the potential for causing an undesirable consequence (the landslide). The description of landslide hazard should include the location, volume (or area), classification and velocity of the potential landslides and any resultant detached material, and the likelihood of their occurrence within a given period of time.

Individual Risk to Life – The risk of fatality or injury to any identifiable (named) individual who lives within the zone impacted by the landslide; or who follows a particular pattern of life that might subject him or her to the consequences of the landslide.

Landslide Activity – The stage of development of a landslide; pre failure when the slope is strained throughout but is essentially intact; failure characterised by the formation of a continuous surface of rupture; post failure which includes movement from just after failure to when it essentially stops; and reactivation when the slope slides along one or several pre-existing surfaces of rupture. Reactivation may be occasional (e.g. seasonal) or continuous (in which case the slide is “active”).

Landslide Intensity – A set of spatially distributed parameters related to the destructive power of a landslide. The parameters may be described quantitatively or qualitatively and may include maximum movement velocity, total displacement, differential displacement, depth of the moving mass, peak discharge per unit width, kinetic energy per unit area.

Landslide Risk – The AGS Australian GeoGuide LR7 (AGS, 2007e) should be referred to for an explanation of Landslide Risk.

Landslide Susceptibility – The classification, and volume (or area) of landslides which exist or potentially may occur in an area or may travel or retrogress onto it. Susceptibility may also include a description of the velocity and intensity of the existing or potential landsliding.

Likelihood – Used as a qualitative description of probability or frequency.

Probability – A measure of the degree of certainty. This measure has a value between zero (impossibility) and 1.0 (certainty). It is an estimate of the likelihood of the magnitude of the uncertain quantity, or the likelihood of the occurrence of the uncertain future event.

There are two main interpretations:

(i) Statistical – frequency or fraction – The outcome of a repetitive experiment of some kind like flipping coins. It includes also the idea of population variability. Such a number is called an “objective” or relative frequentist probability because it exists in the real world and is in principle measurable by doing the experiment.

(ii) Subjective probability (degree of belief) – Quantified measure of belief, judgment, or confidence in the likelihood of an outcome, obtained by considering all available information honestly, fairly, and with a minimum of bias. Subjective probability is affected by the state of understanding of a process, judgment regarding an evaluation, or the quality and quantity of information. It may change over time as the state of knowledge changes.

Qualitative Risk Analysis – An analysis which uses word form, descriptive or numeric rating scales to describe the magnitude of potential consequences and the likelihood that those consequences will occur.

Quantitative Risk Analysis – An analysis based on numerical values of the probability, vulnerability and consequences and resulting in a numerical value of the risk.

Risk – A measure of the probability and severity of an adverse effect to health, property or the environment. Risk is often estimated by the product of probability x consequences. However, a more general interpretation of risk involves a comparison of the probability and consequences in a non-product form.

Risk Analysis – The use of available information to estimate the risk to individual, population, property, or the environment, from hazards. Risk analyses generally contain the following steps: Scope definition, hazard identification and risk estimation.

Risk Assessment – The process of risk analysis and risk evaluation.

Risk Control or Risk Treatment – The process of decision making for managing risk and the implementation or enforcement of risk mitigation measures and the re-evaluation of its effectiveness from time to time, using the results of risk assessment as one input.

Risk Estimation – The process used to produce a measure of the level of health, property or environmental risks being analysed. Risk estimation contains the following steps: frequency analysis, consequence analysis and their integration.

Risk Evaluation – The stage at which values and judgments enter the decision process, explicitly or implicitly, by including consideration of the importance of the estimated risks and the associated social, environmental and economic consequences, in order to identify a range of alternatives for managing the risks.

Risk Management – The complete process of risk assessment and risk control (or risk treatment).


Societal Risk – The risk of multiple fatalities or injuries in society as a whole: one where society would have to carry the burden of a landslide causing a number of deaths, injuries, financial, environmental and other losses.

Susceptibility – see Landslide Susceptibility


Temporal Spatial Probability – The probability that the element at risk is in the area affected by the landsliding, at the time of the landslide.

Tolerable Risk – A risk within a range that society can live with so as to secure certain net benefits. It is a range of risk regarded as non-negligible and needing to be kept under review and reduced further if possible.


Vulnerability – The degree of loss to a given element or set of elements within the area affected by the landslide hazard. It is expressed on a scale of 0 (no loss) to 1 (total loss). For property, the loss will be the value of the damage relative to the value of the property; for persons, it will be the probability that a particular life (the element at risk) will be lost, given the person(s) is affected by the landslide.




Rotational landslide




Translational landslide




Block slide




Rockfall



Topple




Debris flow



Debris avalanche



Earthflow



Creep



Lateral spread


ATTACHMENT 3 MAJOR TYPES OF LANDSLIDES

ATTACHMENT 4


SOME GUIDELINES FOR HILLSIDE CONSTRUCTION

ADVICE		GOOD ENGINEERING PRACTICE	POOR ENGINEERING PRACTICE
GEOTECHNICAL ASSESSMENT		Obtain advice from a qualified, experienced geotechnical consultant at early stage of planning and before site works.	Prepare detailed plan and start site works before geotechnical advice.
PLANNING			
SITE PLANNING		Having obtained geotechnical advice, plan the development with the risk arising from the identified hazards and consequences in mind.	Plan development without regard for the Risk.
DESIGN AND CONSTRUCTION			
HOUSE DESIGN		Use flexible structures which incorporate properly designed brickwork, timber or steel frames, timber or panel cladding. Consider use of split levels. Use decks for recreational areas where appropriate.	Floor plans which require extensive cutting and filling. Movement intolerant structures.
SITE CLEARING		Retain natural vegetation wherever practicable.	Indiscriminately clear the site.
ACCESS & DRIVEWAYS		Satisfy requirements below for cuts, fills, retaining walls and drainage. Council specifications for grades may need to be modified. Driveways and parking areas may need to be fully supported on piers.	Excavate and fill for site access before geotechnical advice.
EARTHWORKS		Retain natural contours wherever possible.	Indiscriminant bulk earthworks.
CUTS		Minimise depth. Support with engineered retaining walls or batter to appropriate slope. Provide drainage measures and erosion control.	Large scale cuts and benching. Unsupported cuts. Ignore drainage requirements
FILLS		Minimise height. Strip vegetation and topsoil and key into natural slopes prior to filling. Use clean fill materials and compact to engineering standards. Batter to appropriate slope or support with engineered retaining wall. Provide surface drainage and appropriate subsurface drainage.	Loose or poorly compacted fill, which if it fails, may flow a considerable distance including onto property below. Block natural drainage lines. Fill over existing vegetation and topsoil. Include stumps, trees, vegetation, topsoil, boulders, building rubble etc in fill.
ROCK OUTCROPS & BOULDERS		Remove or stabilise boulders which may have unacceptable risk. Support rock faces where necessary.	Disturb or undercut detached blocks or boulders.
RETAINING WALLS		Engineer design to resist applied soil and water forces. Found on rock where practicable. Provide subsurface drainage within wall backfill and surface drainage on slope above. Construct wall as soon as possible after cut/fill operation.	Construct a structurally inadequate wall such as sandstone flagging, brick or unreinforced blockwork. Lack of subsurface drains and weepholes.
FOOTINGS		Found within rock where practicable. Use rows of piers or strip footings oriented up and down slope. Design for lateral creep pressures if necessary. Backfill footing excavations to exclude ingress of surface water.	Found on topsoil, loose fill, detached boulders or undercut cliffs.
SWIMMING POOLS		Engineer designed. Support on piers to rock where practicable. Provide with under-drainage and gravity drain outlet where practicable. Design for high soil pressures which may develop on uphill side whilst there may be little or no lateral support on downhill side.	
DRAINAGE SURFACE		Provide at tops of cut and fill slopes. Discharge to street drainage or natural water courses. Provide general falls to prevent blockage by siltation and incorporate silt traps. Line to minimise infiltration and make flexible where possible. Special structures to dissipate energy at changes of slope and/or direction.	Discharge at top of fills and cuts. Allow water to pond on bench areas.
SUBSURFACE		Provide filter around subsurface drain. Provide drain behind retaining walls. Use flexible pipelines with access for maintenance. Prevent inflow of surface water.	Discharge roof runoff into absorption trenches.
SEPTIC & SULLAGE		Usually requires pump-out or mains sewer systems; absorption trenches may be possible in some areas if risk is acceptable. Storage tanks should be water-tight and adequately founded.	Discharge sullage directly onto and into slopes. Use absorption trenches without consideration of landslide risk.
EROSION CONTROL & LANDSCAPING		Control erosion as this may lead to instability. Revegetate cleared area.	Failure to observe earthworks and drainage recommendations when landscaping.
DRAWINGS AND SITE VISITS DURING CONSTRUCTION			
DRAWINGS		Building Application drawings should be viewed by geotechnical consultant	
SITE VISITS		Site Visits by consultant may be appropriate during construction/	
INSPECTION AND MAINTENANCE BY OWNER			
OWNER'S RESPONSIBILITY		Clean drainage systems; repair broken joints in drains and leaks in supply pipes. Where structural distress is evident see advice. If seepage observed, determine causes or seek advice on consequences.	

EXAMPLES OF **GOOD** HILLSIDE PRACTICE



EXAMPLES OF **POOR** HILLSIDE PRACTICE



APPENDIX C

FORM 1 & 1A

GEOTECHNICAL RISK MANAGEMENT POLICY FOR PITTWATER
FORM NO. 1 – To be submitted with Development Application

Development Application for _____

Name of Applicant

Address of site 56 Central Road, Avalon Beach

Declaration made by geotechnical engineer or engineering geologist or coastal engineer (where applicable) as part of a geotechnical report

I, Matthew Green on behalf of Green Geotechnics Pty Ltd
(Insert Name) (Trading or Company Name)

on this the 15 November 2022 certify that I am a geotechnical engineer or engineering geologist or coastal engineer as defined by the Geotechnical Risk Management Policy for Pittwater - 2009 and I am authorised by the above organisation/company to issue this document and to certify that the organisation/company has a current professional indemnity policy of at least ~~\$40 million~~ \$5,000,000.00

I:
Please mark appropriate box

- ☒ have prepared the detailed Geotechnical Report referenced below in accordance with the Australia Geomechanics Society's Landslide Risk Management Guidelines (AGS 2007) and the Geotechnical Risk Management Policy for Pittwater - 2009
- ☐ am willing to technically verify that the detailed Geotechnical Report referenced below has been prepared in accordance with the Australian Geomechanics Society's Landslide Risk Management Guidelines (AGS 2007) and the Geotechnical Risk Management Policy for Pittwater - 2009
- ☒ have examined the site and the proposed development in detail and have carried out a risk assessment in accordance with Section 6.0 of the Geotechnical Risk Management Policy for Pittwater - 2009. I confirm that the results of the risk assessment for the proposed development are in compliance with the Geotechnical Risk Management Policy for Pittwater - 2009 and further detailed geotechnical reporting is not required for the subject site.
- ☐ have examined the site and the proposed development/alteration in detail and I am of the opinion that the Development Application only involves Minor Development/Alteration that does not require a Geotechnical Report or Risk Assessment and hence my Report is in accordance with the Geotechnical Risk Management Policy for Pittwater - 2009 requirements.
- ☐ have examined the site and the proposed development/alteration is separate from and is not affected by a Geotechnical Hazard and does not require a Geotechnical Report or Risk Assessment and hence my Report is in accordance with the Geotechnical Risk Management Policy for Pittwater - 2009 requirements.
- ☐ have provided the coastal process and coastal forces analysis for inclusion in the Geotechnical Report

Geotechnical Report Details:

Report Title: Geotechnical Investigation - 56 Central Road, Avalon Beach

Report Date: 15 November 2022

Author: Matthew Green

Author's Company/Organisation: Green Geotechnics Pty Ltd

Documentation which relate to or are relied upon in report preparation:

Architectural Drawings by Granny Flat Solutions - Project Number 220296, Dated 1 November 2022, Rev A

Site Survey Prepared by NSW Land Services, Proj No. 9962, Dated 18/08/2022

I am aware that the above Geotechnical Report, prepared for the abovementioned site is to be submitted in support of a Development Application for this site and will be relied on by Pittwater Council as the basis for ensuring that the Geotechnical Risk Management aspects of the proposed development have been adequately addressed to achieve an "Acceptable Risk Management" level for the life of the structure, taken as at least 100 years unless otherwise stated and justified in the Report and that reasonable and practical measures have been identified to remove foreseeable risk.

Signature . 

Name Matthew Green

Chartered Professional Status RPGeo

Membership No. 10276

Company Green Geotechnics Pty Ltd

GEOTECHNICAL RISK MANAGEMENT POLICY FOR PITTWATER
FORM NO. 1(a) - Checklist of Requirements For Geotechnical Risk Management Report for
Development Application

Development Application for _____
 Address of site 56 Central Road, Avalon Beach Name of Applicant _____

The following checklist covers the minimum requirements to be addressed in a Geotechnical Risk Management Geotechnical Report. This checklist is to accompany the Geotechnical Report and its certification (Form No. 1).

Geotechnical Report Details:

Report Title: **Geotechnical Investigation - 56 Central Road, Avalon Beach**
 Report Date: **15 November 2022**
 Author: **Matthew Green**
 Author's Company/Organisation: **Green Geotechnics Pty Ltd**

Please mark appropriate box

- ☒ Comprehensive site mapping conducted 10/11/22
 (date)
- ☒ Mapping details presented on contoured site plan with geomorphic mapping to a minimum scale of 1:200 (as appropriate)
- ☒ Subsurface investigation required
 ☐ No Justification
- ☒ ☐ Yes Date conducted 10/11/22
- ☒ Geotechnical model developed and reported as an inferred subsurface type-section
- ☒ Geotechnical hazards identified
 ☐ Above the site
 ☒ On the site
 ☐ Below the site
 ☐ Beside the site
- ☒ Geotechnical hazards described and reported
- ☒ Risk assessment conducted in accordance with the Geotechnical Risk Management Policy for Pittwater - 2009
 ☐ Consequence analysis
 ☐ Frequency analysis
- ☒ Risk calculation
- ☒ Risk assessment for property conducted in accordance with the Geotechnical Risk Management Policy for Pittwater - 2009
- ☒ Risk assessment for loss of life conducted in accordance with the Geotechnical Risk Management Policy for Pittwater - 2009
- ☒ Assessed risks have been compared to "Acceptable Risk Management" criteria as defined in the Geotechnical Risk Management Policy for Pittwater - 2009
- ☒ Opinion has been provided that the design can achieve the "Acceptable Risk Management" criteria provided that the specified conditions are achieved.
- ☒ Design Life Adopted: ☒ 100 years
 ☐ Other specify
- ☒ Geotechnical Conditions to be applied to all four phases as described in the Geotechnical Risk Management Policy for Pittwater - 2009 have been specified
- ☒ Additional action to remove risk where reasonable and practical have been identified and included in the report.
- ☐ Risk assessment within Bushfire Asset Protection Zone.

I am aware that Pittwater Council will rely on the Geotechnical Report, to which this checklist applies, as the basis for ensuring that the geotechnical risk management aspects of the proposal have been adequately addressed to achieve an "Acceptable Risk Management" level for the life of the structure, taken as at least 100 years unless otherwise stated, and justified in the Report and that reasonable and practical measures have been identified to remove foreseeable risk.

Signature  _____
 Name Matthew Green _____
 Chartered Professional Status RPGeo _____
 Membership No. 10276 _____
 Company Green Geotechnics Pty Ltd _____