

# **Landscape Referral Response**

| Application Number:             | DA2022/1128  |
|---------------------------------|--|
| Date:                           | 31/01/2023   |
| Proposed Development:           | Partial demolition of the existing dwelling and construction of<br>a new dwelling including retention of substantial portions of<br>the existing dwelling and a detached secondary dwelling over<br>a garage together with a swimming pool |
| Responsible Officer:            | Stephanie Gelder   |
| Land to be developed (Address): | Lot 12 DP 829988, 38 The Drive FRESHWATER NSW 2096   |

#### Reasons for referral

This application seeks consent for the following:

- Construction / development works within 5 metres of a tree or
- New residential works with three or more dwellings. (RFB's, townhouses, seniors living, questhouses, etc). or
- Mixed use developments containing three or more residential dwellings.
- New Dwellings or

#### Officer comments

The proposal is supported with regard to landscape issues.

#### Additional Information Comment 31/01/23:

The amended plans are noted.

The Landscape Plan has not been updated and as such it shall be coordinated with the amended architectural drawings prior to issuing a Construction Certificate.

#### **Original Comment:**

An Arboricultural Impact Assessment (AIA) and Landscape Plan is included in the application and will be assessed as part of the Landscape Referral. No significant trees are proposed to be removed; however, the works will impact trees outside the property boundary which are required to be retained and protected. Landscape Referral supports the recommendations in the AIA for tree protection, and a Project Arborist shall be engaged to supervise all works within tree protection zones of trees to be retained and as recommended in the AIA, subject to the imposed conditions. The Stormwater Management Plan shows new connections to the road in close proximity to existing tree 2, and should trenching be required it shall be under the advice and supervision of the Project Arborist.

As required under DCP control E6 all rock outcrops outside the excavation zone shall be retained and protected, including rock outcrops that will remain under suspended elements of the proposal. Conditions shall be imposed for the retention of these significant environmental features to ensure unnecessary removal is avoided.

Some low vegetation will be required to be removed to facilitate the works; however, the landscape proposal will re-establish significant planting areas which will help to satisfy DCP control D1. The landscape area between the garage and the dwelling is an important zone to help reduce the visual

DA2022/1128 Page 1 of 6



bulk and scale of the proposal, therefore an additional tree shall be planted, subject to the imposed conditions. If any vegetation shown to be retained is damaged or removed during construction it shall be replaced with a like-for-like substitute to ensure the existing character is maintained. The planting in the raised planter above the garage shall reach a minimum height of 1.2 metres, as outlined in the conditions of consent. Furthermore, all on slab landscaping shall meet the soil depth requirements outlined in the conditions of consent.

Minor works are proposed in the road reserve and as such the appropriate referral body shall determine this matter.

The proposal is therefore supported.

Note: Should you have any concerns with the referral comments above, please discuss these with the Responsible Officer.

## **Recommended Landscape Conditions:**

# CONDITIONS TO BE SATISFIED PRIOR TO THE ISSUE OF THE CONSTRUCTION CERTIFICATE

## **Amended Landscape Plan**

An Amended Landscape Plan shall be issued to the Principal Certifier prior to the issue of a Construction Certificate to include the following details:

i) coordinate the landscape plan with the latest architectural plans.

Certification shall be provided to the Principal Certifier that these amendments have been documented.

Reason: Landscape amenity.

### On Slab Landscape Works

Details shall be submitted to the Certifying Authority prior to the issue of the Construction Certificate indicating the proposed method of waterproofing and drainage to all planters over slab, over which soil and planting is being provided.

Landscape treatment details shall be submitted to the Certifying Authority prior to the issue of the Construction Certificate indicating the proposed soil type, planting, automatic irrigation, services connections, and maintenance activity schedule.

The following soil depths are required to support landscaping as proposed:

- i) 300mm for groundcovers or native grasses,
- ii) 600mm for shrubs.

Design certification shall be submitted to the Certifying Authority by a qualified Structural Engineer, that the planters are designed structurally to support the 'wet' weight of landscaping (soil, materials and established planting).

Reason: To ensure appropriate soil depth for planting and secure waterproofing and drainage is installed.

# CONDITIONS THAT MUST BE ADDRESSED PRIOR TO ANY COMMENCEMENT

# **Project Arborist**

A Project Arborist with minimum AQF Level 5 in arboriculture shall be engaged to provide tree

DA2022/1128 Page 2 of 6



protection measures in accordance with Australian Standard 4970-2009 Protection of Trees on Development Sites, and the recommendations of the Arboricultural Impact Assessment.

The Project Arborist shall be in attendance and supervise all works as nominated in the Arboricultural Impact Assessment, and in particular:

- i) tree protection measures under section 8 Recommendations and Section 9 Tree Protection Specification,
- ii) works under section 8 Recommendations and any stormwater work in tree protection zones,
- iii) additionally, the Project Arborist shall be in attendance and supervise any landscaping works within the TPZ of all existing trees to be retained.

Existing ground levels shall be maintained within the tree protection zone of trees to be retained, unless authorised by the Project Arborist.

All tree protection measures specified must:

- a) be in place before work commences on the site, and
- b) be maintained in good condition during the construction period, and
- c) remain in place for the duration of the construction works.

The Project Arborist shall provide certification to the Certifying Authority that all recommendations listed for the protection of the existing tree(s) have been carried out satisfactorily to ensure no impact to the health of the tree(s). Photographic documentation of the condition of all trees to be retained shall be recorded, including at commencement, during the works and at completion.

#### Note:

- i) A separate permit or development consent may be required if the branches or roots of a protected tree on the site or on an adjoining site are required to be pruned or removed.
- ii) Any potential impact to trees as assessed by the Project Arborist will require redesign of any approved component to ensure existing trees upon the subject site and adjoining properties are preserved and shall be the subject of a modification application where applicable.

Reason: Tree protection.

# CONDITIONS TO BE COMPLIED WITH DURING DEMOLITION AND BUILDING WORK

#### **Protection of Rock and Sites of Significance**

All rock outcrops outside of the area of approved works are to be preserved and protected at all times during demolition excavation and construction works.

Should any Aboriginal sites be uncovered during the carrying out of works, those works are to cease and Council, the NSW Office of Environment and Heritage (OEH) and the Metropolitan Local Aboriginal Land Council are to be contacted.

Reason: Preservation of significant environmental features.

#### **Protection of Existing Street Trees**

All existing street trees in the vicinity of the works shall be retained during all construction stages, and the street tree fronting the development site shall be protected by tree protection fencing in accordance with Section 4 of Australian Standard 4970-2009 Protection of Trees on Development Sites.

All street trees within the road verge are protected under Northern Beaches Council development control plans, except where Council's written consent for removal has been obtained. The felling, lopping, topping, ringbarking, or removal of any tree(s) is prohibited.

DA2022/1128 Page 3 of 6



No excavated material, building material storage, site facilities, nor landscape materials are to be placed within the canopy dripline of street trees.

Should any problems arise with regard to the existing or proposed trees on public land during construction, Council's Tree Services section is to be contacted immediately to resolve the matter to Council's satisfaction and at the cost of the applicant.

Reason: Street tree protection.

# Tree and Vegetation Protection

- a) Existing trees and vegetation shall be retained and protected, including:
- i) all trees and vegetation within the site, excluding exempt trees and vegetation under the relevant planning instruments of legislation,
- ii) all trees and vegetation located on adjoining properties,
- iii) all road reserve trees and vegetation.
- b) Tree protection shall be undertaken as follows:
- i) tree protection shall be in accordance with Australian Standard 4970-2009 Protection of Trees on Development Sites, including the provision of temporary fencing to protect existing trees within 5 metres of development,
- ii) existing ground levels shall be maintained within the tree protection zone of trees to be retained, unless authorised by an Arborist with minimum AQF Level 5 in arboriculture,
- iii) removal of existing tree roots at or >25mm (Ø) diameter is not permitted without consultation with an Arborist with minimum AQF Level 5 in arboriculture,
- iv) no excavated material, building material storage, site facilities, nor landscape materials are to be placed within the canopy dripline of trees and other vegetation required to be retained,
- v) structures are to bridge tree roots at or >25mm ( $\emptyset$ ) diameter unless directed by an Arborist with minimum AQF Level 5 in arboriculture on site,
- vi) excavation for stormwater lines and all other utility services is not permitted within the tree protection zone, without consultation with an Arborist with minimum AQF Level 5 in arboriculture including advice on root protection measures.
- vii) should either or all of v) or vi) occur during site establishment and construction works, an Arborist with minimum AQF Level 5 in arboriculture shall provide recommendations for tree protection measures. Details including photographic evidence of works undertaken shall be submitted by the Arborist to the Certifying Authority,
- viii) any temporary access to, or location of scaffolding within the tree protection zone of a protected tree or any other tree to be retained during the construction works is to be undertaken using the protection measures specified in sections 4.5.3 and 4.5.6 of Australian Standard 4970-2009 Protection of Trees on Development Sites,
- ix) tree pruning from within the site to enable approved works shall not exceed 10% of any tree canopy, and shall be in accordance with Australian Standard 4373-2007 Pruning of Amenity Trees, and should additional pruning be required an application to Council's Tree Services shall be submitted for approval or otherwise.

# The Certifying Authority must ensure that:

c) The activities listed in section 4.2 of Australian Standard 4970-2009 Protection of Trees on Development Sites, do not occur within the tree protection zone of any tree, and any temporary access to, or location of scaffolding within the tree protection zone of a protected tree, or any other tree to be retained on the site during the construction, is undertaken using the protection measures specified in sections 4.5.3 and 4.5.6 of that standard.

Reason: Tree and vegetation protection.

DA2022/1128 Page 4 of 6



#### **Condition of Trees**

During the construction period the applicant is responsible for ensuring all existing trees required to be retained are maintained in a healthy and vigorous condition. This is to be done by ensuring that all identified tree protection measures are adhered to, or by seeking arboricultural advice from the Project Arborist during the works. In this regard all protected trees shall not exhibit:

- i) a general decline in health and vigour,
- ii) damaged, crushed or dying roots due to poor pruning techniques,
- iii) more than 10% loss or dieback of roots, branches and foliage,
- iv) mechanical damage or bruising of bark and timber of roots, trunk and branches,
- v) yellowing of foliage or a thinning of the canopy untypical of its species,
- vi) an increase in the amount of deadwood not associated with normal growth,
- vii) an increase in kino or gum exudation,
- viii) inappropriate increases in epicormic growth that may indicate that the plants are in a stressed condition.
- ix) branch drop, torn branches and stripped bark not associated with natural climatic conditions.

Any mitigating measures and recommendations required by the Project Arborist are to be implemented.

The owner of the adjoining allotment of land is not liable for the cost of work carried out for the purpose of this clause.

Reason: Protection of trees.

# CONDITIONS WHICH MUST BE COMPLIED WITH PRIOR TO THE ISSUE OF THE OCCUPATION CERTIFICATE

### **Landscape Completion**

Landscaping is to be implemented in accordance with the approved Landscape Plan (drawing L-02 by Space Landscape Designs dated 16/05/22), and inclusive of the following conditions:

- i) install one (1) additional *Banksia integrifolia* between the garage and the dwelling, in the area between the existing path (to be retained) and the new stair adjacent to the proposed store,
- ii) substitute all *Rhaphiolepis* species with a suitable alternative (although a cultivar is proposed, *Rhaphiolepis* species are considered an environmental weed),
- iii) substitute *Westringia fruticosa* 'Aussie Box' in the planter above the garage with a suitable alternative that can reach a mature height of at least 1.2 metres,
- iv) all tree planting shall be a minimum planting size of 75 litres, and shall meet the requirements of Natspec Specifying Trees,
- v) all trees shall be planted into a prepared planting hole 1m x 1m x 600mm depth, backfilled with a sandy loam mix or approved similar, mulched to 75mm depth minimum and maintained, and watered until established, and shall be located at least 3.0 metres from buildings, and at least 1.5 metres from common boundaries, and located either within garden bed or within a prepared bed within lawn,
- vi) mass planting shall be installed at minimum 1 plant per metre square for shrubs of a minimum 200mm container size at planting or as otherwise scheduled if greater in size, and at least 4 plants per metre square for grasses/groundcovers of a minimum 140mm container size at planting or as otherwise scheduled if greater in size, and shall be in a garden bed prepared with a suitable free draining soil mix and minimum 50mm depth of mulch.
- vii) all proposed tree planting shall be positioned in locations to minimise significant impacts on neighbours in terms of blocking winter sunlight to living rooms, private open space and where the proposed location of trees may otherwise be positioned to minimise any significant loss of views from neighbouring and nearby dwellings and from public spaces,
- viii) should any vegetation shown to be retained be damaged or removed during construction, it shall be

DA2022/1128 Page 5 of 6



replaced with a like-for-like substitute.

Prior to the issue of an Occupation Certificate, details from a landscape architect or landscape designer shall be submitted to the Certifying Authority, certifying that the landscape works have been completed in accordance with any conditions of consent.

Reason: Environmental amenity.

## **Condition of Retained Vegetation - Project Arborist**

Prior to the issue of an Occupation Certificate, a report prepared by the Project Arborist shall be submitted to the Certifying Authority, assessing the health and impact on all existing trees required to be retained, including the following information:

- i) compliance to any Arborist recommendations for tree protection generally and during excavation works.
- ii) extent of damage sustained by vegetation as a result of the construction works,
- iii) any subsequent remedial works required to ensure the long term retention of the vegetation.

Reason: Tree protection.

# ON-GOING CONDITIONS THAT MUST BE COMPLIED WITH AT ALL TIMES

## **Landscape Maintenance**

If any landscape materials/components or planting under this consent fails, they are to be replaced with similar materials/components. Trees, shrubs and groundcovers required to be planted under this consent are to be mulched, watered and fertilised as required at the time of planting.

If any tree, shrub or groundcover required to be planted under this consent fails, they are to be replaced with similar species to maintain the landscape theme and be generally in accordance with the approved amended Landscape Plan and any conditions of consent.

The approved landscaped areas as shown on Landscaping Proposed (drawing DA27 by Northern Beaches Designs dated 27/01/23) shall remain as planting.

All weeds are to be managed in accordance with the NSW Biosecurity Act 2015.

Reason: To maintain local environmental amenity.

DA2022/1128 Page 6 of 6