

J5617B 4th July, 2025 Page 1.

2131 Pittwater Road, Church Point

Geotechnical Comments for Section 4.55 Plans

We have reviewed the existing geotechnical report, the original plans, and the 15 amended plans by CHROFI, project 25002, drawings numbered DA501, revision 01. DA000 to 001, DA 100 to 103, DA200 to 201, DA300 to 301, DA400, DA500, and DA502 to 503, revision 03. All dated 24/06/2025.

The changes are as follows:

- Move the lower ground floor excavation further SW with no significant change in excavation depth.
- Rotate the proposed pool 90°.
- Internal and external alterations to the house layout, increasing the number of existing walls and slabs to be demolished.

The changes are considered minor from a geotechnical perspective. Increasing the amount of demolition of existing walls on the ground floor level decreases the amount of underpinning required, reducing the overall complexity and risk of the project. The changes do not alter the recommendations or the risk assessment in the original report carried out by this firm numbered J5617 and dated the 31st October, 2024.

White Geotechnical Group Pty Ltd.

Whardner

Reviewed By:

Nathan Gardner B.Sc. (Geol. & Geophys. & Env. Stud.)
AIG., RPGeo Geotechnical & Engineering.

No. 10307

Engineering Geologist & Environmental Scientist.

Ben White M.Sc. Geol.,

Fellet

AIG., RPGeo Geotechnical & Engineering.

No. 10306

Engineering Geologist.



GEOTECHNICAL RISK MANAGEMENT POLICY FOR PITTWATER FORM NO. 1 – To be submitted with Development Application

Develo	opment Application	for	Name of Applicant	
		0404 PM		
Addre	ss of site	2131 Pittwater R	Road, Church Point	
			uirements to be addressed in a Geotechnical Risk Declaration made b gist or coastal engineer (where applicable) as part of a geotechnica	
I,	Ben White	on behalf of ${f V}$	White Geotechnical Group Pty Ltd	
	(Insert Name)		(Trading or Company Name)	
organisa	engineer as defined l	1/10/24 by the Geotechnical Rule this document and	certify that I am a geotechnical engineer or engineering geon I Risk Management Policy for Pittwater - 2009 and I am authorised by the not to certify that the organisation/company has a current professional in	ne above
l: Please i	mark appropriate bo	υx		
			nical Report referenced below in accordance with the Australia Geometric Guidelines (AGS 2007) and the Geotechnical Risk Management P	
\boxtimes	accordance with th		the detailed Geotechnical Report referenced below has been prepechanics Society's Landslide Risk Management Guidelines (AGS 2007) v for Pittwater - 2009	
	have examined the with Section 6.0 of assessment for the	site and the propose the Geotechnical Ris e proposed developr	sed development in detail and have carried out a risk assessment in acc Risk Management Policy for Pittwater - 2009. I confirm that the results of spment are in compliance with the Geotechnical Risk Management P leotechnical reporting is not required for the subject site.	f the risk
	have examined the Application only i	site and the propose nvolves Minor Deve	sed development/alteration in detail and I am of the opinion that the Deve velopment/Alteration that does not require a Geotechnical Report n accordance with the Geotechnical Risk Management Policy for Pittwate	or Risk
	have examined the Hazard and does r	not require a Geotech	sed development/alteration is separate from and is not affected by a Geot chnical Report or Risk Assessment and hence my Report is in accorda	
		•	Policy for Pittwater - 2009 requirements. d coastal forces analysis for inclusion in the Geotechnical Report	
Geotecl	nnical Report Detail	s:		
			1 Pittwater Road, Church Point	
	Report Date: 31/10)/24		
	Author: BEN WHI	ΓΕ		
	Author's Company/	Organisation: White	ite Geotechnical Group Pty Ltd	
Docume	entation which relat	e to or are relied up	upon in report preparation:	
	Australian Geo	mechanics Soc	ociety Landslide Risk Management March 2007.	
	White Geotec	hnical Group co	company archives.	

I am aware that the above Geotechnical Report, prepared for the abovementioned site is to be submitted in support of a Development Application for this site and will be relied on by Pittwater Council as the basis for ensuring that the Geotechnical Risk Management aspects of the proposed development have been adequately addressed to achieve an "Acceptable Risk Management" level for the life of the structure, taken as at least 100 years unless otherwise stated and justified in the Report and that reasonable and practical measures have been identified to remove foreseeable risk.

Signature

Name
Ben White

Chartered Professional Status
MScGEOL AIG., RPGeo

Membership No.
10306

Company
White Geotechnical Group Pty Ltd



GEOTECHNICAL RISK MANAGEMENT POLICY FOR PITTWATER FORM NO. 1(a) - Checklist of Requirements for Geotechnical Risk Management Report for Development Application

			Developme	nt Applicatio	n	
Deve	lopment Application f	or	NI	of Americans		
			iname	of Applicant		
Addr	ess of site	2131 Pittwa	ter Road, Ch	urch Point		
	llowing checklist covers This checklist is to acc					Risk Management Geotechnical o. 1).
	chnical Report Details					
	rt Title: Geotechnical R	eport 2131 Pitt	water Road, (Church Point		
'	rt Date: 31/10/24					
Autho	or: BEN WHITE					
Auth	or's Company/Organis	sation: White	Geotechni	cal Group P	Pty Ltd	
Please	mark appropriate box	ĸ				
	Comprehensive site r	napping conducte	ed <u>1/8/24</u> (date)			
\boxtimes	Mapping details prese Subsurface investigat ☐ No		(/	geomorphic mappii	ng to a minimu	um scale of 1:200 (as appropriate)
	☑ Yes Geotechnical model of Geotechnical hazards ☑ Above t □ On the ☑ Below t	Date conducted developed and rep is identified the site site		rred subsurface typ	pe-section	
\boxtimes		s described and re	•	otechnical Risk Ma	inagement Po	licy for Pittwater - 2009
	· · · · · · · · · · · · · · · · · · ·	ncy analysis				
	Risk assessment for I Assessed risks have Management Policy for	loss of life conduct been compared to or Pittwater - 200	cted in accordanc o "Acceptable Ris 9	e with the Geotech	nnical Risk Ma riteria as defin	agement Policy for Pittwater - 2009 inagement Policy for Pittwater - 2009 ed in the Geotechnical Risk ent" criteria provided that the
	specified conditions a Design Life Adopted: ☐ 100 yea ☐ Other _	ars	-16			
	Geotechnical Condition	ons to be applied	ecify to all four phases	s as described in th	ne Geotechnic	al Risk Management Policy for
		emove risk where			n identified an	d included in the report.
that the Manag	e geotechnical risk mana	agement aspects of the structure	s of the proposa e, taken as at lea	l have been adequast 100 years unl	uately addres ess otherwise	st applies, as the basis for ensuring sed to achieve an "Acceptable Risk e stated, and justified in the Report.
	- B	Elit				FESSION
	Signature					AUSTRALIAN C
	Name			Ben White		INSTITUTE OF GEOSCIENTISTS BENJAMIN WHITE
	Chartered Professiona	l Status	MScGEOL	AIG., RPGeo	\	H DENSAME THE

222757

White Geotechnical Group Pty Ltd

Membership No.

Company



J5617.

31st October, 2024.

Page 1.

GEOTECHNICAL INVESTIGATION:

Additions and Alterations and New Pool at 2131 Pittwater Road, Church Point

1. Proposed Development

- **1.1** Demolish most of the existing internal and external walls of the house.
- **1.2** Extend the lower ground floor of the house upslope and install a lift by excavating to a maximum depth of ~2.8m.
- **1.3** Extend the ground floor of the house to the NW by excavating to a maximum depth of ~1.7m.
- **1.4** Demolish the existing pool and install a new pool in the same location.
- **1.5** Minor internal and external alterations and additions.
- **1.6** Details of the proposed development are shown on 24 drawings prepared by Archisoul Architects, project 2251, drawings numbered DA01 to DA24, dated 28.10.2024.

2. Site Description

- **2.1** The site was inspected on the 1st August, 2024.
- 2.2 This residential property is on the high side of the road and has a NE aspect. It is located on the gentle to moderately graded lower reaches of a hillslope. The natural slope rises across the property at an average angle of ~9°. The slope above the property continues at moderate angles. The slope below the property eases to near level angles at the waterfront.
- 2.3 At the road frontage, a concrete ROW (Right of Carriageway) and driveway run to a garage under the downhill side of the house (Photo 1). Fill for the driveway and garden bedding between the road frontage (Photo 2) and the house is supported by a



J5617.

31st October, 2024.

Page 2.

stable rendered masonry retaining wall (Photo 3) which approximates the downhill and SE boundaries. The part two-story house is supported on rendered masonry walls. Horizontal hairline cracking in the rendering was observed in some of the supporting walls. This minor cracking is not attributed to foundation movement. The house foundations are currently considered stable. Most of the supporting walls of the house will be demolished as part of the proposed works. A stable pool (Photo 4) and tiled patio occupies the space between the upper and lower portions of the house. The pool will also be demolished as part of the proposed works. The cut for the patio is supported by a stable rendered masonry retaining wall reaching ~1.5m high (Photo 5). Above the house a cut for level garden bedding is supported by a stable low sandstone block retaining wall which approximates the uphill common boundary (Photo 6).

3. Geology

The Sydney 1:100 000 Geological Sheet indicates the contact of Hawkesbury Sandstone and the Narrabeen Group Rocks cuts through the middle of the property, although at a residential scale the map is not always accurate. Ground testing and observations on site indicate that the property is underlain by geology which is consistent with the Narrabeen Group. The Narrabeen Group of Rocks are described as interbedded laminite, shale, and quartz to lithic quartz sandstone.

4. Subsurface Investigation

Two hand Auger Holes (AH) were put down to identify the soil materials. Four Dynamic Cone Penetrometer (DCP) tests were put down to determine the relative density of the overlying sand and the depth to weathered rock. The locations of the tests are shown on the site plan attached. It should be noted that a level of caution should be applied when interpreting DCP test results. The test will not pass through hard buried objects so in some instances it can be difficult to determine whether refusal has occurred on an obstruction in the profile or on the natural rock surface. This is not expected to have been an issue for this site. But due to the possibility that the actual ground conditions vary from our interpretation there should be



J5617. 31st October, 2024. Page 3.

allowances in the excavation and foundation budget to account for this. We refer to the appended "Important Information about Your Report" to further clarify. The results are as follows:

AUGER HOLE 1 (~RL3.8) – AH1 (Photo 7)

Depth (m)	Material Encountered
0.0 to 0.1	FILL, dark brown, Medium Dense, damp, medium grained
0.1 to 0.4	CLAYEY FILL, brown, Soft, damp, fine to medium grained, clay
	fragments included.
0.4 to 0.7	CLAYEY SANDY SOIL, dark brown, Soft, damp, fine to medium grained.
0.7 to 1.2	CLAYEY SAND, brown to light brown, Medium Dense to Dense, damp,
	fine to medium grained.
1.2 to 1.5	CLAY, mottled maroon, orange, yellow, grey, Very Stiff, damp, charcoal
	inclusions.
1.5 to 1.7	CLAY, derived from weathered shale, mottled orange and grey, Stiff,
	damp.

End of test @ 1.7m in clay derived from weathered shale. No water table encountered.

AUGER HOLE 2 (~RL8.5) - AH2 (Photo 8)

Depth (m)	Material Encountered
0.0 to 0.2	FILL, brown, Dense, dry, fine to medium grained.
0.2 to 0.4	CLAY, mottled orange and grey, Hard, dry, fine to medium grained, soil
	lenses present.
0.4 to 0.6	SANDY CLAY, derived from weathered shale, mottled maroon, orange,
	and grey, Hard, dry, fine to medium grained.

End of test @ 0.6m in clay derived from weathered shale. No water table encountered.

DCP TEST RESULTS ON THE NEXT PAGE



J5617. 31st October, 2024. Page 4.

	DCP TEST RESUL	TS – Dynamic Co	ne Penetrometer	
Equipment: 9kg han	nmer, 510mm drop, coi	nical tip.	Standard:	AS1289.6.3.2 - 1997
Depth(m)	DCP 1	DCP 2	DCP 3	DCP 4
Blows/0.3m	(~RL3.6)	(~RL3.8)	(~RL8.5)	(~RL8.5)
0.0 to 0.3	3	3	8	18
0.3 to 0.6	13	7	8	31
0.6 to 0.9	17	12	24	43
0.9 to 1.2	7	19	22	#
1.2 to 1.5	9	17	30	
1.5 to 1.8	8	15	#	
1.8 to 2.1	5	12		
2.1 to 2.4	12	15		
2.4 to 2.7	22	36		
2.7 to 3.0	12	38		
3.0 to 3.3	17	#		
3.3 to 3.6	20			
3.6 to 3.9	25			
3.9 to 4.2	32			
4.2 to 4.5	#			
	End of Test @ 4.2m	End of Test @ 3.0m	End of Test @ 1.3m	End of Test @ 0.7m

#refusal/end of test. F=DCP fell after being struck showing little resistance through all or part of the interval.

DCP Notes:

DCP1 – End of test @ 4.2m, DCP still very slowly going down, grey sandy clay on wet tip and in collar above tip.

DCP2 – End of test @ 3.0m, DCP still very slowly going down, grey clay on damp tip, orange, maroon and yellow clay smeared up DCP rod.

DCP3 – End of test @ 1.3m, DCP thudding and still very slowly going down, clean dry tip.

DCP4 – End of test @ 0.7m, DCP thudding and still very slowly going down, clean dry tip.



J5617.

31st October, 2024.

Page 5.

5. Geological Observations/Interpretation

The natural slope materials are colluvial at the near surface and residual at depth. In the test

locations, the ground materials consist of younger sandy clay alluvial sediment at the downhill

boundary which overlies deep weathered clay. Filling has been placed across the property for

landscaping. The clays merge into the weathered zone of the underlying shale at depths of

between 2.4m to 3.9m below the current surface on the downhill side of the house, and

depths of 0.3m to 1.2m on the uphill side of the house. This variation in depth is due to the

fills and sediment on the downhill side of the property, and cuts on the uphill side, as well as

a variable weathering profile. The weathered zone is interpreted as Extremely Low to Very

Low Strength Shale. It is to be noted that this material can appear as a mottled stiff clay when

it is cut up by excavation equipment. See Type Section attached for a diagrammatical

representation of the expected ground materials.

6. Groundwater

Normal ground water seepage is expected to move over the denser and less permeable clay

and weathered shale layers in the sub-surface profile. The water table was not encountered

in AH1 at ~1.7m (~RL2.1) but is expected to sit just above the waterline. As such, it is expected

to be at least 3.0m below the base of the proposed excavation. It should be noted the

watertable fluctuates with the tide and climatic changes.

7. Surface Water

No evidence of surface flows were observed on the property during the inspection. It is

expected that normal sheet wash will move onto the site from above the property during

heavy down pours.

8. Geotechnical Hazards and Risk Analysis

No geotechnical hazards were observed above, below, or beside the property. The

moderately graded slope that rises across the property is a potential hazard (Hazard One).

The proposed excavations are a potential hazard until retaining structures are in place



J5617. 31st October, 2024. Page 6.

(Hazard Two). The proposed excavations undercutting the walls of the house which are to remain, is a potential hazard (Hazard Three). The additional surcharge loads from the proposed works are a potential hazard to the existing retaining walls for the house (Hazard Four).

Risk Analysis Summary

HAZARDS	Hazard One	Hazard Two
TYPE	The moderate slope that rises	The excavations collapsing onto
	across the property failing and	the work site before retaining
	impacting on the proposed works.	structures are in place.
LIKELIHOOD	'Unlikely' (10 ⁻⁴)	'Possible' (10 ⁻³)
CONSEQUENCES TO PROPERTY	'Medium' (12%)	'Medium' (15%)
RISK TO PROPERTY	'Low' (2 x 10 ⁻⁵)	'Moderate' (2 x 10 ⁻⁴)
RISK TO LIFE	8.3 x 10 ⁻⁷ /annum	5.9 x 10 ⁻⁵ /annum
COMMENTS	This level of risk is 'ACCEPTABLE'.	This level of risk to life and property is 'UNACCEPTABLE'. To move risk to 'ACCEPTABLE' levels, the recommendations in Section 13 and 14 are to be followed.

(See Aust. Geomech. Jnl. Mar 2007 Vol. 42 No 1, for full explanation of terms)

RISK ANALYSIS SUMMARY CONTINUED ON THE NEXT PAGE



J5617. 31st October, 2024. Page 7.

HAZARDS	Hazard Three	Hazard Four
TYPE	The proposed excavations	The additional surcharge loads
	undercutting the walls of the	from the works transferring onto
	house (which are shown on the	the existing retaining walls which
	plans to remain) causing damage	support the cuts for the house
	or failure.	causing damage and instability.
LIKELIHOOD	'Possible' (10 ⁻³)	'Possible' (10 ⁻³)
CONSEQUENCES TO PROPERTY	'Medium' (15%)	'Medium' (20%)
RISK TO PROPERTY	'Moderate' (2 x 10 ⁻⁴)	'Moderate' (2 x 10 ⁻⁴)
RISK TO LIFE	5.3 x 10 ⁻⁵ /annum	5.6 x 10 ⁻⁵ /annum
COMMENTS	This level of risk to life and	This level of risk to life and
	property is 'UNACCEPTABLE'. To	property is 'UNACCEPTABLE'. To
	move risk to 'ACCEPTABLE' levels,	move the risk to 'ACCEPTABLE'
	the recommendations in Section	levels the recommendations in
	13 are to be followed.	Section 14 are to be followed.

(See Aust. Geomech. Jnl. Mar 2007 Vol. 42 No 1, for full explanation of terms)

9. Suitability of the Proposed Development for the Site

The proposed development is suitable for the site. No geotechnical hazards will be created by the completion of the proposed development provided it is carried out in accordance with the requirements of this report and good engineering and building practice.

10. Stormwater

The fall is to Pittwater Road. Roof water from the development is to be piped to the street drainage system through any tanks that may be required by the regulating authorities.

11. Excavations

Two excavations will be required for the proposed development:

 An excavation to a maximum depth of ~2.8m to extend the lower ground floor on the uphill side and install the proposed lift.



J5617.

31st October, 2024.

Page 8.

• An excavation to a maximum depth of ~1.7m to extend the ground floor of the house

to the NW.

The excavations are expected to be through fill, soil, clayey sand, and clay, with Extremely

Low to Very Low Strength Shale expected at depths of between ~0.3m and ~2.4m in the area

of the proposed excavations. It is envisaged that excavations through soil, clay, and Extremely

Low to Very Low Strength Shale can be carried out with an excavator and toothed bucket.

12. Vibrations

It is expected the proposed excavations will be carried out with an excavator and bucket and

the vibrations produced will be below the threshold limit for building or infrastructure

damage using a domestic sized excavator up to 16 tonnes.

13. Excavation Support Requirements

Allowing 0.5m for back wall drainage, the depths and setbacks for the proposed excavations

are as follows:

• The lower ground floor excavation will reach a maximum depth of ~2.8m and be set

back ~0.6m from the subject house walls.

The excavation to extend the ground floor of the house to the NW will reach a

maximum depth of ~1.7m and come ~flush with the subject house walls.

These supporting walls are shown on the plans to remain. As such, they will lie within the

Zone of Influence of the excavations. In this instance, the zone of influence is the area above

a theoretical 45° line (from horizontal) from the base of the excavation towards the

surrounding structures and boundaries. This line reduces to 30° through the fill and soil.

Following the demolition of any non-retaining structures, where any walls that are to remain

fall within the zone of influence of any excavations, exploration pits along the walls will need

to be put down by the builder to determine the foundation depth and material. These are to

be inspected by the geotechnical consultant.



J5617.

31st October, 2024.

Page 9.

If the foundations are confirmed to extend below the zone of influence of the proposed

excavation, the excavation may commence. If they are not, the walls will need to be

underpinned to below the zone of influence of the cut prior to the excavation commencing.

See the site plan attached for the minimum extent of the required exploration

pits/underpinning.

Underpinning is to follow the underpinning sequence 'hit one miss two'. Under no

circumstances is the bulk excavation to be taken to the edges of the walls and then

underpinned. Underpins are to be constructed from drives that should not exceed 0.6m in

width along strip footings and should be proportioned according to footing size for other

foundation types. Allowances are to be made for drainage through the underpinning to

prevent a build-up of hydrostatic pressure. Underpins that are not designed as retaining walls

are to be supported by retaining walls. The void between the retaining walls and the

underpinning is to be filled with free-draining material such as gravel.

The excavation requires the demolition of the retaining walls supporting the cut for the lower

ground floor of the house and cut for the NW patio on the uphill side (Photo 5). The walls are

to be demolished from the top down in an orderly manner with the ground material behind

the walls being systematically lowered at the same time. The batter slope is not to exceed 1.0

Vertical to 1.7 Horizontal (30°) as the walls are demolished.

The demolition of the existing pool is to be carried out in an orderly manner, this may involve

the underpinning of surrounding retaining walls as described above, during the demolition

process to ensure the integrity of the subject house and SE common boundary. The

geotechnical consultant is to be on site at the commencement of the pool demolition to

ensure any necessary underpinning of the surrounding walls are carried out.

Where room permits, the sides of the proposed excavation are also expected to stand

temporarily at batter angles of 30°. Where there is not room for these batters, the excavation

will need to be temporarily or permanently supported prior to the commencement of the

excavation, or during the excavation process in a staged manner, so cut batters are not left



J5617.

31st October, 2024.

Page 10.

unsupported. The support will need to be designed / approved by the structural engineer.

See the site plan attached for the minimum extent of the required shoring shown in blue.

During the excavation process, the geotechnical consultant is to inspect the cuts in 1.5m

intervals as they are lowered, while the machine/excavation equipment is on site, to ensure

the ground materials are as expected and the batter slope/temporary support is adequate.

All unsupported cut batters are to be covered to prevent access of water in wet weather and

loss of moisture in dry weather. The covers are to be tied down with metal pegs or other

suitable fixtures so they cannot blow off in a storm. The materials and labour to construct the

retaining walls are to be organised so on completion of the excavations they can be

constructed as soon as possible. The excavations are to be carried out during a dry period. No

excavations are to commence if heavy or prolonged rainfall is forecast.

All excavation spoil is to be removed from site following the current Environmental Protection

Agency (EPA) waste classification guidelines.

14. Retaining Structures

For cantilever or singly propped retaining structures it is suggested the design be based on a

triangular distribution of lateral pressures using the parameters shown in Table 1.

TABLE 1 ON THE NEXT PAGE



J5617. 31st October, 2024. Page 11.

Table 1 – Likely Earth Pressures for Retaining Structures

	Ea	rth Pressure Coefficien	ts
Unit	Unit weight (kN/m³)	'Active' Ka	'At Rest' K₀
Fill and Topsoil	20	0.40	0.55
Residual Clays	20	0.35	0.45
Extremely Low Strength Rock	22	0.25	0.38
Very Low Strength Rock	22	0.22	0.35

For rock classes refer to Pells et al "Design Loadings for Foundations on Shale and Sandstone in the Sydney Region". Australian Geomechanics Journal 1978.

It is to be noted that the earth pressures in Table 1 assume a level surface above the structure, do not account for any surcharge loads from the slope and assume retaining structures are fully drained. Rock strength and relevant earth pressure coefficients are to be confirmed on site by the geotechnical consultant.

All retaining structures are to have sufficient back-wall drainage and be backfilled immediately behind the structure with free draining material (such as gravel). This material is to be wrapped in a non-woven Geotextile fabric (i.e. Bidim A34 or similar), to prevent the drainage from becoming clogged with silt and clay. If no back-wall drainage is installed in retaining structures the full hydrostatic pressures are to be accounted for in the retaining structure design.

15. Foundations

The proposed additions and alterations to the house can be supported on Extremely Low to Very Low Strength Shale. This material is expected to be exposed across the uphill side of the proposed excavations. Where it is not exposed, and where weathered rock drops away with the slope, piers will be required to maintain a uniform foundation material across the



J5617.

31st October, 2024.

Page 12.

structure. To ensure no surcharge loads are added to the retaining walls supporting the

existing cuts for the house, where necessary, the works are to be supported on piers taken to

below the Zone of Influence of the walls.

The foundations supporting the existing house are currently unknown. Ideally, footings

should be founded on the same footing material across the old and new portions of the

structure. Where the footing material does change across the structure, construction joints

or similar are to be installed to prevent differential settlement, where the structure cannot

tolerate such movement in accordance with a 'Class M' site.

The proposed pool can also be supported on piers taken to the underlying Extremely Low to

Very Low Strength Shale. Extremely Low to Very Low Strength Shale is expected at depths of

between ~0.3m and ~2.4m below the current surface in the location of the proposed works.

A maximum allowable bearing pressure of 600kPa can be assumed for footings on Extremely

Low to Very Low Strength Shale. It should be noted that this material is a soft rock and a rock

auger will cut through it so the builders should not be looking for refusal to end the footings.

As the bearing capacity of clay and shale reduces when it is wet, we recommend the footings

be dug, inspected, and poured in quick succession (ideally the same day if possible). If the

footings get wet, they will have to be drained and the soft layer of wet clay or shale on the

footing surface will have to be removed before concrete is poured.

If a rapid turnaround from footing excavation to the concrete pour is not possible, a sealing

layer of concrete may be added to the footing surface after it has been cleaned and inspected

by the geotechnical consultant.

NOTE: If the contractor is unsure of the footing material required, it is more cost-effective to

get the geotechnical consultant on site at the start of the footing excavation to advise on

footing depth and material. This mostly prevents unnecessary over-excavation in clay-like

shaly-rock but can be valuable in all types of geology.



J5617.

31st October, 2024.

Page 13.

16. Geotechnical Review

The structural plans are to be checked and certified by the geotechnical engineer as being in

accordance with the geotechnical recommendations. On completion, a Form 2B will be

issued. This form is required for the Construction Certificate to proceed.

17. Inspections

The client and builder are to familiarise themselves with the following required inspections

as well as council geotechnical policy. We cannot provide certification for the Occupation

Certificate or the owner if the following inspections have not been carried out during the

construction process.

• The exploration pits to determine the foundation material along the walls that fall

within the Zone of Influence of the proposed excavations are to be inspected by the

geotechnical consultant to determine if underpinning is necessary. This is to occur

before the bulk excavations commence.

• The geotechnical consultant is to be on site at the commencement of the pool

demolition to ensure any necessary underpinning of the surrounding walls are carried

out.

During the excavation process, the geotechnical consultant is to inspect the cuts in

1.5m intervals as they are lowered, while the machine/excavation equipment is on

site, to ensure the ground materials are as expected and the batter slope/temporary

support is adequate.

• All footings are to be inspected and approved by the geotechnical consultant while

the excavation equipment and contractors are still onsite and before steel reinforcing

is placed or concrete is poured.



J5617.

31st October, 2024.

Page 14.

White Geotechnical Group Pty Ltd.

Reviewed By:

Nklardner

Nathan Gardner B.Sc. (Geol. & Geophys. & Env. Stud.) AIG., RPGeo Geotechnical & Engineering.

No. 10307

Engineering Geologist & Environmental Scientist.

Ben White M.Sc. Geol., AIG., RPGeo Geotechnical & Engineering. No. 10306






Photo 1



J5617. 31st October, 2024. Page 15.



Photo 2



Photo 3



J5617. 31st October, 2024. Page 16.



Photo 4



Photo 5



J5617. 31st October, 2024. Page 17.



Photo 6



J5617. 31st October, 2024. Page 18.



Photo 7 – AH1 – downhole is top to bottom



J5617. 31st October, 2024. Page 19.



Photo 8– AH2 – downhole is top to bottom



J5617. 31st October, 2024. Page 20.


Important Information about Your Report

It should be noted that Geotechnical Reports are documents that build a picture of the subsurface conditions from the observation of surface features and testing carried out at specific points on the site. The spacing and location of the test points can be limited by the location of existing structures on the site or by budget and time constraints of the client. Additionally, the test themselves, although chosen for their suitability for the particular project, have their own limiting factors. The testing gives accurate information at the location of the test, within the confines of the test's capability. A geological interpretation or model is developed by joining these test points using all available data and drawing on previous experience of the geotechnical consultant. Even the most experienced practitioners cannot determine every possible feature or change that may lie below the earth. All of the subsurface features can only be known when they are revealed by excavation. As such, a Geotechnical report can be considered an interpretive document. It is based on factual data but also on opinion and judgement that comes with a level of uncertainty. This information is provided to help explain the nature and limitations of your report.

With this in mind, the following points are to be noted:

- If upon the commencement of the works the subsurface ground or ground water conditions prove different from those described in this report, it is advisable to contact White Geotechnical Group immediately, as problems relating to the ground works phase of construction are far easier and less costly to overcome if they are addressed early.
- If this report is used by other professionals during the design or construction process, any questions should be directed to White Geotechnical Group as only we understand the full methodology behind the report's conclusions.
- The report addresses issues relating to your specific design and site. If the proposed project design changes, aspects of the report may no longer apply. Contact White Geotechnical if this occurs.
- This report should not be applied to any other project other than that outlined in section 1.0.
- This report is to be read in full and should not have sections removed or included in other documents as this can result in misinterpretation of the data by others.
- It is common for the design and construction process to be adapted as it progresses (sometimes to suit the previous experience of the contractors involved). If alternative design and construction processes are required to those described in this report, contact White Geotechnical Group. We are familiar with a variety of techniques to reduce risk and can advise if your proposed methods are suitable for the site conditions.

SITE PLAN – showing test locations





UNIT 23/28-34 ROSEBERRY STREET BALGOWLAH NSW AUSTRALIA 2093 Ph: 02 9976 5449 www.archisoul.com.au NOTES

COPYRIGHT - ARCHISOUL ARCHITECTS PTY LTD COPYRIGHT - ARCHITECTS ACT - 2003 NSW ABN 92 159 526 066 NSW NOMINATED ARCHITECT 6850 - JOANNE GILLIES

DRAWING NOT ISSUED FOR CONSTRUCTION. DO NOT SCALE FROM DRAWINGS. THE BUILDER SHALL CHECK AND VERIFYALL DIMENSIONS AND LEVELS ON SITE PRIOR TO MANUFACTURE & INSTALLATION ALL EPRORS AND OMISSIONS TO BE CONFIRMED WITH THE ARCHITECT.
DRAWINGS ARE TO BE READ IN CONJUNCTION WITH THE PREPARED WRITTEN SPECIFICATION & SCHEDULES & REQUIRED SHOP DRAWINGS, ALL WORK IN ACCORDANCE WITH RELEVANT AUSTRALIAN STANDARDS.

PROJE	DESCRIPTION	DATE	REV
Drawn	STAGE 2 - DA	23/10/2024	01
Plot Da			
Project			
Client:			
Client:			

PROJECT DETAILS | Checked JG - RR - RP

28/10/2024 Development Application

Brad & Louise Dowe

Church Point Project 2251

DRAWING TITLE: PROPOSED SITE PLAN

PROJECT NAME: 2131 Pittwater Road, REVISION NO.


01

DRAWING NO.


DA10



1:200 @ A3




GROUND FLOOR PLAN - showing minimum extent of required shoring / exploration pits / underpinning




Expected Ground Materials

Fill
Clayey Sandy Soil
Clayey Sand
Clay
Narrabeen Group Rocks – Extremely Low to Very Low Strength Shale



EXAMPLES OF GOOD HILLSIDE PRACTICE



EXAMPLES OF POOR HILLSIDE PRACTICE

