

Civilscan is a DBYD Ltd Certified Locating Organisation (CLO)

The Certified Locating Organisation (CLO) program is a formal agreement between DBYD Certification Ltd (as representative of the utility) and a locating company that gives certain properly certified employees access permissions to utility networks for the purposes of locating that utility's

Why Certified Locating Organisation status is necessary?

WHS regulations requires that all reasonable steps must be taken to obtain current underground essential services information about a workplace where excavation work is being carried out before directing or allowing the excavation work to commence. (WHS Regulations 2011, 304 Excavation work—underground essential services information).

Additionally, there is a "Duty of Care" to minimise the risk to fellow workers and the public against accidents, damage to property and fatalities. Underground networks are complex and requires expert knowledge to interpret information, to identify and locate components, to pothole underground assets for validation and to safely work around assets without causing damage.



Underground Services Report (USR)

10003770

Prepared for:

Matthews, Megan











Our Services

- ✓ Electronic Locating
- ✓ Ground Penetrating Radar
- ✓ Non Destructive vacuum **Excavation & vacuum loading**
- ✓ Concrete Scanning
- ✓ CCTV Pipe Inspections
- ✓ Drain Cleaning



 Civilscan Underground Services Report v37
ABN 51167311159 0416068060

Underground Services Report

Location Activities means

- (a) reviewing and interpreting plans of underground and above ground services provided by utilities;
- (b) conducting site investigations utilizing plans, knowledge and experience;
- (c) identifying and locating utility assets using approved industry equipment and practices including EMF devices, sondes, transponders and physically exposing if applicable; and
- (d) recording and marking of sub surface information in accordance with AS5488

To be completed by the underground service locator and emailed/handed to the client

DBYD Details									
Location			11 Coutts (Collaroy NS		2097				
Was the work si to hinder norma procedures? (Leave blank if I	If Yes, please provide a comment Examples include Wet Weather, Construction activities in progress, operational production facility				Nearby pits in accessible.				
DBYD Job	-	Telstra equence		-	Enquiry Date	′			
Optus Sequence		Optus Log			Have all plans been received		✓		
Electrical High	Ausgrid	If Vo	f Yes, refer to asset owner warning coversheet and contact Ausgrid						
Voltage	Endeavour	prior	to excavati	ion					
Trans- mission	Other	Take	note of Aus	sgriu	ilistructions and ex	Clusion 20	1165.		
Jemena High Pressure Gas		conta	act Jemena vation.	High	na High Pressure Ga Pressure Gas Netw instructions and ex	ork repres	enta	ative prior to	
Gas/Oil/Fu el Pipeline		repre	Yes, refer to the asset owner's warning coversheet and contact the presentative prior to excavation. Ake note of asset owner's instructions and exclusion zones.						

Services Located

- Spatial data to AS5488.1-2019 Classification of Subsurface Utility
- Measurements are in cm as per the instrument's accuracy
- ELV70B means Electricity Low Voltage (<1000V) 70cm AS5488.1-2019 QL-B below surface at the measurement point only.
- Pipes indicate diameter (∅) and depth to Top of Pipe. Invert Level (IL) maybe indicated in diagrams.

Service	0	Q L	Comments
---------	---	--------	----------

			Civilscan Underground Services Report v37
Service	0	Q L	Comments
Comms (All)			Additional Recommendations: Gas Monitor Level:

			Civilso	an Underground Services Report v37
Service	0	⊘ Q L	Commo	ents
SMOF (AII)			Additional Recommendations:	
Civilscan F014 Und	derground S	ground Services	Report	

Service Optus Additional Recommendations: Civilscan F014 Underground Services Report				Civilscan Underground Services Report v37
Additional Recommendations:	Service	0	Q L	Comments
Additional Recommendations:				
	Optus			
				Additional Recommendations:
er ur enaall la alfa la fina :				

				Civilscan Underground Services Report v3	
Service		0	Q L	Comments	
SX (Verizon)					
Data (Data/ Video/ Intercom)					
HPGM					
				Additional Recommendations:	
Civilscan F014 Underground Services Report					

				Civilscan Underground Services Report v37
Service		0	Q L	Comments
GM				Additional Recommendations:
GS				
Civilscan F014 Und	Hero	round S4	arvicas	s Renort

				Civilscan Underground Services Report v37
Service		0	Q L	Comments
				Additional Recommendations:
			<u> </u>	
ELV				Additional Recommendations:
Civilscan F014 Un	dora	round Sc	arvico	s Ranort

				Civilscan Underground Services Report v37
Service		0	Q L	Comments
EHV				
				Additional Recommendations:
WM				
Civilscan F014 U	nderg	round S	ervices	s Report

			Civilscan Underground Services Report v37
Service	0	Q L	Comments
			Additional Recommendations:
WS			Additional Recommendations:
Civilscan F014 Unde			

				Civilscan Underground Services Report v37	
Service		0	Q L	Comments	
			•		
FH					
				Additional Recommendations:	
IR					
ivilscan F014 Underground Services Report					

	Civilscan Underground Services Report v37			
Service	0	Q L	Comments	
			Additional Recommendations:	
S		A	IO identified Additional Recommendations:	
			Gas Monitor Level: ☑ O2 Level=20.9	
Civilscan F014 Under	ground S	ervice	s Report	

			Civilscan Underground Services Report v37
Service	0	Q L	Comments
SW	675	В	SW traced by cctv tractor camera and sonde from SPP43661 in Cumberland Ave. Initial attempt to enter from SPP13159 in Coutts Crescent was abandoned at SPP19163 due to a 1.0m vertical drop. No intermediate pits have been constructed. The trace was therefore done from a downstream access point. Additional Recommendations: CCTV Inspection Gas Monitor Level: O2 Level=20.9

Task Description	Compliance	Details of non compliance (Attach separate statement if insufficient space)
SWMS or JSA Completed	\checkmark	
DBYD/ Utility information received from the client	X	
Traffic Management		Private Property

	Civil	scan Underground Services Report v37
	×	
Services marked on ground as per ground marking requirements	V	
Indicative depths provided	X	Flags Used
Drainage inverts provided / measured	$\overline{\checkmark}$	
Site walk-thru completed		
USR- Marked up service plans for Quality Classes	$\overline{\checkmark}$	
Different services in common trench located separately	\checkmark	
Marked up Utility plans submitted to the Client	\checkmark	
Services located not shown on DBYD/ Utility plans;		
Services not located / unable to be found;		SPP13964
Utility / Asset owner locator required to discover service		Sewer

Figure 1 Work area overview

Figure 2 On-site images

Note	Details
1	Pipe section thru property has been identified and marked. X/Y measurements have been provided from a reference point.
2	Invert levels have been measured. Depth of cover to be calculated from pipe diameter.
3	
4	
5	

EQUIPMENT LIST

	Equipment	Description	Usage
V	RD 7100 TL Receiver RD 8000 PXL Receiver	EMF Locator Set	Active or passive service location for conductive pipes & cables
	RD 7100 TL Receiver RD 8000 PXL Receiver	EMF Locator Set	Active or passive service location for conductive pipes & cables + Power
	RD TX-3 Transmitter	EMF Locator Set	Active service location for conductive pipes & cables only
	RD TX-10 Transmitter	EMF Locator Set	Active service location for conductive pipes & cables only
	IDS Duo GPR (250/700Mhz)	Ground Penetrating Radar	Non-conductive pipes & cables
	Vetter 7.4mm Rod (80m)	Rodding Reel	Non-conductive pipes & cable ducts
	Vetter 4.5mm Rod (80m)	Rodding Reel	Non-conductive pipes & cable ducts
V	CCTV Rod (60m)	Rodding Reel + camera + sonde	Conductive & non-conductive pipes & ducts
	Sonde	Rodding Reel + sonde	Conductive & non-conductive pipes & ducts
	Non-metallic 1.2m probe	Non-conductive rated to 1000V	Testing depth
	Metal 1.0m probe	NOT FOR ELECTRICS	Testing depth
	GPR Concrete (min 1.6GHz)	Ground Penetrating Radar for concrete	Concrete scanning rebar, PT cables, voids
	Rebar detector	Concrete scanning (to 150mm)	Concrete scanning to 150mm
	Acoustic Locator	Geophone Acoustic Locator	Non-metallic pipes and leak dtection
	Vacuum Excavation or Hand Digging	Non-Destructive Excavation	Potholing, under-shoring, QL-A validation

COLOUR ALLOCATION LIST

Asset Type	Colour	Symbol Examples
Gas Main	Yellow	HPGM or GM
Gas Service	Yellow	G
Water Main	Blue	WM
Water Service	Blue	WS
Fire Water	Red	FW
Sewer	Cream (Green maybe used)	S
Stormwater	Green	SW
Telecommunications	White	С
Optical Fiber	White	SMOF (O/F maybe used)
Data/Video	White	D or V
Reclaimed Water	Violet	RW
Power	Orange (Red maybe used)	E (H/V & L/V)
Street Lighting	Orange (Red maybe used)	SL
Unidentified	Pink	As required ("?" maybe used)

^{*}Pink maybe used in poor contrast conditions such as green on grass

ABBREVIATIONS USED

Acronym	Meaning	Additional information
HPGM	High Pressure Gas Main	> 210kPa
GM	Gas Main	<210kPa
GS	Gas service	Typically connected to a

Acronym	Meaning	Additional information
1 A /B /	14.	meter
WM	Water Main	Typically potable mains distribution
WS	Water Service	Typically potable connected to a meter
FW	Firefighting Water	Typically connected to fire hydrants, boosters etc
RW	Reclaimed water	Non potable treated water
S	Sewer Sewer	All sewerage
SW	Stormwater	All stormwater
C	Communications	Typically copper services
SMOF	Single Mode Optical Fiber	Only optical fiber type for lon
MMOF	Multi Mode Optical Fiber	distance. Typical of a carrier. An optical fiber type for short distance (typically internal building runs)
D	Data	Includes telemetry and other remote control applications such as security
V	Video	Typically security cameras
EHV	Electricity High Voltage	> 1000V typically substation supply and transmission supply & DC (Railways)
ELV	Electricity Low Voltage	< 1000V including 415V & D
UKN	Unknown	A located target which cannot be identified without potholing eg abandoned pipes or cabling
HYD	Hydrant	Typically on a water main
SV	Stop valve	Typically on a water main
AV	Air valve	Typically on a water main
SCOUR	Scour point	Typically on a water main
CPIT	Communications Pit	Pit for private, unknown or other communications carriers such as TPG, Superloop etc
OPIT	Optus pit	Includes Verizon (SX)
NPIT	Nextgen pit	Includes Vocus
TPIT	Telstra pit	
SWPIT	Stormwater pit	
SMH	Sewer Man Hole	Typically requires confined space access
SWMH	Stormwater Man Hole	Typically requires confined space access
ТМН	Telstra Man Hole	Now classified as a footway access chamber. Typically requires confined space access
Pnnn	PVC conduit	nnn is the diameter 20, 35, 100 etc eg P100
Annn	Asbestos conduit or duct	nnn is the diameter 20, 35, 100 etc eg A100
ACnnn	Asbestos cement lined	Typically for water mains. nn is the diameter eg AC100
UPnnn	Ultra PVC	typically for water mains

Acronym	Meaning	Additional information
		includes 'Blue Brute' and other PVC variants. nnn is the diameter eg UP100
RC	Reinforced Concrete	Typical of stormwater pipes
SIS	Sewer Inspection Shaft	
IS	Inspection Shaft	
IL	Invert Level	Generally used instead of QL when tracing with sondes eg SW60IL

AS5488 Classification of Subsurface Utility Information (SUI) Quality Levels

Quality levels apply to a subsurface utility at the date that the information was obtained and at that particular measurement point.

Due to physical man-made and natural changes that may occur in the area around the subsurface utility since that date, at any future time and without further investigation the relative spatial position only indicates the best information available about the location of the subsurface utility.

Quality Levels are a classification reflecting the precision and accuracy of utility location and attribute information.

A quality level describes the amount and accuracy of information that is collected or held on a subsurface utility. There are four quality levels—D, C, B and A.

Quality level A is considered to be the highest quality level.

Description	Nomenclature	Attributes
Quality Level D	QL-D	The attribute information and metadata of a subsurface utility can be compiled from any, or a combination of, the following: (a) Existing records. (b) Cursory site inspection. (c) Anecdotal evidence. (d) Ground Penetrating Radar
Quality Level C	QL-C	A surface feature correlation or an interpretation of the approximate location and attributes of a subsurface utility asset using a combination of existing records (and/or anecdotal evidence) and a site survey of visible evidence. The minimum requirement for quality level C is relative spatial position. The location of surface features measured in terms of relative spatial positioning with a maximum horizontal tolerance of ±300 mm.
Quality Level B	QL-B	Provides relative subsurface feature location in three dimensions. The minimum requirement for quality level B is relative spatial position. Location of surface features measured in terms of relative spatial positioning with a maximum horizontal tolerance of ±300 mm; and Location of subsurface features measured in terms of relative spatial positioning with a maximum horizontal tolerance of ±300 mm and maximum vertical tolerance of ±500 mm.

Description	Nomenclature	Attributes	
Quality Level A	QL-A	Highest quality level and consists of the positive identification of the attribute and location of a subsurface utility at a point to an absolute spatial position in three dimensions. It is the only quality level that defines a subsurface utility as 'validated'. Where the whole line segment cannot be verified by line of sight, quality level A shall not be attributed to the line segment between validated points ie the whole line MUST be exposed.	

WARNING & DISCLAIMER

It must be noted that there are many factors beyond the control or knowledge of CIVILSCAN. There is no guarantee that all services have been located & marked. There has been no judgement made as to what is in the area to be excavated. It is purely an instrumental reading and interpretation and should be taken as such. It is highly recommended to expose the asset by potholing.

We shall not be liable in respect to any claim directly or indirectly arising from or in connection with any loss or damage when such loss or damage occurs due to works undertaken by a third party main contractor, excavator, principal or owner when such mechanical excavating activities occur within a minimum of 1 metre in diameter of the area(s) identified or the standard requirements as per the Work Cover Guidelines, Ausgrid Network Standards (NS156) and Asset Owners Requirement Guidelines for any work near powerlines. This exclusion does not apply to potholing and/or vacuum excavation within the identified area.

The party carrying out the excavation has to make the final decision and is solely responsible for the work being carried out. No liability is attached to CIVILSCAN in relation to the contents of this report or in respect of the work.

It is also important to note that the client fully understands the limitations of the available technology.

Site Representative	Present Not Present		Name	Megan	
Present		$\overline{\checkmark}$	Ivaille	Megan	
Billable Hours (excluding any downtime)		Final Report ☑			
Date	18/01/2023		Signature		

DBYD Certified Locator Details

USL	John Moi	nty	Signature	M	Date	18/01/2023
LLOCATION			outts Cres y NSW 2097	Optus Certified		\checkmark

DBYD CLO Locator	Certification Number		
John Monty	Y		

Our Services



- **✓ Ground Penetrating Radar**
- ✓ Non Destructive vacuum Excavation & vacuum loading
- **✓ Concrete Scanning**
- **✓ CCTV Pipe Inspections**
- **✓ Drain Cleaning**