# CONSENT NO: N0237/16 ENVIRONMENTAL PLANNING & ASSESSMENT ACT, 1979 (AS AMENDED) NOTICE TO APPLICANT OF DETERMINATION OF A DEVELOPMENT APPLICATION

Applicant's Name and Address: DUNCAN JOURNEE 48 TATIARA CRES NORTH NARRABEEN NSW 2101

Being the applicant in respect of Development Application No N0237/16

Pursuant to section 80(1) of the Act, notice is hereby given of the determination by Northern Beaches Council, as the consent authority, of Development Application No **N0237/16** for:

Alterations and additions to the existing dwelling and secondary dwelling

At: 48 TATIARA CRESCENT, NORTH NARRABEEN NSW 2101 (Lot 315 DP 238382)

#### **Decision:**

The Development Application has been determined by the granting of consent based on information provided by the applicant in support of the application, including the Statement of Environmental Effects, and in accordance with

- Architectural drawings 1818-1, 1818-2, 1818-3, 1818-4 and 1818-8, prepared by JD Evans and Company, all dated 15/04/2016
- Arborist Report, prepared by Naturally Trees Arboricultural Consulting, dated 18/03/2016
- Geotechnical Risk Management Report, J0813, prepared by White Geotechnical Group, dated 06/05/2016

as amended in red (shown clouded) or as modified by any conditions of this consent.

### The secondary dwelling is refused by Council and does not form part of this consent.

The reason for the imposition of the attached conditions is to ensure that the development consented to is carried out in such a manner as to achieve the objectives of the Environmental Planning and Assessment Act 1979 (as amended), pursuant to section 5(a) of the Act, having regard to the relevant matters for consideration contained in section 79C of the Act and the Environmental Planning Instruments applying to the land, as well as section 80A of the Act which authorises the imposing of the consent conditions.

Endorsement of date of consent 10-Aug-2016

Mark Ferguson INTERIM GENERAL MANAGER Per:

## **Conditions of Approval**

This consent is not an approval to commence building work. The works associated with this consent can only commence following the issue of the Construction Certificate.

Note: Persons having the benefit of development consent may appoint either a council or an accredited certifier as the principal certifying authority for the development or for the purpose of issuing certificates under Part 4A of the Environmental Planning and Assessment Act. When considering engaging an accredited certifier a person should contact the relevant accreditation body to ensure that the person is appropriately certified and authorised to act in respect of the development.

#### A. Prescribed Conditions:

- 1. All works are to be carried out in accordance with the requirements of the Building Code of Australia.
- In the case of residential building work for which the Home Building Act 1989 requires there to be a contract of insurance in force in accordance with Part 6 of that Act, that such a contract of insurance is in force before any building work authorised to be carried out by the consent commences.
- 3. A sign must be erected in a prominent position onsite only showing:
  - a) the name, address and telephone number of the Principal Certifying Authority for the work, and
  - b) the name of the principal contractor or the person responsible for the works and a telephone number on which that person may be contacted outside working hours, and
  - c) that unauthorised entry to the work site is prohibited.

The sign must to be maintained while the building work, subdivision work or demolition work is being carried out, but must be removed when the work has been completed.

- 4. Residential building work within the meaning of the Home Building Act 1989 must not be carried out unless the Principal Certifying Authority for the development to which the work relates (not being the Council) has given the Council written notice of the following information:
  - a) in the case of work for which a principal contractor is required to be appointed:
    - i) The name and licence number of the principal contractor, and
    - ii) The name of the insurer by which the work is insured under Part 6 of that Act.
  - b) in the case of work to be done by an owner-builder:
    - i) The name of the owner-builder, and
    - ii) If the owner-builder is required to hold an owner-builder permit under that Act, the number of the owner-builder permit.
  - c) If arrangements for doing the residential building work are changed while the work is in progress so that the information notified under a or b above becomes out of date, further work must not be carried out unless the Principal Certifying Authority for the development to which the work relates (not being the Council) has given the Council written notice of the updated information

- 5. If arrangements for doing the residential building work are changed while the work is in progress so that the information notified under subclause (2) becomes out of date, further work must not be carried out unless the Principal Certifying Authority for the development to which the work relates (not being the Council) has given the Council written notice of the updated information.
- 6. This approval/consent relates only to the new work nominated on the approved consent plans and does not approve or regularise any existing buildings or structures within the property boundaries or within Council's road reserve.
- 7. Any building work in relation to the development consent is to be carried out in accordance with the requirements of the Building Code of Australia.

# B. Matters to be incorporated into the development and maintained over the life of the development:

- 1. The secondary dwelling is refused and does not form part of this consent.
- 2. The finished surface materials, including colours and texture of any building, shall match the detail and materials of the existing building.
- 3. If any Aboriginal Engravings or Relics are unearthed all work is to cease immediately and the Aboriginal Heritage Office (AHO) and Office of Environment and Heritage (OEH) are to be notified.
- 4. Prior to the completion of works, all declared noxious weeds are to be removed/controlled in accordance with the Noxious Weeds Act 1993. Environmental weeds are to be removed and controlled. Refer to Council website http://www.pittwater.nsw.gov.au/environment/noxious\_weeds for noxious/environmental weed lists.
- 5. No environmental weeds are to be planted on the site. Refer to Council website http://www.pittwater.nsw.gov.au/environment/noxious weeds for environmental weed lists.
- 6. Domestic pet animals are to be kept from entering wildlife habitat areas at all times. Dogs and cats are to be kept in an enclosed area or on a leash such that they cannot enter areas of bushland or foreshore, unrestrained, on the site or on surrounding properties or reserves. Ferrets and rabbits are to be kept in a locked hutch/run at all times.
- 7. No building materials or other materials are to be placed on Bushland vegetation. Sediment is not to leave the site or enter areas of Bushland vegetation, and the appropriate sediment fencing is to be installed.
- 8. As part of the integrated stormwater management plan, suitably positioned stormwater quality improvement devices shall be installed and operated in accordance with Manufacturer's Specifications and associated operational guidelines.
- 9. In accordance with Pittwater 21 DCP Control B4.22 Protection of Trees and Bushland Vegetation, all existing trees as indicated in the Survey Plan and/or approved Landscape Plan shall be retained except where Council's prior written consent has been obtained, for trees that stand within the envelope of approved development areas and removal is approved through an arborist report. For all other tree issues not related to a development application, applications must be made to Council's Tree Management Officers.

10. The commitments identified in the BASIX Certificate and on the plans or specifications are to be fulfilled and maintained for the life of the development.

### C. Matters to be satisfied prior to the issue of the Construction Certificate:

Note: All outstanding matters referred to in this section are to be submitted to the accredited certifier together. Incomplete Construction Certificate applications / details cannot be accepted.

- 1. Submission of construction plans and specifications and documentation which are consistent with the approved Development Consent plans, the requirements of Building Code of Australia and satisfy all conditions shown in Part B above are to be submitted to the Principal Certifying Authority.
- 2. The Principal Certifying Authority must be provided with a copy of plans that a Quick Check agent/Sydney Water has stamped before the issue of any Construction Certificate.
- 3. The person having the benefit of this consent is required to notify the Principal Certifying Authority to ensure that the following critical stage inspections are undertaken, as required under clause 162A(4) of the Environmental Planning and Assessment Regulation 2000:
  - a) after excavation for, and prior to the placement of, any footings, and
  - b) prior to pouring any in-situ reinforced concrete building element, and
  - c) prior to covering of the framework for any floor, wall, roof or other building element, and
  - d) prior to covering waterproofing in any wet areas, and
  - e) prior to covering any stormwater drainage connections, and
  - f) after building work has been completed and prior to any occupation certificate being issues in relation to the building.

To allow a Principal Certifying Authority to carry out critical stage inspections, at least 48 hours notice must be given before building work is commenced and prior to further work being undertaken.

- 4. Construction works approved by this consent must not commence until:
  - a) Construction Certificate has been issued by a Principal Certifying Authority
  - b) a Principal Certifying Authority has been appointed and Council has been notified in writing of the appointment, and
  - c) at least 2 days notice, in writing has been given to Council of the intention to commence work.
- 5. In accordance with section 34 of the Building and Construction Industry Long Service Payments Act 1986, the applicant must pay a long service levy at the prescribed rate of 0.0035 of the total cost of the work to either the Long Service Payment Corporation or Council for any work costing \$25,000 or more.
- 6. Prior to issue of the Construction Certificate, Form 2 of the Geotechnical Risk Management Policy for Pittwater (Appendix 5 of P21 DCP) is to be completed and submitted to the Accredited Certifier.

7. Drainage plans including specifications and details showing the site stormwater management are to be submitted to the Accredited Certifier with the Construction Certificate application. Such details are to be accompanied by a certificate from (as appropriate) either a Licensed plumber or qualified practicing Civil Engineer with corporate membership of the Institute of Engineers Australia (M.I.E), or who is eligible to become a Corporate member and has appropriate experience and competence in the related field, that the stormwater management system complies with the requirements of section 3.1.2 Drainage of the Building Code of Australia Housing Provision and AS/NZS 3500.3.2 - Stormwater Drainage. The details shall include disposal of site stormwater (if the site is in a known slip area the stormwater disposal system must comply with the recommendations of a Geotechnical Engineers Report).

Note: Where Council is the Principal Certifying Authority 3 sets of plans/specifications are to be submitted.

- 8. Plans and details demonstrating that the commitments identified in the BASIX Certificate that apply to the construction certificate or complying development plans and specifications are fulfilled.
  - 9. The finished surface materials, including colours and texture of any building, shall blend with the surrounding and/or natural materials. Colours and materials shall be non-glare and of low reflectivity. A satisfactory specification which achieves this shall be submitted to the Accredited Certifier or Council with the Construction Certificate application in the form of a Schedule of Finishes.

# D. Matters to be satisfied prior to the commencement of works and maintained during the works:

Note: It is an offence to commence works prior to issue of a Construction Certificate.

- 1. The hours of construction are restricted to between the hours of 7.00am and 5.00pm Monday Friday and 7.00am to 1.00pm on Saturdays. No works are to be carried out on Sundays or Public Holidays. Internal building work may be carried out at any time outside these hours, subject to noise emissions from the building or works not being audible at any adjoining boundary.
  - Note: This condition does not apply in relation to Crown building work that is certified, in accordance with Section 116G of the Act, to comply with the technical provisions of the States building laws.
- 2. Any proposed demolition works shall be carried out in accordance with the requirements of AS2601-2001 The Demolition of Structures.
  - Amongst others, precautions to be taken shall include compliance with the requirements of the WorkCover Authority of New South Wales, including but not limited to:

- a) Protection of site workers and the general public.
- b) Erection of hoardings where appropriate.
- c) Asbestos handling and disposal where applicable.
- d) Any disused service connections shall be capped off.

Council is to be given 48 hours written notice of the destination/s of any excavation or demolition material. The disposal of refuse is to be to an approved waste disposal depot.

- 3. A stamped copy of the approved plans is to be kept on the site at all times, during construction.
- 4. Where excavations extend below the level of the base of the footings of a building on an adjoining allotment of land, the person causing the excavation must give the owner of the adjoining property at lease seven (7) days written notice of their intention to excavate below the level of the base of the footing and furnish the adjoining property owner with particulars of the proposed work.
- 5. All excavations and backfilling associated with the erection or demolition of a building must be executed safely and in accordance with appropriate professional standards.
- 6. The site must be fenced throughout demolition and/or excavation and must comply with WorkCover New South Wales requirements and be a minimum of 1.8m in height.
- 7. Where excavations extend below the level of the base of the footings of a building on an adjoining allotment of land, the person causing the excavation must preserve and protect the building from damage and, if necessary, underpin and support the adjoining building in an approved manner.
- 8. Temporary sedimentation and erosion controls are to be constructed prior to commencement of any work to eliminate the discharge of sediment from the site.
- 9. Sedimentation and erosion controls are to be effectively maintained at all times during the course of construction and shall not be removed until the site has been stabilised or landscaped to the Principal Certifying Authority's satisfaction.
- 10. Adequate measures shall be undertaken to remove clay from vehicles leaving the site so as to maintain public roads in a clean condition.
- 11. Personnel with appropriate training, or demonstrated knowledge and experience in erosion and sediment control shall be responsible for supervising the installation and maintenance of approved erosion and sediment control measures during and after construction and until the site has been restored to the satisfaction of council.
- 12. No works are to be carried out in Council's Road Reserve without the written approval of the Council.
  Note: Separate approval is required for access driveways, paths, connections to underground
  - Note: Separate approval is required for access driveways, paths, connections to underground services (stormwater, gas, sewer, electricity,etc:), and landscaping works within Council's Road Reserve.
- 13. No skip bins or materials are to be stored on Council's Road Reserve.
- 14. A clearly legible *Site Management Sign* is to be erected and maintained throughout the course of the works. The sign is to be centrally located on the main street frontage of the site and is to clearly state in legible lettering the following:

- a) The builder's name, builder's telephone contact number both during work hours and after hours.
- b) That no works are to be carried out in Council's Road Reserve without prior application and approval of a Road Opening Permit from Council.
- c) That a Road Opening Permit issued by Council must be obtained for any road openings or excavation within Council's Road Reserve associated with development of the site, including stormwater drainage, water, sewer, electricity, gas and communication connections. During the course of the road opening works the Road Opening Permit must be visibly displayed at the site.
- d) That no skip bins or materials are to be stored on Council's Road Reserve.
- e) That the contact number for Northern Beaches Council for permits is 9970 1111.
- 15. No storage of building materials or building waste, excavated fill or topsoil storage is to occur within the dripline of trees shown on the approved landscape working drawing(s) as being retained or within protective fenced areas.
  - Drainage is to be arranged such that fill, building materials or contaminants are not washed into protective fenced areas.
- 16. The developer or contractor will take all measures to prevent damage to trees and root systems during site works and construction activities including provision of water, sewerage and stormwater drainage services. In particular, works, erection of structures, excavation or changes to soil levels within 5 metres of the trunks of trees to be retained are not permitted, and the storage of spoil, building materials, soils or the driving or parking of any vehicle or machinery within 5 metres of the trunk of a tree to be retained, is not permitted.

NOTE: Trees that are part of an Endangered Ecological Community or are habitat for threatened species and endangered populations must comply with the requirements of the Threatened Species Conservation Act, 1995. Failure to do so may result in a penalty up to a maximum of \$250,000.00 and jail sentences.

Failure to comply with the requirements of the Pittwater 21 DCP Control B4.22 Preservation of Trees of Bushland Vegetation may result in a penalty up to a maximum of \$20,000.00.

### E. Matters to be satisfied prior to the issue of Occupation Certificate:

Note: Prior to the issue of an Occupation Certificate the principal certifying authority is to ensure that Council's assets, including road, kerb and gutter and drainage facilities adjacent or near to the site have not been damaged as a result of the works. Where such damage has occurred, it is to be repaired to Council's written satisfaction prior to the issue of an Occupation Certificate or suitable arrangements put in place to effect those repairs at a future date to Council's written satisfaction. Should this process not be followed, Council will pursue action against the principal accredited certifier in relation to the recovery of costs to effect such works.

Note: It is an offence to occupy the building or part thereof to which this consent relates prior to the issue of an Occupation Certificate.

- 1. An Occupation Certificate application stating that the development complies with the Development Consent, the requirements of the Building Code of Australia and that a Construction Certificate has been issued must be obtained before the building is occupied or on completion of the construction work approved by this Development Consent.
- 2. Prior to issue of the Occupation Certificate, Form 3 of the Geotechnical Risk Management Policy (Appendix 5 of P21 DCP) is to be completed and submitted to the Accredited Certifier.
- 3. The stormwater drainage system must be constructed and completed in accordance with the approved design and relevant Australian Standards.
  - A plan showing pipe locations and diameters of the stormwater drainage system, together with certification by a Licensed Plumber or qualified practicing Civil Engineer that the drainage system has been constructed in accordance with the approved design and relevant Australian Standards must be provided.
- 4. Restoration of all damaged public infrastructure caused as a result of the development to Council's satisfaction. Council's written approval that all restorations have been completed satisfactorily must be obtained and provided to the Private Certifying Authority with the Occupation Certificate application.
- 5. Certification is to be provided that the commitments identified in the BASIX Certificate have been fulfilled.

### G. Advice:

- 1. Failure to comply with the relevant provisions of the *Environmental Planning and Assessment Act*, 1979 (as amended) and/or the conditions of this Development Consent may result in the serving of penalty notices (on-the-spot fines) under the summary offences provisions of the above legislation or legal action through the Land and Environment Court, again pursuant to the above legislation.
- Dial before you dig: Prior to excavation the applicant is advised to contact Australia's National Referral Service for Information on Underground Pipes and Cables telephone 1100 or www.1100.com.au
- It is the Project Managers responsibility to ensure that all of the Component Certificates/certification issued during the course of the project are lodged with the Principal Certifying Authority. Failure to comply with the conditions of approval or lodge the Component Certificates/certification will prevent the Principal Certifying Authority issuing an Occupation Certificate.

- 4. In accordance with Section 95(1) of the EPA Act 1979, this development consent lapses 5 years after the date from which this consent operates if the development is not commenced.
- 5. To ascertain the date upon which a consent operates, refer to Section 83 of the *Environmental Planning and Assessment Act, 1979* (as amended).
- 6. Should any of the determination not be acceptable, you are entitled to request reconsideration under Section 82A of the Environmental Planning and Assessment Act, 1979. Such request to Council must be made in writing, together with appropriate fees as advised at the time of lodgement of such request, within 6 months of the determination.
- 7. If you are dissatisfied with this decision, Section 97 of the Environmental Planning and Assessment Act, 1979, gives you a right of appeal to the Land and Environment Court within 6 months of the date of endorsement of this Consent.
- 8. The approved plans must be submitted to a Sydney Water Quick Check agent or Customer Centre to determine whether the development will affect Sydney Waters sewer and water mains, stormwater drains and/or easements, and if further requirements need to be met. The approved plans will be appropriately stamped. For Quick Check agent details please refer to the web site at <a href="https://www.sydneywater.com.au">www.sydneywater.com.au</a> then see Building Developing and Plumbing then Quick Check, or telephone 13 20 92.