

16 May 2008

The General Manager Pittwater Council PO Box 882 MONA VALE NSW 1660

Dear Sır/Madam

CONSTRUCTION CERTIFICATE PROPOSAL Swimming Pool PREMISES 23 Thyra Road, Palm Beach DEVELOPMENT APPLICATION NO NO333/07

I refer to the above matter and accordingly submit the following documentation for your records

- Construction Certificate No 08/71
- Form 7
- Copy of construction certificate application form
- Copy of the Home Warranty Certificate
- Copy of plan stamped by Sydney water
- Form 2
- Soil & erosion control plan certification
- Landscape plans & site plans prepared by Paul Scrivener
- Structural engineering details prepared by Neilly Davies & Partners Pty Ltd
- Cheque from the owners for \$537 50 in favour of Council being payment for the Long Service Leave Levy (\$507 50) & Construction Certificate registration fee (\$30 00)

In addition to the above please be advised that the builder for this project will be Jade Swimming Pools, Licence No 31789

238502. 20/5/08 Should you have any queries in relation to this matter, please contact us immediately

Yours Sincerely

Greg Hough DIRECTOR

C \Documents and Settings\Greg\My Documents\Get Certified Building Services\Clients\J\Jade Swimming Pools Ptv Ltd\23 Thyra Rd, Palm Beach\Letter to Council doc



GONSTRUCTION OF REFEORTS

Pursuant to Section 109D(1) of the Environmental Planning and Assessment Act 1979

Construction Certificate Application No 08/71

Date of this Construction Certificate 16 May 2008

Applicant's Name Jade Swimming Pools P/L

Applicant's Address 488 Windsor Road, Baulkham Hills,

NSW, 2153

Details of the land on which the development is to be carried out

Lot 23, DP 18612, 23 Thyra Road, Palm

Beach, NSW

Development as described on any relevant development consent

Swimming Pool

Registered number and date of issue of any relevant development consent

NO333/07 – 8 August 2007

The issue of this Construction Certificate has been endorsed on the plans, specification and documentation lodged with the Application and detailed on the attached table. The classification (in accordance with the Building Code of Australia) of the building and structures to which this certificate relates is 10b.

Work completed in accordance with the documentation accompanying the application for Construction Certificate No CC-08/71 (with such modifications verified by the certifying as may be shown on that documentation) will comply with the requirements of the Environmental Planning and Assessment Regulation 2000 as are referred to in Section 81A(5) of the Environmental Planning and Assessment Act 1979

The Certifying Authority by which this Construction Certificate is granted is Gregory Hough, Accredited Certifier

Gregory Hough
Accredited Certifier

(Accreditation Number BPB0186)

4/

Building Professionals Board is the accreditation body by which Gregory Hough is accredited Attachments Endorsed plans, specifications and documentation




CONSTRUCTION CERTIFICATE No. 08/71

PLANS / DETAILS	REFERENCE NUMBERS
Structural Engineering Details & Site Plan Prepared by Neilly Davies & Partners Pty Ltd	Job No J0813 DWG No 1/4 to 4/4p
Landscape Plans & Site Plan Prepared by Paul Scrivener	Dated 8 May, 2007 Sheets 1 of 4 to 4 of 4 Issue B







Ø CONSTRUCTION CERTIFICATE APPLICATION COMPLYING DEVELOPMENT CERTIFICATE APPLICATION **Environmental Planning and Assessment Act 1979**

Application No 08 171 Subject land. Address 23 THYRA ROAD, PALM BEACH Lot no, DP/MPS, etc vol/fol LOT 6 DP 18612 m^2 Area of site 676 Description of development: Type of application new application modification to existing approved certificate Description of proposed works INGROUND CONCRETE SWIMMING POOLS WITH CATCH TANK AND TIMBER STEPS Applicant's details.

Telephone No

Name/s (In block letters) JADE SWIMMING POOLS PLL Address 488 WINDSOR RD, BAULKHAM HILLS 2153 Telephone No (Business 9686-6000 (Private) JOHN-(Mobile) 0418 229 010 (Fax No.) 9686-6665 (Email Address) jadepoolsejadepools.com.au

The state of the s Owner's details: Name/s RON & JENNY HICKEY

Address 23 THYRA ROAD, PALM BEACH.

1 (Mobile) 0407411 093 (Fax No)

(Email Address)

(Business)

Get Certified Building Services Pty Ltd ABN 30 123 390 429 • PO Box 191 Cherrybrook NSW 2126 Phone 9651 6754 • Fax 9651 6780 • Mobile 0413 618 933 • Email getcertified@optusnet.com au

9974-1612

(Private)

Consent of owners.	(- 4 ; ; (1 - ;) 3
 I / we consent to The making of this application Appointment of Greg Hough of Get Certified Build as the Principal Certifying Authority for this developed PCA Service Agreement (Refer to attached PCA Agreement) 	opment and agree by the terms under the greement)
Signature/s >	Date 23 april 08
Signature/s × efelicary	Date 23 April 08
Development consent devals (Construction Certifical	te Application Only):
	Date of determination 8 18 107
Value of work (building). \$ 145,7	(including GST)
Builder / owner-builder details (if known at, this stage	e):
Name/s Jode Swimming Pools	Pty Ltd
Address 488 Windsor Rd Bawkh	
Contract licence No or Permit No in case of an owner build	der 31789
Contact details ROSYN 9686-6000	
Building Code of Australia building classification (af known)): 106
Privacy	
The personal details requested on this form are required Assessment Act 1979 and will only be used in connection and Access to this information is restricted to Get Certified But	with the requirements of this legislation

Date 7-5-08

authorised under the Act

Signature of Applicant

SCHEDULE TO CONSTRUCTION CERTIFICATE/COMPLYING DEVELOPMENT APPLICATION (This information will be sent to the Australian Bureau of Statistics)

Pool

N/A

All new buildings:

Specified

Please complete the following

• Number of storeys (including underground floors)

• Gross floor area of new building (m²)

• Gross	site a	ırea (n	1-)				L	67	6m2		
All new bu	ıldir	ıgs:			٠	ų . n²	بو ٠	۲ ۸.	2 m 3 4 4 5		
Please comp	lete t	he fol	lowing details	of re	esident	ial structures					
• Numb	er of	dwell	ings to be con:	struc	ted			N/A	1]	
• Numb	er of	pre-ex	usting dwellin	gs o	n site			ONE	·]	
• Numb	er of	dwell	ngs to be dem	olisł	ned						
 Will the Buildi 		w dwe	elling (s) be att	ache	ed to ot	her new	Y	es 🛚	No 😉	-	
 Wıli ti Buildi 		w dwe	iling (s) be at	ache	d to ex	asting	Y	es 🗖	No (9	_	
			taın a dual occ ncy = two dwe			ne same site)	Y	es 🗖	No 🖸		
All new bu	ıldır	ıgs:	Norman Spir	-	~ ~		•			-	
Please indica	te th	e mate	erials to be use	d m	the co	nstruction of	the ne	w buil	dıng(s)		
Walls		Code	Roof	_(ode	Floor	C	ode	Frame	Cod	e
Brick (double)		11	Tiles		10	Concrete or slate	đ	20	Tımber	□ 40	
Brick (veneer)		12	Concrete		20	Timber		40	Steel	≥ 60	
Concrete or stone		20	or slate Fibre		30	Other		80	Alummum	□ 70	
Fibre Cement Timber	0	30 40	Steel		60	Not Specified		90	Other	□ 80	
Curtain glass		50	Aluminium		70 80	1			Not specified	□ 90	
Steel	D	60	Not		90						
Alumınıum		70	specified	LJ	<i>9</i> 0			İ			
Other		80	N/A								
Not		90	/ ~,			1					





Certificate of Insurance

Jade Swimming Pools Pty Ltd PO Box 654 BAULKHAM HILLS NEW SOUTH WALES 1755

> Form 1 Section 92 Home Building Act 1989

CERTIFICATE IN RESPECT OF INSURANCE

Local Authority's Copy
Issue Date 2/04/2008

Date 2/04/2008

Certificate No RCW73773341

Contract Of Insurance Complies With Section 92

Of The Home Building Act 1989

Issued By Vero Insurance Limited

ABN 48 005 297 807

Building Contract Details

Contract Date March 31, 2008

Declared Building Contract Value \$145,650 00

(Refer policy for indemnity limit)

Carried Out By Jade Swimming Pools Pty Ltd

ABN 80001835552

Licence No 31789

For R&J Hickey

In Respect Of Swimming Pools

At House No 23

Thyra Road

PALM BEACH NEW SOUTH WALES 2108

Permit Authority Pittwater Council

Subject to the Act and the Home Building Regulation 2004 and the conditions of the Insurance contract, cover will be provided to a beneficiary described in the contract and successors in the title to the beneficiary. Please note when the Insurer has issued this certificate the Insurer is not entitled to refuse to pay a claim or to cancel the insurance contract on the grounds that the premium was not paid. This certificate is to be read in conjunction with the policy wording

N 30MHD4ATY88R

Printed 2/04/2008

Signed for and on behalf of the insurer

Insurer Vero Insurance Limited ABN 48 005 297 807



Transaction Summary



Date Requested

Wed April 16 2008

A B N 49 776 225 038

Agent

Cooks North Rocks, 27 Loyalty Road North Rocks

Applicant

JADE POOLS, 488 WINDSOR RD BAULKHAM HILLS 2153

This document will be a tax invoice when you make payment


Transaction	Details	Charge	GST	Total
23 Thyra Rd,	Palm Beach 2108			
03	2269744 Building Plan Approval Application Fee	\$24 40	\$0 00	\$24 40
Transaction	Total	+24.40	έΩ ΩΩ	÷24.40

Fax ląΤ POOLS **JA8** 09 JA8 384 y C

80 40 11	MIE AUG CPCUK UPOR 9200b
JTAO	CHECKED

758486 (20) leT Fax (02) 94198241 44 Hampden Road, Suite 405, Artarmon, NSW 2064 Consulting Civil & Structural Engineers

Neilly Davies & Partners Pty Ltd



SYDNEY WATER

FILLING OF SWIMMING POOLS

The water supply to the pool must be drawn from a metered service and any tap or hose used to fill the pool must be at least 150mm above the highest possible water level of the pool

EMPTYING OF SWIMMING POOLS

Pools emptying into Sydney Water's Se ver must

- a) Discharge into a gully through a pipe
- Discharge only in dry weather, with prior approval from Sydney Water's Customer Centre

NOTE IT IS PROHIBITED TO

er

DISCHARGE POOL WATER INTO ANY OF SYDNEY WAS **VACUUM SYSTEM SEWERS**


Cooks North Rocks Quick Check Agent in behalf of SYDNEY WATER

161.4108 solow.

Swimming Pool Stamp

Permits are required to fill all new swimming pools with a capacity greater than 10,000L Contact Sydney Water on 13 20 92 during business hours

Fines of \$220 will apply for filling pools without a permit



GEOTECHNICAL RISK MANAGEMENT POLICY FOR PITTWATER

FORM NO 2 – To be submitted with detailed design for construction certificate
Development Application for
Name of Applicant
Address of site23 Thyra Road, Palm Beach
Declaration made by Structural or Civil Engineer in relation to the incorporation of the Geotechnical issues into the project design
Bala Muhunthan on behalf of Neilly Davies & Partners
(insert name) (trading or company name)
on this the \ \ \oS \ \O8
certify that I am a Structural or Civil Engineer as defined by the Geotechnical Risk Management Policy for Pittwater. I am authorised by the above organization/company to issue this document and to certify that the organization/company has a current professional indemnity policy at least \$2million. I also certify that I have prepared the below listed structural documents in accordance with the recommendations given the Geotechnical Report for the above development.
Geotechnical Report Details
Report Title Risk Analysis and Management Report for the proposed pool at 23 Thyra Road Palm Beach VS 24515
Report Date 28 th May 2007
Author BEN WHITE
Structural Documents list
Drawing No JO 813 Sheets 1 to 4
I am also aware that Pittwater Council relies on the processes covered by the Geotechnical Risk Management Policy including this certification as the basis for ensuring that the geotechnical risk management aspects of the proposed development have been adequately addressed to achieve an Acceptable Risk Management level for the life of the structure taken as at least 100 years unless otherwise stated and justified
BALA MUHUNTHAN TULL (name) (signature)
(name) (signature)
Declaration made by Geotechnical Engineer or Engineering Geologist in relation to Structural Drawings
I prepared and/or technically ventied the abovementioned Geotechnical Report as per Form 1 dated 30/05/2007 and now certify that I have viewed the above listed structural documents prepared for the same development. I am satisfied that the recommendations given in the Geotechnical Report have been appropriate taken into account by the structural engineer in the preparation of these structural documents. I am aware that Pittwater Council relies on the processes covered by the Geotechnical Risk Management Policy. Including this certification at the basis for ensuring that the geotechnical risk management aspects of the proposed development have been adequately addressed to achieve an Acceptable Risk Management. Level for the life of the structure taken as at least 100 years unless otherwise stated and justified the Report and that reasonable and practical measures have been identified to remove foreseeable risk.

Signature Name J HODGSON MEngSc FIEAust Chartered Professional Status Membership No 149 788 Jack Hodgson Consultants Pty Ltd Company





28 April 2008

The Principal Certifier 23 Thyra Road Palm Beach NSW 2108

Dear Sir,

Re - Landscape Development at 23 Thyra Road, Palm Beach

This is to certify that I have reviewed the above landscape development plans specifically sheet 4 of 4 Dwg No 07/1176/DA4 issue B and consider that the sediment control measures that have been provided are adequate during the construction stage


Yours faithfully,


Arriv


Bala Muhunthan


B Sc, (Hon) Civil Eng, M.Eng Sc, FICE, MIE Aust, CP Eng NPER

28/04/08









CERTIFICATE No. 08/71

These plans form part of the above Gemplying Development Certificate as issued by

0

NOTES FOR OWNERS

4 S12

AVERAGE WATER LEVEL

BOND BEAM BARS

150

100

8

Greg Hough of

Get Certified Building Services Pty Ltd level is deemed to be acceptible to the owner-authorsochrowipseegadwised BP 80186

POOL SET OUT
Pool set—out size location and height otherwise. Such advice must be prior be thoroughly wetted down twice daily for at least (7) days (ten (10) days in

CURING CONCRETE

After concreting the pool shell is to

2512

SAFETY FENCES
Safety fencing is to be Council approved prior to the pool being filled summer)

S12'S AS NOTED ON

SECTIONS

FILLING POOL

Hose to be prevented from swishing around during filling. DO NOT use rubber hoses

UNDERWATER LIGHTS
Lights must be fully submerged during

CANTILEVERED WALKWAY DETAIL

CORNER DETAIL

BOND BEAM

1 25

중

--당

WALKWAYS AND COPINGS

Walkways and copings are designed for a 2 kPa live load and are not designed to support masonry walts unless noted

SPECIFICATIONS

- All workmanship and materials to be in accordance with Australian Standard AS 2783
- Site Plan dimensions are to water
- Dimensions shall not be obtained by scaling the details

2 SI2 ፔ

- All levels and dimensions are relative to concrete coping level. Fixed Datum represents the fixed coping height/level
- Approximate coping levels are represented as follows

 a) NGL +200 represents 200 mm above existing Natural Ground Level

 b) NGL -400 represents 400 mm below existing Natural Ground Level
- Provide filter with matched pump of and plumbing to manufacturers recommendations
- Supporting soil to be stable natural material with a min safe bearing capacity of 100 kPa
- Advise Engineer if excavation in fill or ground water is enco ground water level exceeds 500 mm above deep floor level or ground water is encountered. Provide temporary penetrations to floor slab if

- The excavation base is to be provided with an undershell drainage layer as follows a) 75 min blue metal drainage layer, or 50 min thick layer with plastic over b) Corrugated iron sheeting & membrane if over rock c) Plastic layer only if base is entirely in sand d) Main Drain pit is to be blue metal filled irrespective of drainage layer type
- All reinforcement to be of Australia S Grade 230 stuctural grade of Y Grade 410 tempcore grade t
- entirely in sand

 metal filled irrespective of drainage layer type

 item Manufacture in accordance with S.A.A. Standards

 deformed

 R.—Grade 230 plain grade round

 deformed

 F.—Grade 450 hard drawn wire fabric

 f.—Grade 450 hard drawn wire fabric
- Reinforcing bars, unless notd otherwise are to be lapped 40 bar diameters min , fabric to be lapped 400mm min laps should preferably be staggered
- All reinforcing to be securely supported by bar chairs at 1000 max cs
- 72 = 1 Minimum concrete cover to reinforcement from closest concrete surface to be as follows: Water face Salt Chlorination 65mm
 Water face standard chlorination 50mm
 Coping/walkway surface. 50mm
 Rear face formed 40mm

400

Concrete to be pneumatically placed have a min design strength of Fc 25 MPa at 28 days except

A) Where structure located < 1km from large expanses of water — concrete design strength min Fc 32 MPa at 28 days

B) Where structure is located in tidal or splash zone of salt water — 40 MPa at 28 days rough ground 65mm

Upon completion of concreting the hydrostatic volve is to be cleaned & checked to ensure correct operation

7

ä

A C N 001 835 552

SWIMMING POOL FOR

HYDRO VALVE DETAIL

5

488 WINDSOR ROAD, BAULKHAM HILLS 2153

PO BOX 654, BAULKHAM HILLS 1755 (02) 9686 6000 (02) 9686 6665

DRAWN BY RON & JENNY HICKEY

23 THYRA ROAD, PALM BEACH DATE 98 80 80

፟ APRIL <u>0</u>8 AS SHOWN

MIE AUG C. PCUL

NPGE 92996

11 04 08

SECKED

DATE

Consulting Civil & Structural Engineers
44 Hampden Road, Suite 405, Artarmon, NSW 2064
Tel (02) 98848637 Fax (02) 94198241

Nelly

Davies

જ્

Partners

Pty Ltd

PLUMBING LAYOUT

ì

DIAGRAMMATIC ONLY

MAIN DRAIN

SURFACE SKIMMER

DISCHARGE

ELEVATION

SECTION

2 S12 U

COMPLY WITH AS3000 REINFORCEMENT TO EARTHING OF POOL


SKIMMER DETAIL


20

, filter & Pump

POOL RETURN

J0813







Legend


370.74m²	Soft landscaping
20.91m²	Pool area
49.44m²	Open timber walkways


Site area calculations


Compliance	Yes	
Total assessable landscape area	432.21 m2	63.93%
Pool area	20.91 m2	3.09%
Timber walkways (49.44 m2) (only 6% functional allowance included)	40.56 m2	6.00%
Soft landscaping	370.74 m2	54.80%
Site area	676.00 m2	100.009






























Any existing trees and vegetation to be retained shall be preserved and protected from damage of any sort during the execution of landscape work. In particular, root systems of existing plants must not be disturbed if possible. Any nearby site works should be carried carefully using hand tools.

To ensure the survival and growth of existing trees during landscaping works, protect by fencing or armouring where necessary. Trees shall not be removed or lopped unless specific written approval to do so is given or is indicated on plan. Storage of materials, mixing of materials, vehicle parking, disposal of liquids, machinery repairs and refueling, site office and sheds, and the lighting of fires shall not occur within three (3) metres of any existing trees. Do not stockpile soil, rubble or other debris cleared from the site, or building materials, within the dripline of existing trees. Vehicular access shall not be permitted within three (3) metres of any tree.

2. Soil preparation All proposed planting areas to be deep ripped to 200mm and clay soils to be treated with clay breaker.. Harvested existing top soil from site and store on site. Mix with 25% A.N.L. Greenlife compost or approved equivalent. Apply at least 100mm soil depth to planting areas. Additional soil to be 75mm depth of good quality planting mix to be imported and combined with 25mm depth A.N.L. Greenlife compost or approved equivalent. To be worked in with rotary hoe. Care taken to hand cultivate in any area where existing tree

 New plantings
 Newly planted trees and large shrubs should be secured to stakes with hessian ties to prevent rocking by wind. Planting holes for plant material should be large enough in size to take root ball with additional space to take back filling of good quality planting mix.

Mature heights of planting as shown on planting schedule show the greatest height possible in ideal conditions. These heights are subject to particular site conditions, possible container environments and intended hedging or pruning for functional requirements such as available planting width, intended access under branches and solar access.

All planting areas to be mulched with a minimum 100mm thick cover of leaf litter mulch and then all plant areas to be thoroughly soaked with water. All

mulch shall be free of vegetative reproductive parts of all weed species All planting areas to be fertilised with 9 month 'NPK' slow release fertiliser. Mass planted areas: allow one slow release Agriform pellet per 5-25 litre

plant. All fertilisers to be applied in accordance with the manufacturers instructions.

Turfed areas:Supply and install Agriform slow release fertiliser or approved equivalent lawn start fertiliser applied at the rate recommended by the manufacturer

To those plants indicated on the planting schedules provide; hardwood stakes as nominated and driven into ground to a depth able to achieve rigid support and to finish a minimum of 300-1000mm above finished levels

All planter beds adjacent to lawn areas to have flush timber edging

8. Turfing
Make good all turfed areas along lowe area of site to match existing when all construction works have been completed.

9. Structural
All structural details whatsoever to Engineer's details.

The Landscape Contractor shall maintain the contract areas by accepted horticultural practices as well as rectifying any defects that become apparent in the works under normal use. The Landscape Contractor shall maintain the works and make good all defects for a period of thirleen (13) weeks after the date of practical completion. Practical completion of the landscape works shall include but not be limited to the replacement of plants which have failed or been damaged or stolen during work under the contract. Landscape maintenance shall include but not be limited to the following: watering, rubbish removal, spraying and wiping leaf surfaces, replacing failed plants, maintaining mulch, pruning, insect and disease control, cleaning of surrounding areas. Mow the turf when it is established at regular interval A thainfail an average the opt of 1911 the CATE

No. 08/71 These plans form part of the above Construction Certificate as issued by


Greg Hough of Get Certified Building Services Pty Ltd Accreditation No: BPB0186

Drawing schedule

Sheet 1: Site plan Sheet 2: Detail pool plan

Sheet 3: Landscape planting plan

Sheet 4: Sediment control plan / site management plan



PAUL SCRIVENER

LANDSCAPE ARCHITECT

PO Box 795 MANLY NSW 1655 ACN 070 598 882 ABN 56 070 598 882

PHONE: 02 9907.8011
FAX: 02 9948 9527
Mobile: 0417 258 629
www.scrivener-design.com
EMAIL: paul@scrivener-design.com


23 THYRA RD, PALMBEAGE


PATE 1:50@A1 OB REF: 07/1176/DA SHEET NO: 1 OF 4

BUILDER MUST VERIFY ALL DIMENSIONS OF THE SITE BEFORE WORK COMMENCES.
FIGURED DIMENSIONS SHOULD BE USED IN PREFERENCE TO THOSE SCALED OFF.


The concepts, design, details and information described in the drawing are copyright. Other than for the purpose prescribed under the Copyright Act, no part of it may in any form or by any means be used or reproduced without prior written permission. AMENDMENTS

New work shown coloured







Planting plan 1:50




Palm transplanting detail n.t.s




Tree planting detail n.t.s




Shrub planting detail n.t.s



Timber edge detail n.t.s.



Soil preparation detail n.t.s.



Planting schedule

Symbol	Botanical Name	Common Name	No.	Cont.	Staking	Mature
Trees						
BAS	Banksia serrata	Old Man Banksia	1	100Lt	2x38x38x1800	4-6.0M
Shrubs						
KA	Kunzea ambigua	Butterfly Bush	1	45Lt	nit	2-3M
SYD	Syzygium paniculatum 'Dwarf	Dwarf Lilly Pilly	8	45Lt	nil	3-4.0M
WF	Westringia fruticosa	Coastal Rosemary	8	300mm	nil	1.5M
Ferns/Pair	ns/Succulents					
CAA	Cyathea australis	Tree fem	5	25Lt	nil	2-4.0M
YUC	Yucca 'Elephantipes'	Giant Yucca	2	300mm	nil	1.5M
Groundco	vers/Climbers					
HIS	Hibbertia scandens	Guinea Flower	2	200mm	nil	4.0M
PP	Pandorea pandorana	Wonga Wonga Vine	7	200mm	nil	2.5M
VH	Viola hederacea	Native violets	100	tubes	nil	0.1M

Planting schedule complies with 80% indigenous content in overall canopy area, species variety and species number

Notes

Site preparation
 Any existing trees and vegetation to be retained shall be preserved and protected from damage of any sort during the execution of landscape work. In particular, root systems of existing plants must not be disturbed if possible. Any nearby site works should be carried carefully using hand

To ensure the survival and growth of existing trees during landscaping works, protect by fencing or armouring where necessary. Trees shall not be removed or lopped unless specific written approval to do so is given or is indicated on plan. Storage of materials, mixing of materials, vehicle parking, disposal of liquids, machinery repairs and refueling, site office and sheds, and the lighting of fires shall not occur within three (3) metres of any existing trees. Do not stockpile soil, rubble or other debris cleared from the site, or building materials, within the dripline of existing trees. Vehicular access shall not be permitted within three (3)

metres of any tree.

2. Soil preparation

All proposed planting areas to be deep ripped to 200mm and day soils to be treated with day breaker.. Harvested existing top soil from site and store on site. Mix with 25% A.N.L. Greenlife compost or approved equivalent. Apply at least 100mm soil depth to planting areas. Additional soil to be 75mm depth of good quality planting mix to be imported and combined with 25mm depth A.N.L. Greenlife compost or approved equivalent. To be worked in with rotary hoe. Care taken to hand cultivate in any area where existing tree roots exist to preserve health of trees.

3. New plantings
Newly planted trees and large shrubs should be secured to stakes with hessian ties to prevent rocking by wind. Planting holes for plant material should be large enough in size to take root ball with additional space to take back filling of good quality planting mix.

Mature heights of planting as shown on planting schedule show the greatest height possible in ideal conditions. These heights are subject to particular site conditions, possible container environments and intended hedging or pruning for functional requirements such as available planting width, intended access under branches and solar

4. Mulching
All planting areas to be mulched with a minimum 100mm thick cover of leaf litter mulch and then all plant areas to be thoroughly soaked with water. All mulch shall be free of vegetative reproductive parts of all

eed species

Fertliser

All planting areas to be fertilised with 9 month 'NPK' slow release fertiliser.

Mass planted areas: allow one slow release Agriform pellet per 5-25 litre plant. All fertilisers to be applied in accordance with the manufacturers instructions.

the manufacturers instructions.

Turfed areas:Supply and install Agriform slow release fertiliser or approved equivalent lawn start fertiliser applied at the rate recommended by the manufacturer

To those plants indicated on the planting schedules provide: hardwood stakes as nominated and driven into ground to a depth able to achieve rigid support and to finish a minimum of 800-1000mm above finished levels

7. Timber edging.
All planter beds adjacent to lawn areas to have flush timber edging

8. Turfing
Make good all turfed areas along lowe area of site to match existing
when all construction works have been completed.

9. Structural

All structural details whatsoever to Engineer's details.

The Landscape Contractor shall maintain the contract areas by accepted horticultural practices as well as rectifying any defects that become apparent in the works under normal use. The Landscape Contractor shall maintain the works and make good all defects for a period of thirteen (13) weeks after the date of practical completion. Practical completion of the landscape works shall include but not be limited to the replacement of plants which have failed or been damaged or stolen during work under the contract. Landscape maintenance shall include but not be limited to the following: watering, rubbish removal, spraying and wiping leaf surfaces, replacing failed plants, maintaining mulch, pruning, insect and disease control, cleaning of surrounding areas. Mow the turf when it is established at regular intervals to maintain an average height of 50mm.


CONSTRUCTION CERTIFICATE

No. OS/T\

These plans form part of the above
Construction Certificate as issued by

Grey Hough of

Greg Hough of
Get Certified Building Services Pty Ltd
Accreditation No: BPB0186



PAUL SCRIVENER

LANDSCAPE ARCHITECT

PO Box 795 MANLY NSW 1655 ACN 070 598 882 ABN 56 070 598 882

PHONE: 02 9907 8011

FAX: 02 9948 9527

MOBILE: 0417 258 629

www.scrivener-design.com

EMAIL: paul@scrivener-design.com

PROJECT: LANDSCAPE DEVELOPMENT AT 23 THYRA RD, PALMBEACH

Dwg: Planting Plan

DATE: 08.05.07 SCALE: 1:50@A1

JOB REF: 07/1176/DA3 SHEET NO: 3 OF 4

ISSUE: B


BUILDER MUST VERIFY ALL DIMENSIONS OF THE SITE BEFORE WORK COMMUNICES.
FIGURED DIMENSIONS SHOULD BE USED IN PREFERENCE TO THOSE SCALED OFF.

Ocopyright is the property of Paul Scrivener Landscape Architects Pty £td A.C.H. 070 538 882 The concepts, design, details and information described in the drawing are copyright. Other than for the purpose prescribed under the Copyright Act, no part of it may in amy form or by any means be used or reproduced without prior written permission.

AMENDMENTS

NORTH**

Job/Hickey/Palmbeach



All work to be constructed to the requirements and satisfaction of the local Council

Soil stockpile areas to be installed as per detail

Before carrying out any internal stormwater pipe laying the drainage contractor is to locate all services on the route of the drainage outlet pipe to the kerb eg Gas, Electricity, Telstra, Water, Sewer and notify the engineer of any level conflicts

Silt fence to be constructed as per detail shown Or by using an approved equivalent measure. The silt fence is to be constructed prior to any other construction activities. It is to be kept in good working order at all times.

When approximately 30% full or as directed by Council's representative, the silt fences are to be cleared of silt and or other built up materials.

OS TIMESTICATE
OS TIMESTON CERTIFICATE
OS TIMESTON OF the above
Construction Certificate as issued by
Grey Hough of



PAUL SCRIVENER

LANDSCAPE ARCHITECT

PO Box 795 MANLY NSW 1655 ACN 070 598 882 ABN 56 070 598 882

PHONE: 02 9907 8011

FAX: 02 9948 9527

MOBILE: 0417 258 629

www.scrivener-design.com

EMAIL: paul@scrivener-design.com

PROJECT: LANDSCAPE DEVELOPMENT AT 23 THYRA RD, PALMBEACH

Dwg: Sedimentation control /
Site management plan

DATE: 08.05.07 SCALE: 1:50@A1

JOB REF: 07/1176/DA4 SHEET NO: 4 OF 4

BUILDER MUST VERIFY ALL DIMENSIONS OF THE SITE BEFORE WORK COMMERCES.
FIGURED DIMENSIONS SHOULD BE USED IN PREFERENCE TO THOSE SCALED OFF.

©Copyright is the property of Paul Scrivener Landscape Architects Pty Ltd A.C.N. 070 558 882
The concepts, design, details and information described in the drawing are copyright. Other than for the purpose prescribed under the Copyright Act, no part of it may in any form or by any means be used or reproduced without prior written permission.

AMENDMENTS NORTH