

Water Management Referral Response

Application Number:	DA2023/1068
Proposed Development:	Demolition works and construction of a vehicle storage facility including a take-away cafe.
Date:	17/08/2023
To:	Claire Ryan
Land to be developed (Address):	Lot 3 DP 617781 , 69 Bassett Street MONA VALE NSW 2103

Reasons for referral

Council's Water Management Officers are required to consider the likely impacts.

Officer comments

Supported

This application was assessed in consideration of:

- Supplied plans and reports;
- Northern Beaches Water Management for Development Policy (WM Policy), and;
- Relevant LEP and DCP clauses;

The proposal seeks consent for demolition and construction on a lot less than 1000 square metres. No subdivision is proposed.

Proposal reduces impervious area and includes a rainwater tank. A planter box is also included in the design and presents an opportunity for onsite water infiltration and water reuse. The applicant is encouraged to make use of this opportunity.

The geotechnical report provided indicates that the water table is likely at a shallow depth and there is a high probability of Acid Sulfate Soil (ASS) occurrence. No bulk excavation is proposed but some soil disturbance will occur. If dewatering is required then the applicant must contact catchment@northernbeaches.nsw.gov.au for advice on Council's groundwater dewatering permit prior to excavating. Any water to be discharged must be compliant with the General Terms of Approval/Controlled Activity permit issued by WaterNSW (if applicable), Landcom's 'Managing Urban Stormwater: Soils and Construction' (2004) (Blue Book), Council's Compliance and Enforcement Policy and legislation including Protection of the Environment Operations Act 1997 and Contaminated Lands Act 1997. All approvals, water discharges and monitoring results are to be documented and kept on site. Copies of all records shall be provided to the appropriate regulatory authority, including Council, upon request.

Sediment and erosion controls must be installed prior to any disturbance of soil on site and maintained until all work is complete and groundcover re-established.

The proposal is therefore supported.

Note: Should you have any concerns with the referral comments above, please discuss these with the Responsible Officer.

Recommended Water Management Conditions:

CONDITIONS TO BE SATISFIED PRIOR TO THE ISSUE OF THE CONSTRUCTION CERTIFICATE

Erosion and Sediment Control Plan

An Erosion and Sediment Control Plan (ESCP) shall be prepared by an appropriately qualified person and implemented onsite prior to commencement. The ESCP must meet the requirements outlined in the Landcom publication Managing Urban Stormwater: Soils and Construction - Volume 1, 4th Edition (2004). The ESCP must include the following as a minimum:

- Site Boundaries and contours
- Approximate location of trees and other vegetation, showing items for removal or retention (consistent with any other plans attached to the application)
- Location of site access, proposed roads and other impervious areas (e.g. parking areas and site facilities)
- Existing and proposed drainage patterns with stormwater discharge points
- Locations and methods of all erosion and sediment controls that must include sediment fences, stabilised site access, materials and waste stockpiles locations, location of any stormwater pits on the site and how they are going to be protected.
- North point and scale.

Details demonstrating compliance are to be submitted to the Certifier for approval prior to the issue of the Construction Certificate.

Reason: Protection of the receiving environment.

CONDITIONS TO BE COMPLIED WITH DURING DEMOLITION AND BUILDING WORK

Installation and Maintenance of Sediment and Erosion Controls

Council proactively regulates construction sites for sediment management.

Sediment and erosion controls must be installed in accordance with Landcom's 'Managing Urban Stormwater: Soils and Construction' (2004) and the Erosion and Sediment Control Plan prior to commencement of any other works on site.

Erosion and sediment controls are to be adequately maintained and monitored at all times, particularly after periods of rain, and shall remain in proper operation until all development activities have been completed and vegetation cover has been re-established across 70 percent of the site, and the remaining areas have been stabilised with ongoing measures such as jute mesh or matting.

Reason: Protection of the receiving environment.

ON-GOING CONDITIONS THAT MUST BE COMPLIED WITH AT ALL TIMES

Dewatering Management

Council proactively regulates construction sites for sediment management.

Discharge of groundwater or tailwater must achieve the following water quality targets in addition to

any conditions/ documentation of this consent, any requirements of the General Terms of Approval/Controlled Activity permit issued by WaterNSW (if applicable), Landcom's 'Managing Urban Stormwater: Soils and Construction' (2004) (Blue Book), Council's Compliance and Enforcement Policy and legislation including Protection of the Environment Operations Act 1997 and Contaminated Lands Act 1997.

Water Quality (<one hour of planned discharge)

Oil and grease, not visible

pH, 6.5-8.5

Total Suspended Solids (TSS), <50mg/L NTU from a meter/grab sample

NOTE: The correlation between NTU and TSS must be established by a NATA accredited laboratory prior to the commencement of dewatering activities.

All records of water discharges and monitoring results are to be documented and kept on site. Copies of all records shall be provided to the appropriate regulatory authority, including Council, upon request.

Tailwater must be discharged to the nearest stormwater pit in accordance with Council's Auspec1 Design Manual and must not spread over any road, footpath and the like. Discharge to the kerb and gutter will not be accepted. If an alternative solution is required, you must contact Council's Catchment Team at catchment@northernbeaches.nsw.gov.au

Reason: Protection of the receiving environment