

5 June 2025



MacKenzie Architects International
736 Pacific Highway
GORDON NSW 2072

Dear Sir/Madam

Application Number: DA2024/0460
Address: Lot 187 DP 16719 , 1 Gondola Road, NORTH NARRABEEN NSW 2101
Lot 188 DP 16719 , 3 Gondola Road, NORTH NARRABEEN NSW 2101
Proposed Development: Demolition works and construction of shoptop housing

Please find attached the Notice of Determination for the above mentioned Application.

You should thoroughly read the Notice of Determination and be aware of any conditions imposed that affect the development and guide the next steps in the process before you can commence works and/or the use.

A copy of the Assessment Report associated with this application is available to view in the Planning and Development > Application Search section of Council's website at www.northernbeaches.nsw.gov.au

If you have any questions regarding the decision or the conditions, please contact Council to speak to the assessment officer or the undersigned on 1300 434 434 or via email quoting the Application number, property address and the description of works to council@northernbeaches.nsw.gov.au

Regards,



Steven Findlay
Manager Development Assessments

NOTICE OF DETERMINATION OF A DEVELOPMENT APPLICATION

Application Number:	DA2024/0460 PAN-425653
Applicant:	MacKenzie Architects International 736 Pacific Highway GORDON NSW 2072
Property:	Lot 187 DP 16719 1 Gondola Road NORTH NARRABEEN NSW 2101 Lot 188 DP 16719 3 Gondola Road NORTH NARRABEEN NSW 2101
Description of Development:	Demolition works and construction of shoptop housing
Determination:	Approved Consent Authority: Northern Beaches Local Planning Panel
Date of Determination:	04/06/2025
Date from which the consent operates:	05/06/2025
Date on which the consent lapses:	05/06/2030

Under section 4.18(1) of the EP&A Act, notice is given that the above development application has been determined by the granting of consent using the power in section 4.16(1)(a) of the EP&A Act, subject to the conditions specified in this notice.

Reasons for approval

The development proposal meets the Objects of the Environmental Planning and Assessment Act 1979, contained in Section 1.3, having considered the relevant provisions under s.4.15 of the aforementioned Act. Consequently, the development is considered to be in the public interest, subject to conditions.

Community views

The application was notified in accordance with Council's Community Participation Plan and the Environmental Planning and Assessment Regulation 2021. Any submissions received representing community views were considered as part of the assessment of the application. Conditions of consent included within this Notice of Determination have been applied to ensure that the development satisfies the Objects of the Environmental Planning and Assessment Act and will not result in unacceptable environmental impacts.

Request a review of the determination

If you are dissatisfied with this determination, you may request a review of the determination:

- You do not have the right to request a review of the determination under section 8.3 of the EP&A Act if you are excluded from those developments listed under Section 8.2(2) of the EP&A Act.
- You may request a review of the consent authority's decision under section 8.3(1) of the EP&A Act. The application must be lodged to and determined by the consent authority within 6 months from the date that the original determination was registered on the NSW Planning Portal. Prospective applicants for a Review of Determination are encouraged to lodge a review application with Council as soon as possible, to enable a full review and determination.

Rights to appeal

You have a right under section 8.7 of the EP&A Act to appeal to the Court within 6 months after the date on which the determination appealed against is notified or registered on the NSW planning portal.

Objector's right of appeal against the determination

An objector who is dissatisfied with the consent authority's determination to grant consent, in relation to Designated Development only has the right to appeal to the Court against the determination under section 8.8 of the EP&A Act within 28 days after the date that the objector was notified of the determination appealed against.

Dictionary

The Dictionary at the end of this consent defines words and expressions for the purposes of this determination.

Signed

On behalf of the Consent Authority



Name

Steven Findlay, Manager Development Assessments

Date

04/06/2025

Terms and Reasons for Conditions

Under section 88(1)(c) of the EP&A Regulation, the consent authority must provide the terms of all conditions and reasons for imposing the conditions other than the conditions prescribed under section 4.17(11) of the EP&A Act. The terms of the conditions and reasons are set out below.

GENERAL CONDITIONS

1. Approved Plans and Supporting Documentation

Development must be carried out in accordance with the following approved plans (stamped by Council) and supporting documentation, except where the conditions of this consent expressly require otherwise.

Approved Plans				
Plan Number	Revision Number	Plan Title	Drawn By	Date of Plan
Architectural Plans				
A0004	C	Demolition Plan	Mackenzie Architects International	25 October 2024
A0005	C	Site Plan	Mackenzie Architects International	25 October 2024
A1001	F	Basement Plan	Mackenzie Architects International	14 March 2025
A1002	F	Ground Floor Plan	Mackenzie Architects International	14 March 2025
A1003	C	First Floor Plan	Mackenzie Architects International	25 October 2024
A1004	C	Second Floor Plan	Mackenzie Architects International	25 October 2024
A1005	C	COS Floor Plan	Mackenzie Architects International	25 October 2024
A1006	C	Roof Plan	Mackenzie Architects International	25 October 2024
A2001	F	North & East Elevations	Mackenzie Architects International	14 March 2025
A2002	E	South & West Elevations	Mackenzie Architects International	5 February 2025
A2101	F	Sections 01	Mackenzie Architects International	14 March 2025
A2102	E	Sections 02	Mackenzie Architects International	5 February 2025
A3009	E	Sample Board	Mackenzie Architects International	5 February 2025
Landscape Plans				
1 of 4	C	Basement plan/Entry level	Paul Scrivener Landscape	22 October 2024

2 of 4	C	Level 1 landscape plan	Paul Scrivener Landscape	22 October 2024
3 of 4	C	Roof Plan	Paul Scrivener Landscape	22 October 2024
4 of 4	C	Planting plans	Paul Scrivener Landscape	22 October 2024

Approved Reports and Documentation			
Document Title	Version Number	Prepared By	Date of Document
Concept Stormwater Management Plans	P2310036	Martens & Associates Pty Ltd	13 December 2024
Flood Risk Assessment and Flood Emergency Response Plan (FERP)	P2310036JR03V03	Martens & Associates Pty Ltd	7 March 2025
Hydrological Assessment and Groundwater Dewatering Management Plan	P2310036JR05V02	Martens & Associates Pty Ltd	4 February 2025
Acid Sulfate Soils Management Plan	P2310036JR03V01	Martens & Associates Pty Ltd	11 April 2024
Geotechnical and Acid Sulfate Soil Assessment	P2310036JR02V01	Martens & Associates Pty Ltd	9 April 2024
Site Contamination Assessment	P2310036JR01V01	Martens & Associates Pty Ltd	1 May 2025
DA Acoustic Assessment Report	230697, Revision 1	Pulse White Noise Acoustics Pty Ltd	18 June 2024
Development Application Access and Adaptability Report	Project No 15/19	Obvius Access Consultants	21 October 2024
Building Code of Australia Compliance Report	220045A	Greenfield Certifiers Pty Ltd	16 October 2024
Arboricultural Assessment Report and Tree Protection Specification	231214, Revision A	Outdoor Interests Pty Ltd	14 December 2023
BASIX Certificate	1742159M_03	Eco Certificates Pty Ltd	24 October 2024
Waste Management Plan '1-3 Gondola Road North Narrabeen 2101'	-	-	-

In the event of any inconsistency between the approved plans, reports and documentation, the approved plans prevail.

In the event of any inconsistency between the approved plans and a condition of this consent, the condition prevails.

Reason: To ensure all parties are aware of the approved plans and supporting documentation that applies to the development.

2. Compliance with Other Department, Authority or Service Requirements

The development must be carried out in compliance with all recommendations and requirements, excluding general advice, within the following:

Other Department, Authority or Service	EDMS Reference	Dated
Ausgrid	Referral - Ausgrid	N/A
WaterNSW	General Terms of Approval - WaterNSW (Reference Number: IDAS1158640)	25 February 2025

(NOTE: For a copy of the above referenced document/s, please see Application Tracking on Council's website www.northernbeaches.nsw.gov.au)

Reason: To ensure the work is carried out in accordance with the determination and the statutory requirements of other departments, authorities or bodies.

3. No Approval for Land Use for the Commercial Tenancies

No approval is granted under this Development Consent for any use of the ground floor commercial tenancies. A separate consent must be obtained prior to the use of the commercial premises.

Reason: To ensure compliance with the Warringah Local Environmental Plan 2011.

4. Approved Land Use

Nothing in this consent shall authorise the use of the site for any land use beyond the definition of shop top housing. The Pittwater Local Environmental Plan 2014 defines this land use as follows:

- **shop top housing** means one or more dwellings located above the ground floor of a building, where at least the ground floor is used for commercial premises or health services facilities.

Note.

Shop top housing is a type of residential accommodation—see the definition of that term in this Dictionary.

Any variation to the approved land use and/occupancy of any unit beyond the scope of the above definition will require the submission to Council of a new development application.

Reason: To ensure compliance with the terms of this consent.

5. No Approval for Strata Subdivision

No approval is granted for Strata Subdivision.

Note: This condition does not preclude the applicant from obtaining a strata subdivision approval pursuant to State Environmental Planning Policy (Exempt and Complying Development Codes) 2008.

Reason: The applicant has not sought consent for Strata Subdivision.

6. Prescribed conditions (Demolition):

(a) A sign must be erected in a prominent position on any site on which building work, subdivision work or demolition work is being carried out:

- (i) showing the name of the principal contractor (if any) for any building work and a telephone number on which that person may be contacted outside working hours, and
- (ii) stating that unauthorised entry to the work site is prohibited.

Any such sign is to be maintained while the building work, subdivision work or demolition work is being carried out, but must be removed when the work has been completed.

(b) Residential building work within the meaning of the Home Building Act 1989 must not be carried out unless the Principal Certifier for the development to which the work relates (not being the Council) has given the Council written notice of the following information:

- (i) in the case of work for which a principal contractor is required to be appointed:
 - A. the name and licence number of the principal contractor, and
 - B. the name of the insurer by which the work is insured under Part 6 of that Act,
- (ii) in the case of work to be done by an owner-builder:
 - A. the name of the owner-builder, and
 - B. if the owner-builder is required to hold an owner-builder permit under that Act, the number of the owner-builder permit.

If arrangements for doing the residential building work are changed while the work is in progress so that the information notified under becomes out of date, further work must not be carried out unless the Principal Certifier for the development to which the work relates (not being the Council) has given the Council written notice of the updated information.

(c) Development that involves an excavation that extends below the level of the base of the footings of a building on adjoining land, the person having the benefit of the development consent must, at the person's own expense:

- (i) protect and support the adjoining premises from possible damage from the excavation, and
- (ii) where necessary, underpin the adjoining premises to prevent any such damage.
- (iii) must, at least 7 days before excavating below the level of the base of the footings of a building on an adjoining allotment of land, give notice of intention to do so to the owner of the adjoining allotment of land and furnish particulars of the excavation to the owner of the building being erected or demolished.
- (iv) the owner of the adjoining allotment of land is not liable for any part of the cost of work carried out for the purposes of this clause, whether carried out on the allotment of land being excavated or on the adjoining allotment of land.

Reason: Legislative Requirement.

7. Prescribed Conditions

- (a) All building works must be carried out in accordance with the requirements of the Building Code of Australia (BCA).

- (b) BASIX affected development must comply with the schedule of BASIX commitments specified within the submitted BASIX Certificate (demonstrated compliance upon plans/specifications is required prior to the issue of the Construction Certificate);
- (c) A sign must be erected in a prominent position on any site on which building work, subdivision work or demolition work is being carried out:
 - (i) showing the name, address and telephone number of the Principal Certifier for the work, and
 - (ii) showing the name of the principal contractor (if any) for any building work and a telephone number on which that person may be contacted outside working hours, and
 - (iii) stating that unauthorised entry to the work site is prohibited.

Any such sign is to be maintained while the building work, subdivision work or demolition work is being carried out, but must be removed when the work has been completed.

- (d) Residential building work within the meaning of the Home Building Act 1989 must not be carried out unless the Principal Certifier for the development to which the work relates (not being the Council) has given the Council written notice of the following information:
 - (i) in the case of work for which a principal contractor is required to be appointed:
 - A. the name and licence number of the principal contractor, and
 - B. the name of the insurer by which the work is insured under Part 6 of that Act,
 - (ii) in the case of work to be done by an owner-builder:
 - A. the name of the owner-builder, and
 - B. if the owner-builder is required to hold an owner-builder permit under that Act, the number of the owner-builder permit.

If arrangements for doing the residential building work are changed while the work is in progress so that the information notified under becomes out of date, further work must not be carried out unless the Principal Certifier for the development to which the work relates (not being the Council) has given the Council written notice of the updated information.

- (e) Development that involves an excavation that extends below the level of the base of the footings of a building on adjoining land, the person having the benefit of the development consent must, at the person's own expense:
 - (i) protect and support the adjoining premises from possible damage from the excavation, and
 - (ii) where necessary, underpin the adjoining premises to prevent any such damage.
 - (iii) must, at least 7 days before excavating below the level of the base of the footings of a building on an adjoining allotment of land, give notice of intention to do so to the owner of the adjoining allotment of land and furnish particulars of the excavation to the owner of the building being erected or demolished.
 - (iv) the owner of the adjoining allotment of land is not liable for any part of the cost of work carried out for the purposes of this clause, whether carried out on the allotment of land being excavated or on the adjoining allotment of land.

In this clause, allotment of land includes a public road and any other public place.

Reason: Legislative requirement.

8. General requirements (Demolition):

(a) Unless authorised by Council:

Demolition and excavation works are restricted to:

- 8.00 am to 5.00 pm Monday to Friday only.

(Excavation work includes the use of any excavation machinery and the use of jackhammers, rock breakers, excavators, loaders and the like, regardless of whether the activities disturb or alter the natural state of the existing ground stratum or are breaking up/removing materials from the site).

(b) At all times after the submission a Notice of Commencement to Council, a copy of the Development Consent is to remain onsite at all times until completion of demolition works. The consent shall be available for perusal of any Authorised Officer.

(c) Where demolition works have been completed and new construction works have not commenced within 4 weeks of the completion of the demolition works that area affected by the demolition works shall be fully stabilised and the site must be maintained in a safe and clean state until such time as new construction works commence.

(d) Onsite toilet facilities (being either connected to the sewer or an accredited sewer management facility) for workers are to be provided for construction sites at a rate of 1 per 20 persons.

(e) The applicant shall bear the cost of all works that occur on Council's property.

(f) No building, demolition, excavation or material of any nature shall be placed on Council's footpaths, roadways, parks or grass verges without Council Approval.

(g) Demolition materials and builders' wastes are to be removed to approved waste/recycling centres.

(h) All sound producing plant, equipment, machinery or fittings will not exceed more than 5dB(A) above the background level when measured from any property boundary and will comply with the Environment Protection Authority's NSW Industrial Noise Policy.)

(i) No trees or native shrubs or understorey vegetation on public property (footpaths, roads, reserves, etc.) or on the land to be developed shall be removed or damaged during construction unless specifically approved in this consent including for the erection of any fences, hoardings or other temporary works.

Reason: To ensure that works do not interfere with reasonable amenity expectations of residents and the community.

9. General Requirements

(a) Unless authorised by Council:

Building construction and delivery of material hours are restricted to:

- 7.00 am to 5.00 pm inclusive Monday to Friday,
- 8.00 am to 1.00 pm inclusive on Saturday,
- No work on Sundays and Public Holidays.

Demolition and excavation works are restricted to:

- 8.00 am to 5.00 pm Monday to Friday only.

(Excavation work includes the use of any excavation machinery and the use of jackhammers, rock breakers, excavators, loaders and the like, regardless of whether the activities disturb or alter the natural state of the existing ground stratum or are breaking up/removing materials from the site).

- (b) Should any asbestos be uncovered on site, its demolition and removal must be carried out in accordance with WorkCover requirements and the relevant Australian Standards.
- (c) At all times after the submission the Notice of Commencement to Council, a copy of the Development Consent and Construction Certificate is to remain onsite at all times until the issue of an Occupation Certificate. The consent shall be available for perusal of any Authorised Officer.
- (d) Where demolition works have been completed and new construction works have not commenced within 4 weeks of the completion of the demolition works that area affected by the demolition works shall be fully stabilised and the site must be maintained in a safe and clean state until such time as new construction works commence.
- (e) Onsite toilet facilities (being either connected to the sewer or an accredited sewer management facility) for workers are to be provided for construction sites at a rate of 1 per 20 persons.
- (f) Prior to the release of the Construction Certificate, payment of the following is required:
 - i) Long Service Levy - Payment should be made to Service NSW (online or in person) or alternatively to Northern Beaches Council in person at a Customer Service Centre. Payment is not required where the value of the works is less than \$250,000. The Long Service Levy is calculated on 0.25% of the building and construction work. The levy rate and level in which it applies is subject to legislative change. The applicable fee at the time of payment of the Long Service Levy will apply.
 - ii) Section 7.11 or Section 7.12 Contributions Plan – Payment must be made to Northern Beaches Council. Where the subject land to which the development is proposed is subject to either a Section 7.11 or 7.12 Contributions Plan, any contribution to which the development is liable under the respective plan that applies is to be paid to Council. The outstanding contribution will be indexed at time of payment in accordance with the relevant Contributions Plan.
 - iii) Housing and Productivity Contribution - Payment must be made on the NSW Planning Portal for development to which this contribution applies. The amount payable is subject to indexation at the time of payment.
- (g) The applicant shall bear the cost of all works associated with the development that occurs on Council's property.
- (h) No skip bins, building materials, demolition or excavation waste of any nature, and no hoist, plant or machinery (crane, concrete pump or lift) shall be placed on Council's footpaths, roadways, parks or grass verges without Council Approval.
- (i) Demolition materials and builders' wastes are to be removed to approved waste/recycling centres.
- (j) No trees or native shrubs or understorey vegetation on public property (footpaths, roads, reserves, etc.), on the land to be developed, or within adjoining properties,

shall be removed or damaged during excavation or construction unless specifically approved in this consent including for the erection of any fences, hoardings or other temporary works.

(k) Prior to the commencement of any development onsite for:

- i) Building/s that are to be erected
- ii) Building/s that are situated in the immediate vicinity of a public place and is dangerous to persons or property on or in the public place
- iii) Building/s that are to be demolished
- iv) For any work/s that is to be carried out
- v) For any work/s that is to be demolished

The person responsible for the development site is to erect or install on or around the development area such temporary structures or appliances (wholly within the development site) as are necessary to protect persons or property and to prevent unauthorised access to the site in order for the land or premises to be maintained in a safe or healthy condition. Upon completion of the development, such temporary structures or appliances are to be removed within 7 days.

(l) A "Road Opening Permit" must be obtained from Council, and all appropriate charges paid, prior to commencement of any work on Council property. The owner/applicant shall be responsible for all public utilities and services in the area of the work, shall notify all relevant Authorities, and bear all costs associated with any repairs and/or adjustments as those Authorities may deem necessary.

(m) The works must comply with the relevant Ausgrid Network Standards and SafeWork NSW Codes of Practice.

(n) Requirements for new swimming pools/spas or existing swimming pools/spas affected by building works.

- (1) Child resistant fencing is to be provided to any swimming pool or lockable cover to any spa containing water and is to be consistent with the following;

Relevant legislative requirements and relevant Australian Standards (including but not limited) to:

- (i) Swimming Pools Act 1992
- (ii) Swimming Pools Amendment Act 2009
- (iii) Swimming Pools Regulation 2018
- (iv) Australian Standard AS1926 Swimming Pool Safety
- (v) Australian Standard AS1926.1 Part 1: Safety barriers for swimming pools
- (vi) Australian Standard AS1926.2 Part 2: Location of safety barriers for swimming pools.

- (2) A 'KEEP WATCH' pool safety and aquatic based emergency sign, issued by Royal Life Saving is to be displayed in a prominent position within the pool/spa area.

- (3) Filter backwash waters shall be conveyed to the Sydney Water sewerage system in sewered areas or managed on-site in unsewered areas in a manner that does not cause pollution, erosion or run off, is separate from the irrigation area for any wastewater system and is separate from any onsite stormwater management system.

- (4) Swimming pools and spas must be registered with the Division of Local Government.

Reason: To ensure that works do not interfere with reasonable amenity expectations of residents and the community.

10. Parking Enclosure

No parking spaces, or access thereto, shall be constrained or enclosed by any form of structure such as fencing, cages, walls, storage space, or the like, without prior consent from Council.

Reason: To ensure accessibility is maintained.

FEES / CHARGES / CONTRIBUTIONS

11. Policy Controls

Northern Beaches Section 7.12 Contributions Plan 2024

A monetary contribution of \$91,668.15 is payable to Northern Beaches Council for the provision of local infrastructure and services pursuant to section 7.12 of the Environmental Planning & Assessment Act 1979 and the Northern Beaches Section 7.12 Contributions Plan (as amended).

The monetary contribution is based on a development cost of \$9,166,815.00.

The total amount payable will be adjusted at the time the payment is made, in accordance with the provisions of the Northern Beaches Section 7.12 Contributions Plan (as amended).

Details demonstrating compliance, by way of written receipts issued by Council, are to be submitted to the Certifier prior to issue of any Construction Certificate or, if relevant, the Subdivision Certificate (whichever occurs first).

A copy of the Contributions Plan is available for inspection at 725 Pittwater Road, Dee Why or on Council's website at Northern Beaches Council - Development Contributions.

Reason: To provide for contributions in accordance with the Contribution Plan to fund the provision of new or augmented local infrastructure and services.

12. Security Bond

A bond (determined from cost of works) of \$10,000 and an inspection fee in accordance with Council's Fees and Charges paid as security are required to ensure the rectification of any damage that may occur to the Council infrastructure contained within the road reserve adjoining the site as a result of construction or the transportation of materials and equipment to and from the development site.

An inspection fee in accordance with Council adopted fees and charges (at the time of payment) is payable for each kerb inspection as determined by Council (minimum (1) one inspection).

All bonds and fees shall be deposited with Council prior to Construction Certificate or demolition work commencing, and details demonstrating payment are to be submitted to the Certifier prior to the issue of the Construction Certificate.

To process the inspection fee and bond payment a Bond Lodgement Form must be completed

with the payments (a copy of the form is attached to this consent and alternatively a copy is located on Council's website at www.northernbeaches.nsw.gov.au).

Reason: To ensure adequate protection of Council's infrastructure.

13. **Housing and productivity contribution - Development consents**

1. The housing and productivity contribution (HPC) set out in the table below, but as adjusted in accordance with condition 2, is required to be made:

Contribution Type	Amount
Housing and Productivity Contribution	\$ 130,454.40.
Total:	\$ 130,454.40.

2. The amount payable at the time of payment is the amount shown in condition 1 as the total housing and productivity contribution adjusted by multiplying it by:

highest PPI number

consent PPI number

where—

highest PPI number is the highest PPI number for a quarter following the June quarter 2023 and up to and including the 2nd last quarter before the quarter in which the payment is made.

consent PPI number is the PPI number last used to adjust HPC rates when consent was granted.

June quarter 2023 and PPI have the meanings given in clause 22 (4) of the Environmental Planning and Assessment (Housing and Productivity Contribution) Order 2023.

If the amount adjusted in accordance with this condition is less than the amount at the time consent is granted, the higher amount must be paid instead.

3. The HPC must be paid before the issue first construction certificate in relation to the development, or before the commencement of any work authorised by this consent (if no construction certificate is required). However, if development is any of the kinds set out in the table below, the total housing and productivity contribution must be paid as set out in the table:

Development	Time by which HPC must be paid
Development consisting only of residential subdivision within the meaning of the HPC Order	Before the issue of the first subdivision certificate
High-density residential development within the meaning of the HPC Order for which no	Before the issue of the first strata certificate

construction certificate is required	
Development that consists only of residential strata subdivision (within the meaning of the HPC Order) or only of residential strata subdivision and a change of use of an existing building	Before the issue of the first strata certificate
Manufactured home estate for which no construction certificate is required	Manufactured home estate for which no construction certificate is required

4. The HPC must be paid using the NSW planning portal (<https://pp.planningportal.nsw.gov.au/>).

5. If the Minister administering the Environmental Planning and Assessment Act 1979 agrees, the HPC (apart from any transport project component) may be made, instead of as a monetary contribution, in the following ways:
 - a) the dedication or provision of land for the purpose of regional infrastructure in the region in which the development will be carried out,
 - b) the carrying out of works for the purpose of regional infrastructure in the region in which the HPC development will be carried out.

If the HPC is made partly as a monetary contribution, the amount of the part payable is the amount of the part adjusted in accordance with condition 2 at the time of payment.

6. Despite condition 1, a housing and productivity contribution is not required to be made to the extent that a planning agreement excludes the application of Subdivision 4 of Division 7.1 of the Environmental Planning and Assessment Act 1979 to the development, or the Environmental Planning and Assessment (Housing and Productivity Contribution) Order 2023 exempts the development from the contribution. The amount of the contribution may also be reduced under the order, including if payment is made before 1 July 2025.

Reason: Statutory requirement.

BUILDING WORK – BEFORE ISSUE OF A CONSTRUCTION CERTIFICATE

14. **On Slab Landscape Works**

Details shall be submitted to the Certifier prior to the issue of the Construction Certificate indicating the proposed method of waterproofing and drainage to all planters over slab, over which soil and planting is being provided. Landscape treatment details shall be submitted to the Certifier prior to the issue of the Construction Certificate indicating the proposed soil type, planting, automatic irrigation, and services connections. The following soil depths are required to support landscaping: as detailed on the Landscape Plans.

Design certification shall be submitted to the Certifier by a qualified Structural Engineer, that the planters are designed structurally to support the 'wet' weight of landscaping (soil, materials

and established planting).

Reason: To ensure appropriate soil depth for planting and ensure waterproofing and drainage is installed.

15. Flood effects caused by development

There is to be no filling of the land or any other reduction of the available flood storage which results in a net loss of storage below the 1% AEP flood level of 3.90m AHD.

Details demonstrating compliance are to be submitted to the Principal Certifier for approval.

Reason: To reduce the impact of flooding and flood liability on owners and occupiers of flood-prone property and reduce public and private losses in accordance with Council and NSW Government policy.

16. Building components and structural soundness

All new development below the Flood Planning Level of 4.40m AHD shall be designed and constructed from flood compatible materials.

The shelter in place refuge must be designed to ensure structural integrity up to the Probable Maximum Flood level of 4.40m AHD, with the remainder of the new development designed to ensure structural integrity up to the Flood Planning Level of 3.90m AHD. The forces of floodwater, debris load, wave action, buoyancy and immersion must all be considered.

All new and existing electrical equipment, power points, wiring and connections must be located above the Flood Planning Level of 4.40m AHD, protected from flood water or have residual current devices installed to cut electricity supply during flood events.

Details demonstrating compliance are to be submitted to the Principal Certifier for approval.

Reason: To reduce the impact of flooding and flood liability on owners and occupiers of flood-prone property and reduce public and private losses in accordance with Council and NSW Government policy.

17. Floor levels

New floor levels within the development shall be set at or above the Flood Planning Level of 4.40m AHD.

Details demonstrating compliance are to be submitted to the Principal Certifier for approval.

Reason: To reduce the impact of flooding and flood liability on owners and occupiers of flood-prone property and reduce public and private losses in accordance with Council and NSW Government policy.

18. Car parking

All access, ventilation and any other potential water entry points, including entry ramp crests to the basement car park shall be at or above the Flood Planning Level of 4.40m AHD.

Details demonstrating compliance are to be submitted to the Principal Certifier for approval.

Reason: To reduce the impact of flooding and flood liability on owners and occupiers of flood-prone property and reduce public and private losses in accordance with Council and NSW

Government policy.

19. **Emergency response**

The shelter-in-place refuge must:

- a) Have a floor level at or above the Probable Maximum Flood level of 4.89m AHD; and
- b) Have a floor space that provides at least 2m² per person; and
- c) Be intrinsically accessible to all people on the site, plainly evident, and self-directing, with sufficient capacity of access routes for all occupants without reliance on electrical means.

Details demonstrating compliance are to be submitted to the Principal Certifier for approval.

Reason: To reduce the impact of flooding and flood liability on owners and occupiers of flood-prone property and reduce public and private losses in accordance with Council and NSW Government policy.

20. **Fencing**

New fencing (including pool fencing, boundary fencing, balcony balustrades and accessway balustrades) shall be open to allow for the unimpeded movement of flood waters. It must be designed with a minimum of 50% open area along any straight length, from the natural ground level up to the 1% AEP flood level. Openings shall be a minimum of 75mm x 75mm.

Details demonstrating compliance are to be submitted to the Principal Certifier for approval.

Reason: To reduce the impact of flooding and flood liability on owners and occupiers of flood-prone property and reduce public and private losses in accordance with Council and NSW Government policy.

21. **Storage of Goods**

Storage areas for hazardous or potentially polluting materials shall not be located below the Flood Planning Level of 4.40m AHD unless adequately protected from floodwaters in accordance with industry standards.

Details demonstrating compliance are to be submitted to the Principal Certifier for approval.

Reason: To reduce the impact of flooding and flood liability on owners and occupiers of flood-prone property and reduce public and private losses in accordance with Council and NSW Government policy.

22. **Stormwater Disposal Details**

The Applicant is to provide a certification of drainage plans detailing the provision of stormwater disposal in accordance with Northern Beaches Council's Water Management for Development Policy, and generally in accordance with the concept drainage plans prepared by Martens, drawing number PS01-A000, PS01-E100, PS01-E101, PS01-E200, PS01-E600, dated 13 December 2024. Detailed drainage plans are to be prepared by a suitably qualified Civil Engineer, who has membership to Engineers Australia, National Engineers Register (NER) or Professionals Australia (RPENG) and registered in the General Area of Practice for civil engineering.

Detailed drainage plans, including engineering certification, are to be submitted to the Certifier for approval prior to the issue of the Construction Certificate.

Reason: To ensure appropriate provision for the disposal of stormwater and stormwater management arising from the development.

23. Erosion and Sediment Control Plan

An Erosion and Sediment Control Plan (ESCP) shall be prepared by an appropriately qualified person and implemented onsite prior to commencement. The ESCP must meet the requirements outlined in the Landcom publication Managing Urban Stormwater: Soils and Construction - Volume 1, 4th Edition (2004). The ESCP must include the following as a minimum:

- Site Boundaries and contours
- Approximate location of trees and other vegetation, showing items for removal or retention (consistent with any other plans attached to the application)
- Location of site access, proposed roads and other impervious areas (e.g. parking areas and site facilities)
- Existing and proposed drainage patterns with stormwater discharge points
- Locations and methods of all erosion and sediment controls that must include sediment fences, stabilised site access, materials and waste stockpiles locations, location of any stormwater pits on the site and how they are going to be protected.
- North point and scale.

Details demonstrating compliance are to be submitted to the Certifier for approval prior to the issue of the Construction Certificate.

Reason: Protection of the receiving environment.

24. Detailed Design of Stormwater Treatment Measures

A certificate from a Civil Engineer, stating that the stormwater treatment measures have been designed in accordance with the Concept Stormwater Management Plan prepared by Martens & Associates (project P2310036, revision D dated 13/12/2024) and Council's Water Management for Development Policy.

The certificate shall be submitted to the Certifier prior to the release of the Construction Certificate.

Reason: Protection of the receiving environment.

25. Car Parking Standards

The driveway/access ramp grades, access and car parking facilities must comply with the Australian/New Zealand Standard AS/NZS 2890.1:2004 - Parking facilities - Off-street car parking. The dimensions of car parking bays and aisle widths in the car park are to comply with Australian/New Zealand Standard for Off-Street Parking AS/NZS 2890.1-2004.

Details demonstrating compliance with this condition are to be submitted to the Principal Certifier prior to the issue of a construction certificate.

Reason: To ensure compliance with Australian Standards relating to manoeuvring, access and parking of vehicles.

26. **Car Parking Finishes**

All driveways, car parking areas and pedestrian paths are to be surfaced and sealed. Details of treatment to these areas are to be submitted to the Principal Certifier prior to issue of the Construction Certificate.

Reason: To provide suitable stormwater disposal and to prevent soil erosion and runoff.

27. **Construction Traffic Management Plan**

A Construction Traffic Management Plan (CTMP) and report shall be prepared by a Transport for NSW accredited person and submitted to and approved by the Northern Beaches Council Traffic Team prior to issue of any Construction Certificate.

The CTMP must address following:

- The proposed phases of construction works on the site, and the expected duration of each construction phase.
- The proposed order in which works on the site will be undertaken, and the method statements on how various stages of construction will be undertaken.
- Make provision for all construction materials to be stored on site, at all times.
- The proposed areas within the site to be used for the storage of excavated materials, construction materials and waste containers during the construction period.
- The proposed method of access to and egress from the site for construction vehicles, including access routes and truck routes through the Council area and the location and type of temporary vehicular crossing for the purpose of minimising traffic congestion and noise in the area, with no access across public parks or reserves being allowed.
- Where access is required across private property not in the direct ownership of the proponent, such as a private road/driveway, community title road or right of way, the CTMP is to include:
 - Evidence of the legal right and terms to use the access route or provide owners consent from the owners/strata/community association.
 - Demonstrate that direct access from a public space/road is not viable for each stage of works.
 - An assessment to be carried out of the physical constraints of the Right of Carriageway to determine the maximum size of vehicle that may access the site via the Right of Carriageway during construction.
 - Unless owner/strata/community associations consent is obtained, vehicles are not to exceed 24 tonnes or 7.5 metres in length (an assessment must be undertaken that the surface is capable of supporting up to 24 tonnes, otherwise the weight limit should be reduced in the CTMP). If consent is obtained, a copy must be included in the CTMP.
 - No construction vehicles, materials or plant are to be located or parked in the private road/driveway, community title road or right of way.
 - How any disruption to other users of the private road/driveway, community title road or right of way will be minimised and all users kept informed of likely disruption where the access will be closed or blocked for any given time.
 - If trees are located within or overhang the access route, a tree protection plan prepared by an Arborist with minimum AQF Level 5 in arboriculture demonstrating how any trees within the Right of Carriageway will be protected from damage by construction vehicles. Should any tree protection measures be required on private land in accordance with AS4970-2009 Protection of trees on development sites, owner's consent must be obtained.
 - A Dilapidation report, including photographic surveys, of the private road/driveway/right of way must be included prior to any works commencing on

the site. The report must detail the physical condition of the private road/driveway/right of way, and any other adjacent private property assets (including trees) or adjacent public property that may be adversely affected by vehicles servicing the development site to undertake works or activity during site works.

- A requirement for Post-Construction Dilapidation Reports, including photos of any damage evident at the time of inspection, to be submitted after the completion of works and prior to the Occupation certificate. The report must:
 - Compare the post-construction report with the pre-construction report,
 - Clearly identify any recent damage or change to the private road/driveway/right of way and whether or not it is likely to be the result of the development works,
 - Should any damage have occurred, identify remediation actions taken.
 - Be submitted to Council with the Occupation Certificate.
- The proposed method of loading and unloading excavation and construction machinery, excavation and building materials, formwork and the erection of any part of the structure within the site. Wherever possible mobile cranes should be located wholly within the site.
- Make provision for parking onsite. All Staff and Contractors are to use any basement parking once available.
- Temporary truck standing/ queuing locations in a public roadway/ domain in the vicinity of the site are not permitted unless approved by Council prior.
- Include a Traffic Control Plan prepared by a person with suitable RMS accreditation for any activities involving the management of vehicle and pedestrian safety.
- The proposed manner in which adjoining property owners will be kept advised of the timeframes for completion of each phase of development/construction process. It must also specify that a minimum Fourteen (14) days notification must be provided to adjoining property owners prior to the implementation of any temporary traffic control measure.
- Include a site plan showing the location of any site sheds, location of requested Work Zones, anticipated use of cranes and concrete pumps, structures proposed on the footpath areas (hoardings, scaffolding or shoring) and any tree protection zones around Council street trees.
- Take into consideration the combined construction activities of other development in the surrounding area. To this end, the consultant preparing the CTMP must engage and consult with developers undertaking major development works within a 250m radius of the subject site to ensure that appropriate measures are in place to prevent the combined impact of construction activities, such as (but not limited to) concrete pours, crane lifts and dump truck routes. These communications must be documented and submitted to Council prior to work commencing on site.
- The proposed method/device to remove loose material from all vehicles and/or machinery before entering the road reserve, any run-off from the washing down of vehicles shall be directed to the sediment control system within the site.
- Specify that the public roadway (including footpath) must be kept in a serviceable condition for the duration of construction. At the direction of Council, undertake remedial treatments such as patching at no cost to Council.
- The proposed method of support to any excavation adjacent to adjoining properties, or the road reserve. The proposed method of support is to be designed and certified by an appropriately qualified and practising Structural Engineer, or equivalent.
- Proposed protection for Council and adjoining properties.
- The location and operation of any on site crane.

The CTMP shall be prepared in accordance with relevant sections of Australian Standard 1742

– “Manual of Uniform Traffic Control Devices”, RMS’ Manual – “Traffic Control at Work Sites”.

All fees and charges associated with the review of this plan is to be in accordance with Council’s Schedule of Fees and Charges and are to be paid at the time that the Construction Traffic Management Plan is submitted.

A copy of the approved CTMP must be kept on-site at all times while work is being carried out.

The development is to be undertaken in accordance with the Construction Traffic Management Plan approved by Northern Beaches Council Traffic Team.

Reason: To ensure public safety and minimise any impacts to the adjoining pedestrian and vehicular traffic systems.

28. **Vehicle Access & Parking**

All internal driveways, vehicle turning areas and vehicle parking space/ loading bay dimensions must be designed and constructed to comply with the relevant section of AS 2890 (Off-street Parking standards).

With respect to this, the following revision(s) must be undertaken;

All internal driveways and vehicle access ramps must have ramp grades and transitions complying with AS 2890.1. To ensure the gradient requirements and height clearances are satisfied, a driveway profile must be prepared for all internal ramps showing ramp lengths, grades, surface RL's and overhead clearances, taken from the crest of the ramp to the base. The driveway profile must be taken along the steepest grade of travel or sections having significant changes in grades, where scraping or height restrictions could potentially occur and is to demonstrate compliance with AS 2890 for the respective type of vehicle.

Plans prepared by a suitably qualified Engineer shall be submitted to the Principal Certifier prior to the issue of a Construction Certificate.

Reason: To ensure compliance with Australian Standards relating to manoeuvring, access and parking of vehicles.

29. **Submission of Engineering Plans**

The developer is to provide Civil Engineering plans for the following:

- Kerb and gutter along the full length of the site frontage in Minarto Lane.
- signposting for A Loading Zone of sufficient length to accommodate Council’s 10.5m waste collection vehicle and a No Parking restriction on the remainder of the western side of Minarto Lane. The Loading Zone to apply on a full time basis
- A No Stopping restriction on the east side of Minarto Lane opposite the site.

These are to be generally in accordance with the civil design approved with the Development Application and Council’s specification for engineering works - AUS-SPEC #1 and or Council’s Minor Works Policy. Details demonstrating compliance are to be submitted to the Principal Certifier prior to the issue of the Construction Certificate.

Section 138 and/or 139 applications are to be submitted to Council for Local Traffic Committee approval.

Reason: To ensure compliance with Council's specification for engineering works.

30. Pedestrian sight distance at property boundary

A pedestrian sight triangle of 2.0 metres by 2.5m metres, in accordance with AS2890.1:2004 is to be provided at the vehicular access to the property and where internal circulation roadways intersect with footpaths or other pedestrian access areas.

Details demonstrating compliance are to be submitted to the Principal Certifier prior to the issue of the Construction Certificate.

Reason: To maintain pedestrian safety.

31. Amendments to the approved plans

The following amendments are to be made to the approved plans:

- The approved Demolition Plan referenced in Condition 1 of this consent must be amended to demonstrate that Tree 6 is located entirely within the subject site, consistent with the Detail & Boundary Identification Survey of Lot 187 & 188 in DP 16719, Located at No. 1-3 Gondola Road, North Narrabeen (prepared by C&A Surveyors, dated 8 March 2024).

Details demonstrating compliance are to be submitted to the Certifier prior to the issue of the Construction Certificate.

Reason: To require amendments to the plans endorsed by the consent authority following assessment of the development.

32. Boundary Identification Survey

A boundary identification survey, prepared by a Registered Surveyor, shall be provided in respect of the subject site.

The plans submitted for the Construction Certificate are to accurately reflect the property boundaries as shown on the boundary identification survey, with setbacks between the property boundaries and the approved works consistent with those nominated on the Approved Plans of this consent.

Details demonstrating compliance are to be submitted to the Certifier prior to the issue of any Construction Certificate.

Reason: To ensure all approved works are constructed within the subject site and in a manner anticipated by the development consent.

33. Services and Fire Hydrant Enclosure

Prior to the issue of a Construction Certificate for works above ground level, Council's Executive Manager of Development Assessment is to be provided with plans to their satisfaction demonstrating that all Services (Gas meter, water meter & fire hydrant and sprinkler booster valves and the like) are enclosed in a manner that compliments the building, do not visually dominate the streetscape and are in accordance with the requirements of the BCA.

An updated landscape plan is also to be provided to reflect the changes resulting from the fire hydrant and sprinkler booster detailed design.

Reason: To ensure essential services are appropriately screened.

34. Submission Roads Act Application for Civil Works in the Public Road

The Applicant is to submit an application for approval for infrastructure works on Council's roadway. Engineering plans for the new development works within the road reserve and this development consent are to be submitted to Council for approval under the provisions of Sections 138 and 139 of the Roads Act 1993.

The application is to include Civil Engineering plans for the design of vehicular crossing and associated works which are to be generally in accordance with the Council's specification for engineering works - AUS-SPEC #1. The plans shall be prepared by a qualified Civil Engineer. The design must include the following information:

1. A vehicular crossing 5.5 meters wide to be constructed in Minarto Lane in accordance with Council's standard drawing Normal.
2. Details of the construction of the kerb and gutter in accordance with Council's standards along the Minarto Lane frontage following the alignment of the kerb at the corner of Gondola Rd.
3. The road reserve levels in Minarto Lane are to match the existing levels along the boundary of the site and adjoining property.
4. Reinstatement of redundant vehicle crossings in Gondola Road.
5. Details of the stormwater connections in Gondola Road.
6. A services plan indicating all services in the road reserve. Where any services are to be adjusted as a result of the works, approval from the relevant service authority is to be provided.

The fee associated with the assessment and approval of the application is to be in accordance with Council's Fee and Charges.

An approval is to be submitted to the Principal Certifier prior to the issue of the Construction Certificate

Reason: To ensure engineering works are constructed in accordance with relevant standards and Council's specification.

35. Tanking of Basement Level

The basement area is to be permanently tanked. The Applicant is to submit structural details of the tanking, prepared by a suitably qualified Engineer. Where temporary dewatering works are required on the development site during construction, the developer/applicant must apply for and obtain a bore license from the NSW Office of Environment and Heritage. The bore license must be obtained prior to commencement of dewatering works. All requirements of Water NSW are to be complied with and a copy of the approval must be submitted to the Certifier.

Details demonstrating compliance are to be submitted to the Principal Certifier prior to the issue of the Construction Certificate.

Reason: To prevent ingress of sub-surface flows into the basement area and to comply with State Government Requirements.

36. Shoring of Council's Road Reserve (Temporary road anchors)

Should the proposal require shoring to support an adjoining property or Council land, the Applicant shall provide the adjoining properties with engineering drawings, detailing the proposed shoring works for their consideration and approval.

Written approval from Council under Section 138 of the Roads Act 1993 is required if temporary ground anchors are to be used within Council's road reserve. The Owner's approval is to be submitted to the Principal Certifier prior to the issue of the Construction Certificate.

Reason: To ensure that owners consent is obtained for ancillary works, and to ensure the protection of adjoining properties and Council land.

37. Acoustic Design Recommendations

Prior to the issuing of any Construction Certificate, documentation is to be submitted to the satisfaction of the Principal Certifier that design recommendations within the DA Acoustic Assessment Report referenced in Condition 1 of this consent have been implemented / incorporated into the design of the premises.

Details demonstrating compliance are to be submitted to the Certifier prior to the issue of the Construction Certificate.

Reason: To prevent noise nuisance by using mitigation measures in design.

38. Compliance with Standards

The development is required to be carried out in accordance with all relevant Australian Standards.

Details demonstrating compliance with the relevant Australian Standard are to be submitted to the Certifier prior to the issue of the Construction Certificate.

Reason: To ensure the development is constructed in accordance with appropriate standards.

39. External Colours and Materials (Mixed & Apartment Buildings)

(a) External Glazing - The reflectivity index of external glazing for windows, walls or roof finishes of the proposed development is to be no greater than 20% (expressed as a per centum of the reflected light falling upon any surface).

(b) External Roofing - The external finish to the roof shall have a medium to dark range in order to minimise solar reflections to neighbouring properties. Light colours such as off white, cream, silver or light grey colours are not permitted.

(c) Anti Graffiti Coating - The finishes of the walls adjoining Gondola Road and Minarto Lane must be finished in heavy duty long life, ultra violet resistant coating with a high resistance to solvents and chemicals as an anti-graffiti coating easily cleaned by solvent wipe.

Details demonstrating compliance are to be submitted to the Certifier prior to the issue of the Construction Certificate.

Reason: To ensure that excessive glare or reflectivity nuisance from glazing does not occur as a result of the development.

40. Utilities Services

Prior to the issue of the Construction Certificate, written evidence of the following service

provider requirements must be provided to the Principal Certifier:

- a) a letter from Ausgrid demonstrating that satisfactory arrangements can be made for the installation and supply of electricity,
- b) a response from Sydney Water as to whether the proposed works subject to this consent would affect any Sydney Water infrastructure, and whether further requirements need to be met, and
- c) other relevant utilities or services - that the development as proposed to be carried out is satisfactory to those other service providers, or if it is not, the changes that are required to make the development satisfactory to them.

Details demonstrating compliance are to be submitted to the Principal Certifier prior to the issue of the Construction Certificate.

Reason: To ensure relevant utility and service providers' requirements are provided to the Principal Certifier.

41. Acoustic Design

The acoustic measures as detailed and recommended in the approved DA Acoustic Assessment Report referenced in Condition 1 of this consent are to be incorporated into the construction plans.

Details demonstrating compliance are to be provided to the Certifying Authority prior to the issue of the Construction Certificate.

Reason: To ensure adequate provision is made for access for building occupant safety.

42. Internalised Services

Service ducts, drainage, plumbing, pipes, cables and conduits are to be internalised and must not be visible from the public domain. All service, communication and electricity connections must be provided underground.

Provision must also be made for any future ventilation or exhaust system required for the retail tenancies throughout the development.

Details demonstrating compliance with this requirement must be provided to the Certifying Authority prior to the issuance of the Construction Certificate.

Reason: To remove visual clutter and ensure a high-quality finish to the development.

43. Contaminated Land Requirements

Prior to the issue of any Construction Certificate a Contamination Management Plan is to be prepared by an appropriately qualified Environmental Consultant and provided to the satisfaction of the Certifier. The plan shall detail:

- a) Detail how all the requirements and / or recommendations contained within the Site Contamination Assessment by Martens Consulting Engineers dated 1 May 2024 (P2310036JR01V01) referenced in Condition 1 of this consent are to be implemented;
- b) Stipulate reporting and processes associated with discovery of any new contamination that is revealed during excavation, demolition or development works. This process shall include the

ability to contact NSW Fire and Rescue for pollution incidents, have on call (24 hours a day), a suitably qualified Environmental Consultant to undertake immediate investigations and provide recommendations for containment and rectification of contaminants or toxins and a process for notification to Northern Beaches Council and the Certifier.

c) A requirement to complete ongoing water and soils testing during excavation, demolition and development works as follows:

(a) During construction in order to monitor water and soil quality the following is to be implemented:

i) Water testing is to be completed in accordance with Section 3 of the NSW RTA's Guideline for Construction Water Quality Monitoring

ii) Soil Testing in order to detect contaminants is occur weekly with two (2) samples in accordance with the NSW EPA Contaminated Site Sampling Design Guidelines.

(b) The requirements of (i) and (ii) above are to be implemented from the commencement of works as follows:

i) Fortnightly during excavation works

ii) Monthly during building works

d) All stockpiles of potentially contaminated soil must be stored in a secure area on the site (no greater than 48 hours) so as not to cause pollution or public health risk until disposed of at a waste facility.

All contaminated soil removed from the site must be disposed of at a waste facility that can lawfully receive that waste and must be done in accordance with all relevant Acts, Regulations and Guidelines. Copies of all test results and disposal dockets must be retained for at least 3 years and be made available to authorised Council officers on request.

e) Hazardous or intractable wastes arising from the demolition process shall be removed and disposed of in accordance with the requirements of WorkSafe NSW and the Environment Protection Authority and the provisions of all relevant Acts, Regulations and Guidelines.

The following standards applied at the time of determination:

f) Environment Protection Authority's Environmental Guidelines: Assessment, Classification and Management of Liquid and Non-Liquid Wastes (1999).

g) Stipulate protocols for the importation of any landfill material onto the site the protocols shall include:

- 'Chain of Custody' documentation shall be kept and submitted for the transport of material from the site at 1-3 Gondola Road, North Narrabeen to a licensed waste facility.
- Any landfill material being brought to the site shall have a validation report prepared to the satisfaction of the Certifier (prepared in accordance with the Department of Environment & Climate Change's guidelines).

Details demonstrating compliance are to be submitted to the Certifier prior to the issue of the Construction Certificate.

Reason: Compliance with State Environmental Planning Policy (Resilience and Hazards) 2021.

44. **Remediation Action Plan**

A Remediation Action Plan is to be prepared by a suitably qualified Environmental Consultant

in accordance with State Environmental Planning Policy (Resilience and Hazards) 2021 and with any contaminated land planning guidelines under the Contaminated Land Management Act 1997, if required by the Detailed Site Investigation.

Details demonstrating compliance are to be submitted to the Certifier prior to the issue any Construction Certificate.

Reason: Compliance with State Environmental Planning Policy (Resilience and Hazards) 2021.

45. Site Remediation and Validation

A Remediation Validation Report must be provided by a suitably qualified and experienced environmental consultant, or equivalent person, documenting all remedial and validation works undertaken within the site (if required). All remediation and validation work, imported fill material certification, waste classification and disposal documentation must be documented in the Remediation and Validation Report prepared for the site.

The Remediation Validation Report must demonstrate that the site has been satisfactorily remediated to the Health Investigation Level (HIL) B.

Details demonstrating compliance are to be provided to the Principal Certifier prior to the issue of the Construction Certificate.

Reason: To protect human health and the environment.

46. Building Code of Australia Fire Safety Requirements

The Building Code of Australia fire safety requirements, including any performance solutions, for the building as detailed and recommended in the Building Code of Australia Compliance report referenced in Condition 1 of this consent must be incorporated into the construction plans.

Details demonstrating compliance are to be provided to the Certifying Authority, prior to the issue of a Construction Certificate.

Reason: To ensure adequate provision is made for health, amenity, access and fire safety for building occupant health and safety.

47. Access Requirements

The measures as detailed and recommended in the approved Development Application Access and Adaptability Report referenced in Condition 1 of this consent are to be incorporated into the construction plans.

Details demonstrating compliance are to be provided to the Certifying Authority prior to the issue of the Construction Certificate.

Reason: To ensure adequate provision is made for access for building occupant safety.

CONDITIONS THAT MUST BE ADDRESSED PRIOR TO ANY COMMENCEMENT

48. Tree Removal Within the Property

This consent approves the removal of existing prescribed trees on the subject site as identified in the Arboricultural Impact Assessment, approved Plans, or as listed below:

- a) tree 4 and tree 5,
- b) a qualified AQF level 5 Arborist shall identify these trees on site and tag or mark prior to

removal.

Reason: To enable authorised development works.

49. **Work Zones and Permits**

Prior to commencement of the associated works, the applicant shall obtain a Work Zone Permit where it is proposed to reserve an area of road pavement for the parking of vehicles associated with a construction site.

A separate application is required with a Traffic Guidance Scheme for the standing of construction vehicles in a trafficable lane.

Reason: To ensure Work zones are monitored and installed correctly.

50. **Demolition Traffic Management Plan**

As a result of the site constraints, limited vehicle access and parking, a Demolition Traffic Management Plan (DTMP) shall be prepared by an suitably accredited person and submitted to and approved by the Northern Beaches Council Traffic Team prior to commencing any demolition work.

Due to heavy traffic congestion throughout the area, truck movements will be restricted during the major commuter peak times being 8.00-9.30am and 4.30-6.00pm.

The DTMP must:-

- Make provision for all construction materials to be stored on site, at all times.
- The DTMP is to be adhered to at all times during the project.
- Specify construction truck routes and truck rates. Nominated truck routes are to be distributed over the surrounding road network where possible.
- Provide for the movement of trucks to and from the site, and deliveries to the site. Temporary truck standing/ queuing locations in a public roadway/ domain in the vicinity of the site is not permitted unless prior approval is granted by Council's Traffic Engineers.
- Include a Traffic Control Plan prepared by an TfNSW accredited traffic controller for any activities involving the management of vehicle and pedestrian traffic.
- Specify that a minimum fourteen (14) days notification must be provided to adjoining property owners prior to the implementation of any temporary traffic control measures.
- Include a site plan showing the location of any site sheds, location of requested Work Zones, anticipated use of cranes, structures proposed on the footpath areas (hoardings, scaffolding or temporary shoring) and extent of tree protection zones around Council street trees.
- Take into consideration the combined construction activities of other development in the surrounding area. To this end, the consultant preparing the DTMP must engage and consult with developers undertaking major development works within a 250m radius of the subject site to ensure that appropriate measures are in place to prevent the combined impact of construction activities. These communications must be documented and submitted to Council prior to work commencing on site.
- Specify spoil management process and facilities to be used on site.
- Specify that the roadway (including footpath) must be kept in a serviceable condition for the duration of demolition. At the direction of Council, the applicant is to undertake remedial treatments such as patching at no cost to Council.

The DTMP shall be prepared in accordance with relevant sections of Australian Standard 1742 – "Manual of Uniform Traffic Control Devices", RMS' Manual – "Traffic Control at Work Sites".

All fees and charges associated with the review of this plan is to be in accordance with Council's Schedule of Fees and Charges and are to be paid at the time that the Demolition Traffic Management Plan is submitted.

Reason: This condition is to ensure public safety and minimise any impacts to the adjoining pedestrian and vehicular traffic systems. The DTMP is intended to minimise impact of construction activities on the surrounding community, in terms of vehicle traffic (including traffic flow and parking) and pedestrian amenity adjacent to the site.

51. Pre-Construction Dilapidation Reports

Dilapidation reports, including photographic surveys, of the following adjoining properties must be provided to the Principal Certifying Authority prior to any works commencing on the site (including demolition or excavation). The reports must detail the physical condition of those properties (excluding demountable structures) listed below within 10 metres of the excavation perimeter, both internally and externally, including walls, ceilings, roof, structural members and other similar items. The reports must be prepared for the following property:

- 5 Gondola Road, North Narrabeen
- 2 Rickard Road, North Narrabeen
- 4 Rickard Road, North Narrabeen
- 6 Rickard Road, North Narrabeen
- 8 Rickard Road, North Narrabeen

The dilapidation reports are to be prepared by a suitably qualified person. A copy of the report must be provided to Council, the Principal Certifier and the owners of the affected properties prior to any works commencing.

The dilapidation report is to be prepared by a suitably qualified person. A copy of the report must be provided to Council, the Principal Certifier and the owners of the affected properties prior to any works commencing.

In the event that access for undertaking the dilapidation report is denied by an adjoining owner, the applicant must demonstrate, in writing that all reasonable steps have been taken to obtain access. The Principal Certifier must be satisfied that the requirements of this condition have been met prior to commencement of any works. If access is denied, then no dilapidation report is required.

Note: This documentation is for record keeping purposes and may be used by an applicant or affected property owner to assist in any action required to resolve any civil dispute over damage rising from the works.

Details demonstrating compliance are to be submitted to the Principal Certifier prior to the commencement of any works on site.

Reason: To maintain proper records in relation to the proposed development.

52. Notification to Adjoining Owners of Commencement of Works

The adjoining owners are to be notified at least 48 hours prior to commencement of works.

Reason: To ensure adjoining owners are informed of construction activity.

53. Protection to Surrounding Properties

From the commencement of any works being carried out until occupation a secure fence is to be erected and maintained along the common boundary of neighbouring properties.

Reason: To ensure the integrity and security of surrounding properties is maintained.

DURING BUILDING WORK

54. Acid Sulfate Soils

All excavation, construction and associated works must be conducted in accordance with the approved Acid Sulfate Soil Management Plan titled Acid Sulfate Soils Management Plan prepared by Martens & Associates, dated April 2024, reference P2310036JR04V01.

Reason: To ensure management of potential acid sulfate soils.

55. Site Contamination - Acid Sulfate Soils

All stockpiles of potentially contaminated soil must be stored in a secure area in a way that is not likely to cause pollution or be a public health risk.

All contaminated soil removed from the site must be disposed of at a waste facility that can lawfully receive that waste and must be done in accordance with all relevant Acts, Regulations and Guidelines.

Copies of all test results and disposal dockets must be retained by whom? for at least 3 years and be made available to authorised Council officers on request.

Note: The following Acts and Guidelines applied at the time of determination:

- i) Protection of the Environment Operations Act 1997;
- ii) Environment Protection Authority, Waste Classification Guidelines (2014);
- iii) Water Quality Australia, National Acid Sulfate Soils Guidance (2018); and
- iv) Acid Sulfate Soil Advisory Committee, Acid Sulfate Soil Manual (1998).

Reason: To protect environment and public health.

56. Tree and Vegetation Protection

a) Existing trees and vegetation shall be retained and protected, including:

- i) all trees and vegetation located on adjoining properties,
- ii) all trees and vegetation within the road reserve.

b) Tree protection shall be undertaken as follows:

- i) tree protection shall be in accordance with AS4970-2009 Protection of trees on development sites, and any recommendations of an approved Arboricultural Impact Assessment,
- ii) existing ground levels shall be maintained within the tree protection zone of trees to be retained, unless authorised by an Arborist/Project Arborist with minimum AQF Level 5 in arboriculture,
- iii) removal of existing tree roots at or >25mm (Ø) diameter is not permitted without consultation with an Arborist/Project Arborist with minimum AQF Level 5 in arboriculture,
- iv) no excavated material, building material storage, site facilities, nor landscape materials are to be placed within the canopy dripline of trees and other vegetation required to be retained,
- v) structures are to bridge tree roots at or >25mm (Ø) diameter unless directed by an Arborist/Project Arborist with minimum AQF Level 5 in arboriculture on site,
- vi) excavation for stormwater lines and all other utility services is not permitted within the tree

protection zone, without consultation with an Arborist/Project Arborist with minimum AQF Level 5 in arboriculture including advice on root protection measures,

vii) should either or all of v) or vi) occur during site establishment and construction works, an Arborist/Project Arborist with minimum AQF Level 5 in arboriculture shall provide recommendations for tree protection measures. Details including photographic evidence of works undertaken shall be submitted by the Arborist/Project Arborist to the Principal Certifier,

viii) any temporary access to, or location of scaffolding within the tree protection zone of a protected tree or any other tree to be retained during the construction works is to be undertaken using the protection measures specified in sections 4.5.3 and 4.5.6 of AS4970-2009 Protection of trees on development sites,

ix) the activities listed in section 4.2 of AS4970-2009 Protection of trees on development sites, shall not occur within the tree protection zone of any tree on the lot or any tree on an adjoining site,

x) tree pruning from within the site to enable approved works shall not exceed 10% of any tree canopy, and shall be in accordance with AS4373-2007 Pruning of amenity trees,

xi) the tree protection measures specified in this clause must: i) be in place before work commences on the site, and ii) be maintained in good condition during the construction period, and iii) remain in place for the duration of the construction works.

The Principal Certifier must ensure that:

c) The arboricultural works listed in a) and b) are undertaken as complaint to AS4970-2009 Protection of trees on development sites, and any recommendations of an approved Arboricultural Impact Assessment and/or Project Arborist as applicable.

Reason: Tree and vegetation protection.

57. **Road Reserve**

The applicant shall ensure the public footways and roadways adjacent to the site are maintained in a safe condition at all times during the course of the work.

Reason: Public safety.

58. **Dewatering Management**

Groundwater: A permit from Council is required for any dewatering of groundwater.

The groundwater/tailwater to be discharged must be compliant with the General Terms of Approval/Controlled Activity permit issued by WaterNSW (if applicable), Landcom's 'Managing Urban Stormwater: Soils and Construction' (2004) (Blue Book), Council's Compliance and Enforcement Policy and legislation including Protection of the Environment Operations Act 1997 and Contaminated Lands Act 1997.

All approvals, water discharges and monitoring results are to be documented and kept on site. Copies of all records shall be provided to the appropriate regulatory authority, including Council, upon request.

Reason: Protection of the receiving environment and groundwater resources.

59. **Installation and Maintenance of Sediment and Erosion Controls**

Sediment and erosion controls must be installed in accordance with Landcom's 'Managing Urban Stormwater: Soils and Construction' (2004) and the Erosion and Sediment Control Plan prepared by prior to commencement of any other works on site.

Erosion and sediment controls are to be adequately maintained and monitored at all times, particularly after periods of rain, and shall remain in proper operation until all development activities have been completed and vegetation cover has been re-established across any remaining areas.

Reason: Protection of the receiving environment.

60. Implementation of Demolition Traffic Management Plan

All works and demolition activities are to be undertaken in accordance with the approved Demolition Traffic Management Plan (DTMP). All controls in the DTMP must be maintained at all times and all traffic management control must be undertaken by personnel having appropriate TfNSW accreditation. Should the implementation or effectiveness of the DTMP be impacted by surrounding major development not encompassed in the approved DTMP, the DTMP measures and controls are to be revised accordingly and submitted to Council for approval. A copy of the approved DTMP is to be kept onsite at all times and made available to the accredited certifier or Council on request.

Reason: To ensure compliance and Council's ability to modify the approved Construction Traffic Management Plan where it is deemed unsuitable during the course of the project.

61. Implementation of Construction Traffic Management Plan

All works and construction activities are to be undertaken in accordance with the approved Construction Traffic Management Plan (CTMP). All controls in the CTMP must be maintained at all times and all traffic management control must be undertaken by personnel having appropriate TfNSW accreditation. Should the implementation or effectiveness of the CTMP be impacted by surrounding major development not encompassed in the approved CTMP, the CTMP measures and controls are to be revised accordingly and submitted to Council for approval. A copy of the approved CTMP is to be kept onsite at all times and made available to Council on request.

Reason: To ensure compliance of the developer/builder in adhering to the Construction Traffic Management procedures agreed and are held liable to the conditions of consent.

62. Ongoing Management

The applicant shall be responsible in ensuring that the road reserve remains in a serviceable state during the course of the demolition and building works.

Reason: To ensure public safety.

63. Survey Certificate

A survey certificate prepared by a Registered Surveyor at the following stages of construction:

(a) Commencement of perimeter walls columns and or other structural elements to ensure the wall or structure, to boundary setbacks are in accordance with the approved details.

(b) At ground level to ensure the finished floor levels are in accordance with the approved levels, prior to concrete slab being poured/flooring being laid.

(c) At completion of the roof frame confirming the finished roof/ridge height is in accordance with levels indicated on the approved plans.

Details demonstrating compliance are to be submitted to the Principal Certifier.

Reason: To determine the height of buildings under construction comply with levels shown on approved plans.

64. Waste Management During Development

The reuse, recycling or disposal of waste during works must be done generally in accordance with the Waste Management Plan for this development.

Details demonstrating compliance must be submitted to the Principal Certifier.

Reason: To ensure demolition and construction waste is recycled or reused and to limit landfill.

65. Requirement to Notify about New Contamination Evidence

Any new information revealed during demolition works that has the potential to alter previous conclusions about site contamination or hazardous materials shall be immediately notified to the Council and the Principal Certifier.

Reason: To protect human health and the environment.

66. Stockpiling materials

During construction, all material associated with works is to be contained at source, covered and must be within the construction area. All material is to be removed off site and disposed of according to local regulations. The property is to be kept clean and any building debris removed as frequently as required to ensure no debris enters receiving waters.

Reason: To ensure pollution control measures are effective to protect the aquatic habitats within receiving waters throughout the construction period.

67. Staff and Contractor Parking

The applicant is to make provision for parking for all construction staff and contractors for the duration of the project. All Staff and Contractors are to use the basement parking once available. All necessary facilities are to be provided to accommodate this requirement including lighting in the basement, security cameras, etc.

Reason: To ensure minimum impact of construction activity on local parking amenity.

68. Dust Minimisation

The applicant must take all reasonable measures to minimise dust generated during all works authorised by this consent. During construction, the applicant must ensure that:

- a) All trucks entering or leaving the site with loads have their loads covered.
- b) Trucks associated with the development do not track dirt onto the public road network.
- c) Public roads used by these trucks are kept clean.
- d) Land stabilisation works are carried out progressively on site to minimise exposed surfaces.

Reason: To minimise the environmental impacts of construction works.

69. WaterNSW General Terms of Approval

The General Terms of Approval issued by WaterNSW do not constitute an approval under the Water Management Act 2000. The development consent holder must apply to WaterNSW for a Water Supply Work approval after consent has been issued by Council and before the

commencement of any dewatering activity.

Reason: Statutory compliance.

70. Waste/Recycling Requirements (Waste Plan Submitted)

During demolition and/or construction the proposal/works shall be generally consistent with the submitted Waste Management Plan dated October 2024 including updated plans by Mackenzie Architects dated 14/03/2025.

Reason: To ensure waste is minimised and adequate and appropriate waste and recycling facilities are provided.

71. Waste/Recycling Requirements (Materials)

During demolition and/or construction the following materials are to be separated for recycling: timber, bricks, tiles, plasterboard, metal, concrete, and evidence of disposal for recycling is to be retained on site.

Reason: To ensure waste is minimised and recovered for recycling where possible.

BEFORE ISSUE OF THE OCCUPATION CERTIFICATE

72. Landscape Completion

Landscape works are to be implemented in accordance with the approved Landscape Plans, and inclusive of the following conditions:

a) landscape works are to be contained within the legal property boundaries.

Prior to the issue of an Occupation Certificate, details (from a landscape architect, landscape designer or qualified horticulturalist) shall be submitted to the Principal Certifier, certifying that the landscape works have been completed in accordance with any conditions of consent.

Reason: Environmental amenity.

73. Street Tree Planting

Street tree planting (4 x *Tristaniaopsis laurina* 'luscious') shall be installed in accordance with the approved Landscape Plans.

All street trees shall be a minimum pre-ordered planting size of 75 litres, and shall meet the requirements of Australian Standard AS2303 - Tree Stock for Landscape Use. All street trees shall be planted into a prepared planting hole 1m x 1m x 600mm depth, backfilled with a sandy loam mix or approved similar, mulched to 75mm depth minimum and maintained, including a four post and top and mid rail timber tree guard, and watered until established, and shall be generally located at least 2.0 metres from driveways, and shall generally be centralised within the road verge.

Details demonstrating compliance are to be submitted to the Principal Certifier prior to the issue of any Occupation Certificate.

Reason: To maintain environmental and streetscape amenity.

74. Certification of Works as Executed

A suitably qualified engineer and/or registered surveyor is to certify that the completed works have been constructed in accordance with this consent and the approved plans with respect to the following:

1. Floor levels for ground floor, shelter in place refuge and garage are set at or above the required level
2. All access, ventilation, driveway crests and any other potential water entry points to the basement car park have been set at or above the required level
3. There has been no filling on the land other than what has been approved
4. Openings are provided under floor areas where required for the free passage of flood waters
5. Openings are provided in fencing where required for the free passage of flood waters

Details demonstrating compliance are to be submitted to the Principal Certifier prior to the issue of the Occupation Certificate.

Reason: To reduce the impact of flooding and flood liability on owners and occupiers of flood-prone property and reduce public and private losses in accordance with Council and NSW Government policy.

75. Building Components and Structural Soundness

A suitably qualified structural engineer is to certify the structural integrity of the shelter in place up to the Probable Maximum Flood level of 4.89m AHD, and the remainder of the new development up to the Flood Planning Level of 4.40m AHD. The depth, velocity, debris load, wave action, buoyancy and immersion must all be considered.

A suitably qualified electrician or contractor is to certify that all new and existing electrical equipment, power points, wiring and connections are located above the Flood Planning Level of 4.40m AHD, are protected from flood water or have residual current devices installed to cut electricity supply during flood events.

Details demonstrating compliance are to be submitted to the Principal Certifier prior to the issue of the Occupation Certificate.

Reason: To reduce the impact of flooding and flood liability on owners and occupiers of flood-prone property and reduce public and private losses in accordance with Council and NSW Government policy.

76. Certification of Civil Works and Works as Executed Data in accordance with Road Act Approval

The Applicant shall submit a certification by a suitably qualified Civil Engineer, who has membership to Engineers Australia, National Engineers Register (NER) or Professionals Australia (RPENG) that the completed works have been constructed in accordance with this consent and the approved Section 138 and/or Construction Certificate plans. Works as Executed data certified by a registered surveyor in relation to boundaries and/or relevant easements, prepared in accordance with Council's 'Guideline for preparing Works as Executed data for Council Assets' in an approved format shall be submitted to the Principal Certifier for

approval prior to the issue of the Occupation Certificate.

Reason: To ensure compliance of works with Council's specification for engineering works.

77. Stormwater Disposal

The stormwater drainage works shall be certified as compliant with all relevant Australian Standards and Codes by a suitably qualified Civil Engineer. Details demonstrating compliance are to be submitted to the Principal Certifier prior to the issue of an Occupation Certificate.

Reason: To ensure appropriate provision for the disposal of stormwater arising from the development.

78. Certification for the Installation of Stormwater Treatment Measures

A certificate from a Civil Engineer, who has membership to Engineers Australia and the National Engineers Register must be provided, stating that the stormwater treatment measures have been installed in accordance with the Concept Stormwater Management Plan prepared by Martens & Associates (project P2310036, revision D dated 13/12/2024). The certificate must confirm that stormwater treatment measures are completed, online, in good condition and are not impacted by sediment. Any vegetated measures must exhibit an 80 percent survival rate of plantings.

The certificate shall be submitted to the Principal Certifier prior to the release of an Occupation Certificate.

Reason: Protection of the receiving environment.

79. Positive Covenant, Restriction as to User and Registration of Encumbrances for Stormwater Treatment Measures

A positive covenant shall be created on the title of the land requiring the proprietor of the land to maintain the stormwater treatment measures in accordance with the standard requirements of Council, the manufacturer and as required by the Stormwater Treatment Measures Operation and Maintenance Plan.

A restriction as to user shall be created on the title over the stormwater treatment measures, restricting any alteration to the measures.

The terms of the positive covenant and restriction as to user are to be prepared to Council's standard requirements (available from Council) at the applicant's expense and endorsed by the Northern Beaches Council's delegate prior to lodgement with the Department of Lands. Northern Beaches Council shall be nominated as the party to release, vary or modify such covenant.

A copy of the certificate of title demonstrating the creation of the positive covenant and restriction as to user is to be submitted to the Principal Certifier prior to the issue of the Occupation Certificate.

Reason: To identify encumbrances on land, ensure ongoing maintenance, and ensure modification to the stormwater treatment measures is not carried out without Council's approval.

80. Stormwater Treatment Measures Operation and Maintenance Plan

An Operation and Maintenance Plan is to be prepared to ensure the proposed stormwater treatment measures remain effective.

The Plan must be attached to the Positive Covenant (and the community or strata management statement if applicable) and contain the following:

1. Detail on the stormwater treatment measures:
 - a) Work as executed drawings
 - b) Intent of the stormwater treatment measures including modelled pollutant removal rates
 - c) Site detail showing catchment for each device
 - d) Vegetation species list associated with each type of vegetated stormwater treatment measure
 - e) Impervious area restrictions to maintain the water balance for the site
 - f) Funding arrangements for the maintenance of all stormwater treatment measures
 - g) Identification of maintenance and management responsibilities
 - h) Maintenance and emergency contact information

2. Maintenance schedule and procedure - establishment period of one year following commissioning of the stormwater treatment measure:
 - a) Activity description, and duration and frequency of visits

Additionally for vegetated devices:

 - b) Monitoring and assessment to achieve an 80 percent survival rate for plantings
 - c) Management of weeds, pests and erosion, with weed and sediment cover limited to a maximum of 5 percent of the total area of the stormwater treatment measure

3. Maintenance schedule and procedure - ongoing
 - a) Activity description, and duration and frequency of visits
 - b) Routine maintenance requirements
 - c) Work Health and Safety requirements
 - d) Waste management and disposal
 - e) Traffic control (if required)
 - f) Renewal, decommissioning and replacement timelines and activities of all stormwater treatment measures (please note that a DA may be required if an alternative stormwater treatment measure is proposed)
 - g) Requirements for inspection and maintenance records, noting that these records are required to be maintained and made available to Council upon request.

Details demonstrating compliance shall be submitted to the Principal Certifier prior to the release of the Occupation Certificate.

Reason: Protection of the receiving environment.

81. **Works as Executed Drawings - Stormwater Treatment Measures**

Works as Executed Drawings for the stormwater treatment measures must be prepared.

The drawings shall be submitted to the Principal Certifier prior to the release of the Occupation Certificate.

Reason: Protection of the receiving environment.

82. Kerb and gutter and parking restriction signage – Implementation

The applicant is to construct kerb and gutter and install all required parking restriction signage as per any plans approved by the Traffic Committee. These works are to be complete at the applicant's cost to Council's satisfaction prior to the issue of an Occupation Certificate.

Reason: To ensure compliance with the Road Act.

83. Basement Traffic Signal System

To prevent conflicting vehicle flows on the one-way basement ramp and avoid vehicles having to reverse up/ down the ramp, a traffic signal system must be installed at each ramp entry, designed to warn drivers about to enter the road of any conflicting vehicle approaching.

The signal system must;

- be clearly visible from ramp entrances,
- is to clearly indicate to an approaching driver, by way of red light or wording, that an opposing vehicle has entered the ramp,
- Incorporate linemarking to delineate traffic flow and nominate waiting bay locations to allow vehicles to overtake another.

Details of the system, including the system operation, components and placement within the development, must be specified by a practising Traffic Engineer. This engineer is to submit a compliance certificate to the Principal Certifier that the system has been installed and operating as designed, in accordance with the requirements of this condition, prior to the issue of an Occupation Certificate issued for the development.

Reason: To ensure no vehicle conflicts within the basement carpark.

84. Allocated Parking Spaces (retail/commercial)

Parking allocated to this development must be clearly signposted and linemarked as being for the exclusive use of this development. Details demonstrating compliance are to be submitted to the Principal Certifier prior to the issue of any Occupation Certificate.

Reason: To ensure parking availability.

85. Disabled Parking Spaces

Disabled parking spaces must be in accordance with AS2890.6:2022.

Details demonstrating compliance are to be submitted to the Principal Certifier prior to the issue of any Occupation Certificate.

Reason: To ensure compliance with Australian Standards.

86. Shared Zone Bollard

A bollard or column is to be provided at the shared zone of each disabled parking space in accordance to Australian Standards AS2890.6:2022.

Details demonstrating compliance are to be submitted to the Principal Certifier prior to the issue of any Occupation Certificate.

Reason: To prevent parking in the shared zone and ensure compliance with Australian Standards.

87. Post-Construction Dilapidation Report

Post-Construction Dilapidation Reports, including photos of any damage evident at the time of inspection, must be submitted after the completion of works. The report must:

- Compare the post-construction report with the pre-construction report,
- Clearly identify any recent damage and whether or not it is likely to be the result of the development works,
- Should any damage have occurred, suggested remediation methods.

Copies of the reports must be given to the property owners referred to in the Pre-Construction Dilapidation Report Condition. Copies must also be lodged with Council.

Details demonstrating compliance with this condition are to be submitted to the Principal Certifier prior to the issue of an Occupation Certificate.

Reason: To maintain proper records in relation to the proposed development.

88. Waste Disposal Verification Statement

On completion of demolition work:

- a signed statement must be submitted to the Certifier verifying that demolition work, and any recycling of materials, was undertaken in accordance with the waste management plan approved under this consent, and
- if the demolition work involved the removal of asbestos, an asbestos clearance certificate issued by a suitably qualified person, must be submitted to the Certifier within 14 days of completion of the demolition work.

Reason: To provide for the submission of a statement verifying that demolition waste management and recycling has been undertaken in accordance with the approved waste management plan.

89. Consolidation of Allotments

The approved development occurs over 1 Gondola Road (Lot 187 DP 16719) and 3 Gondola Road (Lot 188 DP 16719). To ensure orderly development of land, these allotments are to be consolidated into one (1) new allotment. The new allotment is to be registered prior to the issue of an Occupation Certificate.

Details demonstrating compliance must be submitted to the Certifying Authority prior to the issue of the Occupation Certificate.

Reason: To ensure orderly development of land.

90. Plan of Management

An operational Plan of Management (POM) must be prepared for the development. The POM must:

- a) Detail a protocol for managing complaints from the community.
- b) Detail a protocol for managing the number of people permitted on the communal roof top

terrace.

c) Detail a protocol for operating, maintaining and managing the residential lift security door to ensure that only residents of the apartments including any visitors for the residents can gain access beyond the security door.

The POM must be submitted to the Certifier for approval prior to the issue of any Occupation Certificate.

Reason: To ensure orderly management of the premises.

91. Positive Covenant for the Maintenance of Stormwater Pump-out Facilities

The Applicant shall lodge the Legal Documents Authorisation Application with Council. The application shall include the original completed request forms (NSW Land Registry standard forms 13PC) and a copy of the Works-as-Executed plan (details overdrawn on a copy of the approved drainage plan), and Civil Engineers' certification.

The Applicant shall create on the Title a positive covenant in respect to the ongoing maintenance of the pump-out facility on the property being developed. Northern Beaches Council shall be nominated in the instrument as the only party authorised to release, vary or modify the instrument. Northern Beaches Council's delegate shall sign these documents prior to the submission to the NSW Land Registry Services. Details demonstrating compliance are to be submitted to the Principal Certifier prior to the issue of an Occupation Certificate.

A copy of the certificate of title demonstrating the creation of the positive covenant and restriction for on-site storm water detention as to user is to be submitted.

Details demonstrating compliance are to be submitted to the Principal Certifier prior to the issue of an Occupation Certificate.

Reason: To ensure adequate provision is made for the stormwater pump out system to be maintained to an appropriate operational standard.

92. Environmental Reports Certification

Written certification from a suitably qualified person(s) shall submit to the Principal Certifier, stating that all the works/methods/procedures/control measures/recommendations approved by Council in the following reports referenced in Condition 1 of this consent have been completed:

- (a) Acid Sulfate Soils Management Plan.
- (b) Geotechnical and Acid Sulfate Soil Assessment.
- (c) Site Contamination Assessment including any Contamination Reports required by the conditions of consent.
- (d) DA Acoustic Assessment Report.
- (e) Development Application Access and Adaptability Report.
- (f) Building Code of Australia Compliance Report.
- (g) Arboricultural Assessment Report and Tree Protection Specification.
- (h) BASIX Certificate.
- (i) Hydrological Assessment and Groundwater Dewatering Management Plan.

Details demonstrating compliance are to be submitted to the Principal Certifier prior to the issue of an Occupation Certificate.

Reason: To ensure compliance with standards.

93. Garbage and Recycling Facilities

All internal walls of the waste rooms shall be rendered to a smooth surface, coved at the floor/wall intersection, graded and appropriately drained to the sewer with a tap in close proximity to facilitate cleaning.

Waste room floors shall be graded and drained to an approved Sydney Water drainage system.

Waste rooms shall be clear of any other services or utilities infrastructure such as gas, electricity air-conditioning, plumbing, piping ducting or equipment.

Reason: To prevent pollution of the environment, provide a safe workplace for contractors and residents and to protect the amenity of the area.

94. Waste and Recycling Facilities Certificate of Compliance

The proposal shall be constructed in accordance with the Northern Beaches Waste Management Guidelines.

Details demonstrating compliance are to be submitted to the Principal Certifier prior to the issue of an Occupation Certificate.

Reason: To ensure waste and recycling facilities are provided.

95. Waste/Recycling Compliance Documentation

Evidence of disposal for recycling from the construction/demolition works shall be submitted to the Principal Certifier prior to the issue of an Occupation Certificate.

Reason: To ensure waste is minimised and recycled.

ON-GOING CONDITIONS THAT MUST BE COMPLIED WITH AT ALL TIMES

96. Deliveries, waste and recycling collection hours

Deliveries, waste and recycling collection from the site is to be carried out between 7.00am and 10.00pm only to minimise noise.

Reason: To minimise noise to residential receivers.

97. Use of Roof Communal Area

The number of patrons using the roof communal garden is to be limited to the following:

- Between 7:00 am and 6:00 pm: Maximum of 40 people.
- Between 6:00 pm and 10:00 pm: Maximum of 16 people.

Reason: To ensure the noise amenity of the area.

98. Landscape Maintenance

If any landscape materials/components or planting under this consent fails, they are to be replaced with similar materials/components. Trees, shrubs and groundcovers required to be planted under this consent are to be mulched, watered and fertilised as required at the time of planting. If any tree, shrub or groundcover required to be planted under this consent fails, they are to be replaced with similar species to maintain the landscape theme and be generally in accordance with the approved Landscape Plans and any conditions of consent.

A maintenance activity schedule for on-going maintenance of planters on slab shall be incorporated to monitor and replenish soil levels as a result of soil shrinkage over time.

The approved landscape planted areas consisting of lawn, planting at grade, and planting on structure shall in perpetuity remain as planting under the development consent, and shall not be replaced with any hard paved surfaces or structures.

Reason: To maintain local environmental amenity.

99. **Maintenance of Stormwater Treatment Measures**

Stormwater treatment measures must be maintained at all times in accordance with the Stormwater Treatment Measure Operation and Maintenance Plan, manufacturer's specifications and as necessary to achieve the required stormwater quality targets for the development.

Vegetated stormwater treatment measures must maintain an 80 percent survival rate of plantings and limit weed cover to no more than 10 percent of the total area of the stormwater treatment measure.

Where replacement cartridges or other necessary components for the system become unavailable, an alternative system is required to be retrofitted into the development to achieve an equivalent pollutant reduction outcome. Evidence supporting the replacement must be retained on site and made available to Council as required.

Northern Beaches Council reserves the right to enter the property and carry out appropriate maintenance of the device at the cost of the property owner.

Reason: Protection of the receiving environment.

100. **Landscaping adjoining vehicular access**

The applicant must ensure that the planting chosen for any land immediately adjacent to the driveway and adjacent to any driveway intersections must not exceed a height of 1 metre.

Reason: To maintain unobstructed sight distance for motorists.

101. **Graffiti removal**

During ongoing use of the premises, ensure graffiti is removed from the exterior of the building or associated structures, including any fences, site services and retaining/planter bed walls.

Reason: To ensure the safe operation of the premises and to protect the amenity of adjoining premises and the surrounding area.

102. **Commercial Waste and Recycling Storage**

Commercial waste and recycling material/storage bins must be stored in a separate area to the residential waste and recycling material/storage bins as shown on the approved plans.

Reason: To ensure that commercial waste and residential waste is not mixed and is properly managed.

103. **Compliance with Plan of Management**

The operational Plan of Management (POM) that is required by the conditions of consent must be complied with at all times in perpetuity of the development.

Reason: To mitigate amenity impacts.

104. **Fencing Height / Vegetation**

All fencing and/or vegetation along the frontage road(s) shall not impede pedestrian or driver visibility. This requires that vegetation does not exceed 1m in height. Appropriate plants shall be selected within the 2.0m - 2.5m splay to ensure this condition is met.

Reason: To ensure maximum vehicular and pedestrian visibility.

General advisory notes

This consent contains the conditions imposed by the consent authority which are to be complied with when carrying out the approved development. It is an offence under the EP&A Act to carry out development that is not in accordance with this consent. However, this consent is not an exhaustive list of all obligations which may relate to the carrying out of the development under the EP&A Act, EP&A Regulation and other legislation.

Some of these additional obligations are set out in the Conditions of development consent: advisory notes, which has been uploaded to the NSW Planning Portal as a separate document. The consent should be read together with the advisory notes to ensure the development is carried out lawfully.

Dictionary

The following terms have the following meanings for the purpose of this determination (except where the context clearly indicates otherwise):

Approved plans and documents means the plans and documents endorsed by the consent authority, a copy of which is included in this notice of determination.

AS means Australian Standard published by Standards Australia International Limited and means the current standard which applies at the time the consent is issued.

Building work means any physical activity involved in the erection of a building.

Certifier means a council or a person that is registered to carry out certification work under the Building and Development Certifiers Act 2018.

Construction certificate means a certificate to the effect that building work completed in accordance with specified plans and specifications or standards will comply with the requirements of the EP&A Regulation and Environmental Planning and Assessment (Development Certification and Fire Safety) Regulation 2021.

Council means Northern Beaches Council.

Court means the Land and Environment Court of NSW.

EPA means the NSW Environment Protection Authority.

EP&A Act means the Environmental Planning and Assessment Act 1979.

EP&A Regulation means the Environmental Planning and Assessment Regulation 2021.

Independent Planning Commission means Independent Planning Commission of New South Wales constituted by section 2.7 of the EP&A Act.

Local planning panel means Northern Beaches Local Planning Panel.

Occupation certificate means a certificate that authorises the occupation and use of a new building or a change of building use for an existing building in accordance with this consent.

Principal certifier means the certifier appointed as the principal certifier for building work or subdivision work under section 6.6(1) or 6.12(1) of the EP&A Act respectively.

Site work means any work that is physically carried out on the land to which the development the subject of this development consent is to be carried out, including but not limited to building work, subdivision work, demolition work, clearing of vegetation or remediation work.

Stormwater drainage system means all works and facilities relating to: the collection of stormwater, the reuse of stormwater, the detention of stormwater, the controlled release of stormwater, and connections to easements and public stormwater systems.

Strata certificate means a certificate in the approved form issued under Part 4 of the Strata Schemes Development Act 2015 that authorises the registration of a strata plan, strata plan of subdivision or notice of conversion.

Subdivision certificate means a certificate that authorises the registration of a plan of subdivision under Part 23 of the Conveyancing Act 1919.

Subdivision works certificate means a certificate to the effect that subdivision work completed in accordance with specified plans and specifications will comply with the requirements of the EP&A Regulation.

Sydney district or regional planning panel means Sydney North Planning Panel. Some of these additional obligations are set out in the Conditions of development consent: advisory notes, which has been uploaded to the NSW Planning Portal as a separate document. The consent should be read together with the Conditions of development consent: advisory notes to ensure the development is carried out lawfully.

The approved development must be carried out in accordance with the conditions of this consent. It is an offence under the EP&A Act to carry out development that is not in accordance with this consent.