Prepared for Rachael Fisher Site Address: 4 Hume Place Frenchs Forest 23rd September 2025

Date	Version	Change	Stage		
23/9/2025	2	Tree DA			
		numbering			
8/9/2025	1	none	DA		

Statement

Bradshaw Consulting Arborists is a company that exclusively provides tree consultancy within the tree industry. There are no conflicts of interests concerning the recommendations outlined in this report.

Prepared by Tristan Bradshaw

Thou Min

BHort Sci (USYD), Dip Arb AQF 5 (TAFE), Grad Cert AQF 8 (UMELB), TRAQ

Member of Arboriculture Australia, Registered Consulting Arborist No. 1286
Bachelor of Horticultural Science, University Sydney.

AQF Level 2, 3 & 5 Diploma in Arboriculture

Graduate Certificate AQF Level 8 University Melbourne

Tree Risk Assessment Qualification (TRAQ)

2025
REGISTERED CONSULTING MEMBERS

Bradshaw Consulting Arborists Po Box 48 St Ives 2075 0411 608 001 bradshawarborists@gmail.com

Contents

1	Intro	oduction	4
	1.1	Scope	4
	1.2	The Site	4
	1.3	Bushfire Constraints	5
	1.4	Heritage Constraints	5
	1.5	Significant Tree Register	5
	1.6	Vegetation Type classifications and Biodiversity	5
	1.7	Plans used in this Assessment	5
	1.8	Method	5
2	Body	y Observations Results	8
3	Disc	ussion	10
4	Reco	ommendations	11
5	Refe	rences	12
6	Proje	ect Arborist Monitoring Stages	12
7	Tree	locations and Tree Protection Plan (Not to Scale)	13
8	Tree	Protection specifications	15
	8.1	Trunk/Branch Protection	16
	8.2	Ground protection	16
	8.3	Installation of underground services	17
9	Appe	endix A	18
	9.1	Appendix B Methodology for Determining Tree Retention Value	19
	9.2	Appendix C Table 2 Step 1 Landscape Significance Rating	20
	9.3	Appendix D Table 3 Estimating Safe Useful Life Expectancy (SULE) Step 2	21
	9.4	Appendix E Safe Useful Life Expectancy (SULE) subcategories	22
	9.5	Appendix F Table 4 Determining Tree Retention Values	23
10	0 Glos	sary of Terms and Abbreviations	24
1	1 Qua	lifications and Experience	26
	_	ite location (Google Maps 2025)	
	_	iodiversity Mapping NSW	
	-	ree 3 with signs of cockatoo damage to the cambium of the treeree 6 declined health and structural concerns	
	-	ower junction of tree 6 with decay, hollow and included bark	

Figure 6 An example of tree protection fencing (AS4970-2009)	15
Figure 7 An example of trunk, branch and ground protection	16
Figure 8 Trunk Protection	
Figure 9 Sleepers with gravel between protecting ground from compaction	17

1 Introduction

This report has been prepared by Tristan Bradshaw of Bradshaw Consulting Arborists for Rachael Fisher for the property 4 Hume Place Frenchs Forest. The report request was to inspect 14 trees throughout the property and surrounding properties.

The trees' characteristics have been listed in Table 1 page 6. The inspection of the site was undertaken on 21st May 2025.

The report was completed on 23rd September 2025.

See appendix B Section 7 for tree locations and tree protection plan.

The site's trees are managed under Northern Beaches Council's Urban Tree Management Policy.

1.1 Scope

This is an Arboricultural Impact Assessment. It aims to assess the impact of the development on all trees on the property and on surrounding properties. Works undertaken include:

- Site inspection using the survey to locate trees, estimate tree locations that are not included in the survey.
- Record species, trunk diameter, tree size, health, condition, SULE, landscape value, retention value, SRZ, TPZ.
- Assess the impact of the development to Australian Standard 4970-2009.
- Prepare a tree protection plan.

1.2 The Site

The site is composed of an existing house and gardens.




Figure 1 Site location (Google Maps 2025)

1.3 Bushfire Constraints

The property is not bushfire prone and not within RFS 10/50 vegetation entitlement clearing area.

1.4 Heritage Constraints

The property is not heritage listed or within a heritage conservation area.

1.5 Significant Tree Register

No trees are listed on a significant tree register.

1.6 Vegetation Type classifications and Biodiversity

The property is not mapped on the biodiversity values mapping. See figure 2 below.




Figure 2 Biodiversity Mapping NSW

1.7 Plans used in this Assessment

Consultant	Company	Date	Revision
Survey	Infocus Surveyors	31/7/2025	-
Architecture	Argent Design	31/8/2025	Concept
Stormwater	Not Assessed		-
Landscape	Not Assessed		-

1.8 Method

The inspection of the site was undertaken on 21st May 2025.

The inspection method used was the Visual Tree Assessment (VTA) method (Mattheck & Breloer 2010). This method involves inspecting the trees from ground level, using binoculars to aid in identification of any external's signs of decay, physical damage, growth related structural defects and the site conditions where the tree is growing. This method will ascertain whether there is need for a more detailed inspection of any part of the tree. No aerial or subterranean inspections were carried out. See appendix A for the complete flow chart.

The Diameter at Breast Height (DBH) was measured with a diameter tape measure. The height of the measurement was at 140 cm above the ground unless stated. Where access was restricted or prevented to a tree the DBH was estimated.

The height of the tree was estimated.

The canopy spread of the tree was estimated.

The positions of trees are based on a survey by a registered surveyor. If found to be incorrect this will be stated. The position of trees not included in the survey have been estimated and any impacts have been based of this estimated position.

Health: Based on vigour, callus development, % of deadwood, dieback, fruiting levels, internode lengths

- (E) Excellent
- (G) Good
- (F) Fair
- (P) Poor
- (D) Dead

Age Class: (Y) Young=Recently Planted

- (S) Semi mature <20% of life expectancy
- (M) Mature 20-80% of life expectancy
- (O) Over Mature >80% of life expectancy

Condition: Based on the structural integrity of the tree, cavities, fungal decay, branch failure, branch taper, sap or Kino exudate, fruiting bodies, root condition.

- (E) Excellent
- (G) Good
- (F) Fair
- (P) Poor
- (D) Dead

Landscape Significance and Retention Value see section 9.

Safe Useful Life Expectancy (SULE)

In a planning context, the time a tree can expect to be usefully retained is the most important long-term consideration. SULE is a system designed to classify trees into a number of defined categories so that information regarding tree retention can be concisely communicated in a non-technical manner. SULE categories are easily verifiable by experienced personnel without great disparity.

AIA Version 2 23/9/2025 4 Hume Place French Forest

A tree's SULE category is the life expectancy of the tree modified by its age, health, condition, safety and location (to give safe life expectancy), then by economics (i.e. cost of maintenance; retaining trees at an excessive management cost is not normally acceptable), effects on better trees, and sustained amenity (i.e. establishing range of age classes in a local population).

SULE assessments are not static but may be modified as dictated by changes in tree health and environment. Trees with short SULE may at present be making a contribution to the landscape but their value to the local community will decrease rapidly towards the end of this period, prior to their being removed for safety or aesthetic reasons. For details of SULE categories see Appendix D, adapted from Barrell (1993 and 1996) and Subcategories Section 9.

Visual Habitat

This assessment is based on a visual observation of the tree, included in the VTA method.

Habitat trees are trees that provide microhabitats, these can include hollows, deeply fissured bark, cracks, epiphytes or forms of decay (Bütler, R., Lachat, T., Larrieu, L., & Paillet, Y., 2013).

Tree Protection Zone (TPZ) – A specified area above and below ground and at a given distance from the trunk, set aside for the protection of a tree's roots and crown to provide for the viability and stability of a tree that is to be retained where it is potentially subject to damage by development.

Structural Root Zone (SRZ) - The area around the base of a tree required for the tree's stability in the ground. The woody root growth and soil cohesion in this area are necessary to hold the tree upright. The SRZ is nominally circular with the trunk at its centre and is expressed by its radius in metres. This zone considers a tree's structural stability only, not the root zone required for a tree's vigour and long-term viability, which will usually be a much larger area.

2 Body Observations Results

Table 1 Individual tree characteristics

Tree Number	Botanical Name (Common Name)	DBH (mm)	DAB (mm)	Canopy N	Canopy S	Canopy E	Canopy W	Height	Health	Age	Condition/ Structure	SULE	Visual Habitat	Landscape	Retention Value	Structural Root Zone (SRZ metres)	Tree Protection Zone (TPZ metres)	≈Construction impact % encroachment or incursion	Retain or Remove notes
1	Tibouchina Sp. (Tibouchina)	200	300	1	1	1	1	4	F	S M	G	3A	No	Low	Very Low	2.0	2.4	0%	Retain
2	Tibouchina Sp. (Tibouchina)	250	400	2	2	2	2	5	F	М	G	3A	No	Low	Very Low	2.3	3.0	0%	Retain
3	Eucalyptus racemosa (Narrow Leafed Scribbly Gum)	750	800	5	5	5	5	12	F-G	Μ	G	2E	No	Very High	High	3.0	9.0	3% New Deck	Retain
4	Banksia ericifolia (Heath Banksia)	250	250	2	2	2	2	4	F	Μ	G	2A	No	High	High	1.8	3.0	100% building	Remove
5	Murraya paniculata (Orange Jessamine)	140	140	1	1	1	1	3	G	М	G	1A	No	Low	Moderate	1.5	2.0	0%	Remove
6	Hibiscus sp	100	100	1	1	1	1	2	G	М	G	1A	No	Low	Moderate	1.5	2.0	0%	Retain (Neighbours)
7	Callistemon viminalis (Weeping bottlebrush)	290	290	2	3	7	0	7	Р	0 Σ	Р	4C	No	Moderate	Very Low	2.0	3.5	0%	Remove

Tree Number	Botanical Name (Common Name)	DBH (mm)	DAB (mm)	Canopy N	Canopy S	Canopy E	Canopy W	Height	Health	Age	Condition/ Structure	SULE	Visual Habitat	Landscape	Retention Value	Structural Root Zone (SRZ metres)	Tree Protection Zone (TPZ metres)	≈Construction impact % encroachment or incursion	Retain or Remove notes
8	Pittosporum undulatum (Sweet Jessamine)	220	220	2	2	2	2	4	F	M	G	3A	No	Low	Very Low	1.8	2.6	0%	Remove
9	Lophostemon confertus (Brush Box)	750	850	5	5	5	5	12	G	M	G	1A	No	Moderate	Moderate	3.1	9.0	0%	Retain
10	Callistemon viminalis (Weeping bottlebrush)	140	140	4	0	2	2	6	F	М	F	3A	No	Moderate	Moderate	1.5	2.0	0%	Remove
11	Melaleuca linariifolia (Snow in Summer)	396	450	4	4	4	4	12	F	М	F	2A	No	Moderate	Moderate	2.4	4.8	0%	Remove
12	Hibiscus sp	100	100	1	1	1	1	2	G	М	G	1A	No	Low	Moderate	1.5	2.0	0%	Remove
13	Cupressus sempervirens (Italian Cypress)	350	350	3	3	3	3	12	G	М	G	1A	No	Low	Moderate	2.1	4.2	0%	Remove
14	Camellia japonica (Camellia)	150	150	1	1	1	1	2	E	М	E	1A	No	Low	Moderate	1.5	2	100%	Remove

3 Discussion

14 trees have been included in this assessment.

Preliminary information regarding the protection of high retention trees was provided on the 21st May 2025 after a site inspection. The proposal utilises most of the existing house substantially reducing the impact to surrounding trees.

Of the trees assessed trees 1, 2, 4, 5, 6, 8, 12, 13 and 14 are either exempt tree species or less than 5 metres and can be removed without council approval. Tree 6 is located in the neighbouring property and cannot be removed.

It is proposed trees 4, 5, 8, 12, 13 and 14 are removed. Trees 1, 2 and 6 will be retained.

Tree 3 is located in the front yard and listed as high retention value. The front of the existing house has been retained to limit any potential damage to tree 3. The proposed deck will be a piered structure reducing any root loss and tree impact. The tree is in Fair-Good health, it has parts of the trunk cambium damaged, possibly by cockatoos. The removal of this bark kills the cambium and could cause a decline in this tree. There is currently enough cambium present, and if growing conditions are favourable, the tree should be able to seal the wounds. It is proposed this tree is retained and protected. See figure 3 below.



Figure 3 Tree 3 with signs of cockatoo damage to the cambium of the tree

Tree 7 is not impacted by the proposed development, yet it has been proposed to be removed because the tree is at the end of its life span, has included bark in a lower junction with decay. The lower branch has a high probability of snapping and damaging the garden shed. This tree should be removed irrespective of the proposed development. See figures 4 and 5 below.







Figure 5 Lower junction of tree 6 with decay, hollow and included bark

It is proposed that the garden be re designed to complement the proposed alterations to the house. Tree 7 is in poor health and although not affected by the works has been proposed to be removed because of its reduced life expectancy.

Tree 11 contains included bark within its junctions. This included bark is minor and the likelihood of injury or damage is minor. As the garden has been proposed to be re designed it is proposed this tree is removed.

Tree 9 is unaffected by the proposed works and will be retained and protected.

4 Recommendations

- 1. Tree numbers 4, 5, 7, 8, 10, 11, 12, 13 and 14 are proposed to be removed.
- 2. Tree numbers 1, 2, 3, 6 and 9 have been proposed to be retained.
- 3. Tree removal/pruning should be conducted by an Arborist with a minimum (Australian Qualification Framework) AQF level 3.
- 4. Work must be undertaken as per the Code of Practice Amenity Tree Industry 1998 and AS4373-Pruning of Amenity trees.
- 5. The tree removal/pruning process and staff should be skilled and undertake the removal of the tree as per the minimum industry standards.
- 6. A tree protection plan has been included in section 7.

5 References

- 1. Bütler, R., Lachat, T., Larrieu, L. and Paillet, Y., 2013. 2.1 Habitat trees: key elements for forest biodiversity. *Integrative approaches as an opportunity for the conservation of forest biodiversity*, p.84.
- 2. Australian Standard, A.S., 4970, 2009. Protection of trees on development sites, Sydney.
- 3. Australian Standard A.S., 4373-2007. Pruning of Amenity Trees, 2007, Sydney
- 4. <a href="https://www.google.com/maps/place/4+Hume+Pl,+Frenchs+Forest+NSW+2086/@-33.7411067,151.2218694,17.71z/data=!4m6!3m5!1s0x6b12a9efd3520557:0x37d84cbc6ca9257!8m2!3d-33.7413084!4d151.2215032!16s%2Fg%2F11c2f65d3z?entry=ttu&g_en=FgovMDI1MDkwMy
 - <u>33.7413084!4d151.2215032!16s%2Fg%2F11c2f65d3z?entry=ttu&g_ep=EgoyMDI1MDkwMy_4wIKXMDSoASAFQAw%3D%3D.</u> Viewed 8th September 2025.
- 5. Mattheck & Breloer 2010. *The Body Language of Trees a handbook for failure analysis*. Research for Amenity Trees series published by The Stationery Office, Norwich, United Kingdom.
- 6. NSW Government e planning spatial viewer, 2020. https://www.planningportal.nsw.gov.au/propertyreports/9de60642-47ca-4f2d-a485-19a7c1d9cbe8.pdf. Viewed 8th September 2025.
- 7. Northern Beaches Council. https://www.northernbeaches.nsw.gov.au/planning-development/tree-management/private-land. Viewed 8th September 2025.
- 8. RFS 10/50. https://www.rfs.nsw.gov.au/plan-and-prepare/1050-vegetation-clearing/tool. Viewed 8th September 2025.
- 9. https://proofsafe.com.au/tpz_incursion_calculator.html. Viewed 8th September 2025.

6 Project Arborist Monitoring Stages

The list of monitoring stages are imperative to the long-term health of those trees to be retained. The principal contractor (Site Builder) should be informed of these requirements as they often form the basis of the conditions of consent for the project. The stages set out below are a minimum requirement to aid in ensuring the long-term health of any tree recommended for retention on the site.

Stage	Action/Task	What is required
1	Ensure tree protection has been installed as per tree protection plan section 7.	Tree Protection Certification
2	Final project arborist inspection.	Final certification summarises the attendance to the site and reason for attendance. Comment on the likely longterm health of the retained trees. Provide any ongoing recommendations.

Tree locations and Tree Protection Plan (Not to Scale) DP203647




Table 1 Plan Legend

Requirement	Total	Tree Number	Legend
Trees to be removed	9	4, 5, 7, 8, 10, 11, 12, 13, 14	Red
Trees to be retained	5	1, 2, 3, 6, 9	Green
Tree Protection Zone (TPZ)	1	3	
Tree Protection Fencing	4	1, 2, 3, 9	

8 Tree Protection specifications

Tree Protection Fencing (See Figure 6)

Tree protection must be undertaken for all trees to be retained on site or surrounding it.

All fencing should be at the perimeter of the Tree Protection Zone (TPZ), unless shown on Tree Management Plan (TMP).

The tree/s to be retained and protected together with their relevant Tree Protection Zone (TPZ) and Structural Root Zone (SRZ) shall be marked on all demolition and construction drawings.

All contractors and workers on site shall be briefed on the tree protection and management procedures in place as part of their site induction. A written record of the induction process is to be kept on site.

The TPZ must be enclosed with a fully supporting chainmesh protective fencing. The fencing shall be secure and fastened to prevent movement. The fencing shall have a lockable opening for access. Roots greater than 30mm diameter are not to be damaged/severed during the construction of the fence. See Figure 6 below.

The enclosed area must be free of weeds and grass, the application of a 75mm layer of leaf mulch to the tree protection zone (TPZ) must be maintained for the duration of works.

Signs at 7 metre intervals are to be attached to the fencing clearly showing the name and contact details of the Project Arborist and the words NO ENTRY TREE PROTECTION ZONE.

No work is to be undertaken within this Tree Protection Zone; this includes:

- -No removal or pruning of retained trees.
- -No construction, stockpiling or storage of chemicals, soil, and cement. Or the movement of machinery, parking and personnel is to occur within the TPZ unless ground protection has been installed.
- -No refuelling, dumping of waste, placement of fill or Soil level changes.
- -No lighting of fires or physical damage to protected trees.
- -No temporary or permanent installation of utilities or signs.
- -No service trenches should pass through the TPZ, stormwater pits must be located outside the TPZ.





Figure 6 An example of tree protection fencing (AS4970-2009)

Trunk/Branch Protection

Hessian/Carpet or similar material is used as a wrap around the trunk/branch to a height of 2 metres from the base of the tree. Covering the hessian are timbers 100x50x2000mm These are to be spaced around the trunk with gaps of approximately 100mm. The timbers are to be secured with metal strapping. These materials are not to be directly fastened to the tree. See Figure 7 and Figure 8



- 1 For trunk and branch protection use boards and padding that will prevent damage to bark. Boards are to be strapped to trees, not nailed or screwed.
- mble boards should be of a suitable thickness to prevent soil compaction and root damage



Figure 8 Trunk Protection

Figure 7 An example of trunk, branch and ground protection (taken from AS4970-2009)

Ground protection 8.2

This is used to protect the Tree Protection Zone (TPZ) from soil compaction. Soil compaction reduces the available pore spaces within the soil, this reduces water holding capacity, oxygen and carbon dioxide diffusion. It can cause water to runoff the soil surface reducing infiltration. Over time a root system in a compact soil (High Bulk Density) declines. As the root system of a tree declines so does its canopy. When soil compaction is severe the entire tree can die.

Where scaffolding, foot traffic or wheelbarrow access is required. The soil surface should be covered by Geotextile fabric followed by plywood sheets 1.2 x 2.4 metres x 18mm thick and then covered by 200mm of mulch to provide a trafficable surface. Timber slats may be required to provide grip to the surface. Driveways or areas that will have heavy vehicles over the soil surface should have geotextile fabric, 100mm of mulch or gravel followed by sleepers 100x 200 x 3000mm. The sleepers are spaced 150mm apart and the gaps filled with gravel or mulch. The sleepers are then strapped together with metal hoop pine to prevent movement.

Irrigation may be required beneath ground protection.





Figure 9 Sleepers with gravel between protecting ground from compaction

8.3 Installation of underground services

All underground services must be routed outside the TPZ of any protected tree. The project arborist must be consulted (or council if required in DA conditions) if works pass through the TPZ of any tree. Methods such as thrust boring/directional drilling or hand excavation, during supervision by the project arborist are methods that reduce impact to surrounding trees. These are acceptable methods under AS 4970-2009.



9.1 Appendix B Methodology for Determining Tree Retention Value

The aim of this process is to determine the relative value of each tree for retention (i.e. its Retention Value) in the context of development. This methodology assists in the decision-making process by using a systematic approach. The key objective of process is to ensure the retention of good quality trees that make a positive contribution to these values and ensure that adequate space is provided for their long term preservation. The Retention Value of a tree is a balance between its sustainability in the setting in which it is located (the 'landscape') and its significance within that setting (landscape significance).

Step 1: Determining the Landscape Significance Rating

The 'landscape significance' of a tree is a measure of its contribution to amenity, heritage, and ecological values. While these values are fairly subjective and difficult to assess consistently, some measure is necessary to assist in determining the Retention Value of each tree. To ensure in a consistent approach, the assessment criterion shown in Table 2 should be used. A Tree may be considered 'significant' for one or more reasons. A tree may meet one or more of the criteria in any value category (heritage, ecology or amenity) shown in Table 2 to achieve the specified rating. For example, a tree may be considered 'significant' and given a rating of 1, even if it is only significant based on the amenity criteria.

Based in the criterion in this table, each tree should be assigned a landscape significance rating as follows:

- 1. Significant
- 2. Very High
- 3. High
- 4. Moderate
- 5. Low
- 6. Very Low
- 7. Insignificant

Step 2: Determining Safe Useful Life Expectancy (SULE)

The sustainability of a tree in the landscape is a measure of its remaining lifespan in consideration of its current health, condition and suitability to the locality and site conditions. The assessment of the remaining lifespan of a tree is a fairly objective assessment when carried out by a qualified Consulting Arborist. Once a visual assessment of each tree is completed (using the Visual Tree Assessment criteria), the arborist can make an informed judgement about the quality and remaining lifespan of each tree. The Safe Useful Life Expectancy (SULE) methodology (refer to Table 3) can be used to categorise trees as follows:

- Long (Greater than 40 years)
- Medium (Between 15 and 40 years)
- Short (Between 5 and 15 years)
- Transient (less than 5 years)
- Dead or Hazardous (no remaining SULE)

The SULE of a tree is calculated based on an estimate of the average lifespan of the species in an urban area, less its estimated current age and then further modified where necessary in consideration of its current health, condition (structural integrity) and suitability to the site.

9.2 Appendix C Table 2 Step 1 Landscape Significance Rating

RATINGS	HERITAGE VALUE	ECOLOGICAL VALUE	AMENITY VALUE
1. SIGNIFICANT	The subject tree is listed as a Heritage item under the Local Environment Plan (LEP) with a local, state, or national level of significance or is listed on Council's Significant Tree Register.	The subject tree is scheduled as a Threatened Species as defined under the Threatened Species Conversation Act 1995 (NSW) or the Environmental Protection and Biodiversity Conservation Act 1999.	The subject tree has a very large live crown size exceeding 100m2 with normal to dense foliage cover, is located in a visually prominent position in the landscape, exhibits very good form and habit typical of the species.
	The subject tree forms part of the curtilage of a Heritage Item (building/structure/artefact as defined under the LEP) and has a known or documented association with that item.	The tree is a locally indigenous species, representative of the original vegetation of the area and is known as an important food, shelter or nesting tree for endangered or threatened fauna species.	The Subject tree makes a significant contribution to the amenity and visual character of the area by creating a sense of place or creating a sense of identity.
	The subject tree is a Commemorative Planting having been planted by an important historical person (s) or to commemorate an important historical event.	The subject tree is a Remnant Tree, being a tree in existence prior to development of the area.	The tree is visually prominent in view form surrounding areas, being a landmark or visible from a considerable distance.
2. VERY HIGH	The tree has a strong historical association with a heritage item (building/structure/artefact/garden etc) within or adjacent the property and/or exemplifies a particular era or style of landscape design associated with the original development of the site.	The tree is a locally indigenous species representative of the original vegetation of the area and is a dominant or associated canopy species of an Endangered Ecological Community (EEC) formerly occurring in the area occupied by the site.	The subject tree has a very large live crown size exceeding 60m2, a crown density exceeding 70% (normal-dense), is a very good representative of the species in terms of its form and branching habit or is aesthetically distinctive and makes a positive contribution to the visual character and the amenity of the area.
3. HIGH	The tree has a suspected historical association with a heritage item or landscape supported by anecdotal or visual evidence.	The tree is a locally indigenous and representative of the original vegetation of the area and the tree is located within a defined vegetation link/wildlife corridor or has known wildlife habitat value.	The tree is a good representative of the species in terms of its form and branching habit with minor deviations from normal (e.g. crown distortion/suppression) with a crown density of at least 70% (normal); The subject tree is visible form the street and/or surrounding properties and makes a positive contribution to the visual character and the amenity of the area.
4. MODERATE	The tree has no known or suspected historical association but does not detract or diminish the value the value of the item and is sympathetic to the original era of planting.	The subject tree is a non-local native or exotic species that is protected under the provisions of the DCP.	The subject tree has a medium live crown size exceeding 25m²; The tree is a fair representative of the species, exhibiting moderate deviations from typical form (distortion/suppression etc) with a crown density of more than 50% (thinning to normal).
			The tree is visible from surrounding properties but is not visually prominent-view may be partially obscured by other vegetation or built forms. The tree makes a fair contribution to the visual character and amenity of the area.
5. LOW	The subject tree detracts from heritage values and diminishes the value of the heritage item.	The subject tree is scheduled as exempt (not protected) under the provisions of this DCP due to its species, nuisance or position relative to buildings or other structures.	The subject tree has a small live crown of less than 25m² and can be replaced within the short term (5-10 years) with new tree planting.
6. VERY LOW	The subject tree is causing significant damage to a heritage item.	The subject tree is listed as an Environment Weed Species in the Local Government Area, being invasive, or is a nuisance species.	The subject tree is not visible from surrounding properties (visibility obscured) and makes a negligible contribution or has a negative impact on the amenity and visual character of the area. The tree is a poor representative of the species, showing significant deviations from the typical form and branching habit with a crown density of less than 50%.

9.3 Appendix D Table 3 Estimating Safe Useful Life Expectancy (SULE) Step 2

1	Estimate the age of the tree	
2	Establish the average life span of the species	5
3	Determine whether the average life span nee	eds to be modified due to local environmental situation
4	Estimate remaining life expectancy	
	• • •	
	Life Expectancy =	average modified life span of species - age of tree
5	Consider how health may affect safety (& lon	gevitv)
	, , , , ,	<i>5 77</i>
6	Consider how tree structure may affect safety	
7	Consider how location will affect safety	
8	Determine safe life expectancy	
	Safe Life Expectancy =	life expectancy modified by health, structure and location
9	Consider economics of management (cost vs	henefit of retention)
J	Outside economics of management (cost vs	Deficit of retention)
10	Consider adverse impacts on better trees	
11	Consider sustaining amenity - making space	for new trees
_		
12	Determine SULE	
	Safe Useful Life Expectancy =	safe life expectancy modified by economics, effects on better trees and sustaining amenity
	Ref. Barrell, Jeremy (1996) Pre-development Tree Assessment	

Proceedings of the International Conference on Trees and Building Sites (Chicago) International Society of arboriculture, Illinois, USA

9.4 Appendix E Safe Useful Life Expectancy (SULE) subcategories

NOTES ON SAFE USEFUL LIFE EXPECTANCY (SULE RATING) AS USED IN TREE DESCRIPTION

TABLE

In a planning context the time a tree can expect to be usefully retained is the most important long-term consideration. Safe Useful Life Expectancy (SULE) is the life expectancy of the tree modified first by its age, health, condition, safety and location (to give safe life expectancy), then by economics, effects on better trees and sustained amenity (Barrel! 1993 and 1995). Trees with short SULE may at present be making a contribution to the landscape but their value to the local amenity will decrease rapidly towards the end of this period, prior to their being removed for safety or aesthetic reasons.

SULE categories


	1 LONG SULE	2 MEDIUM SULE	3 SHORTSULE	4 REMOVALS	5 MOVED OR REPLACED
A	Long: appeared to be retainable all the time of assessment for over 40 years with an acceptable degree of risk, assuming reasonable maintenance.	Medium: appeared to be retainable at the time of assessment for 15 to 40 years with an acceptable degree of risk, assuming reasonable maintenance.	Short- appeared to be retainable at the time of assessment for 5 to 15 years with an acceptable degree of risk, assuming reasonable maintenance.	Removal: trees which should be removed within the next 5 years.	Moved or Replaced: Trees which can be readily moved or replaced
В	Structurally sound trees located in positions that can accommodate future growth	Trees that may only live between 15 and 40 more years	Trees that may only live between 5 and 1 5 more years.	Dead, dying, suppressed or declining trees through disease or inhospitable conditions	Small trees less than 5 metres (m) in height
С	Trees that could be made suitable for long-term retention by remedial tree care.	Trees that may live for more than 40 years but would be removed for safety or nuisance reasons.	Trees that may live for more than 15 years but would be removed for safety or nuisance reasons.	Dangerous trees through damage, structural defect, instability or recent toss of adjacent trees.	Young trees less than 1 5 years old but over 5m in height
D	Trees of special significance for historical, commemorative or rarity reasons that would warrant extraordinary efforts to secure their long term retention.	Trees that may live for more than 40 years but should be removed to prevent interference with more suitable individuals or to provide space for new planting.	Trees that may live for more than 15 years but should be removed to prevent interference with more suitable individuals or to provide space for new planting.	Dangerous trees through structural detects including cavities, decay, included bark, wounds or poor form.	Trees that have been regularly pruned to artificially control growth'
Е		Trees that could be made suitable for retention in the medium term by remedial tree care	Trees that require substantial remedial tree care and are only suitable for retention in the short term.	Damaged trees that are' clearly not safe to retain	
F				Trees that may live for more than 5 years but should be removed to prevent interference with more suitable individuals or to provide space for new planting	
G				Trees that are damaging or may cause damage to existing structures within 5 years	
Н				Trees that will become dangerous after removal of other trees for the reasons given in A) to F).	

9.5 Appendix F Table 4 Determining Tree Retention Values

The Retention Value of a tree is increased or diminished based on its sustainability in the landscape, which is expressed as its SULE. A tree that has a high Landscape Significance Rating, but low remaining SULE, has a diminished value for retention and therefore has an appropriate Retention Value assigned. Conversely a tree with a low Landscape Significance Rating even with a long remaining SULE, is also considered of low Retention Value. This logic is reflected in the matrix shown in Table 1.

Once the landscape Significance Rating and SULE category have been determined, the following matrix can be used to determine a relative value (or priority) for retention:

TABLE 1 – DETERMINING TREE RETENTION VALUES



10 Glossary of Terms and Abbreviations

AGL: above ground level

Basal flare: the rapid increase in diameter that occurs at the confluence of trunk and root crown, associated with both stem and root tissue.

Canopy Spread: measure from one side of the tree to the other, the canopy spread of the tree was estimated.

Condition: refers to the tree's form and growth habit, as modified by its environment (aspect, suppression by other trees, soils) and the state of the scaffold (i.e. trunk and major branches), including structural defects such as cavities, crooked trunks or weak trunk/branch junctions. These are not directly connected with health and it is possible for a tree to be healthy but in poor condition.

Decay: is the result of invasion by fungal diseases through a wound.

Decline: is the response of the tree to a reduction of energy levels resulting from stress. Recovery from a decline is difficult and slow; is usually irreversible.

Diameter at Buttress (DAB): A measurement at the base of the tree above any significant swelling. Above buttressing.

Diameter at Breast Height (DBH)⁽⁴⁾: refers to the tree trunk diameter at breast height (1.4 metres above ground level) Estimated

Dieback: refers to the withdrawal of energy by the tree from some areas of the crown. Symptoms are leaf drop, bare twigs, dead branches and tree death, in order of progression. This can be caused by root damage, root disease, severe bark damage, intensive grazing by insects, abrupt changes in growth conditions, drought, water logging or over maturity. Dieback often implies stress or decline.

Epicormic shoots: are sprouts produced from dormant buds in the bark. Production can be triggered by fire, pruning or root damage but may also be as a result of stress or decline.

Encroachment: The amount of the Tree Protection Zone (TPZ) occupied by a structure activity that affects a tree. The structure or activity does not involve the complete removal of all tree roots. Part of a trees root system is retained.

Future: A time period of 12 months from the date of report. As described by the Land and Environment Court.

Hazard: refers to anything with the potential to harm health, life or property.

Height of tree: refers to the height of the tree from ground level to the highest point of the tree. This is estimated with the use of a clinometer.

Health: refers to the tree's vigour as exhibited by the crown density, leaf colour, presence of epicormic shoots, ability to withstand disease invasion, and the degree of dieback. Listed as Excellent, Good, Fair or Poor.

AIA Version 2 23/9/2025 4 Hume Place French Forest

Inclusion: See weak junctions

Incursion: The amount of the Tree protection Zone (TPZ) where all of the root system has been proposed to be removed. Measured as a percentage or in square metres.

Sparse crown: refers to reduced leaf density, often a precursor to dieback and may imply stress or decline. Also, possibly a response to drought or root damage.

Topping: or heading is a pruning practice that results in removal of terminal growth leaving a cut stub end. Topping causes serious damage to the tree.

Weak junctions: are points of possible failure in the scaffold. They are usually caused by the trunk or branch bark being squeezed within the junction so that the necessary interlocking of the wood fibres does not occur, and the junction is forced open by the annual increments in growth. This is often a genetic problem.

Weed species: are plants that are known to invade native remnant bushland. The species concerned may be exotic or may be native species from other parts of Australia.

Wounds: are areas where the bark has been damaged by branch breakage, impact or insect attack. Some wounds decay and cause structural defects or weakness. Healthy trees are able to resist and contain infection by walling off areas within the wood. Tree wounds are often eventually covered over by new bark but the walled off or infected areas still remain internally and may lead to weakness of the heartwood.

11 Qualifications and Experience

TRISTAN BRADSHAW

Postal Address: PO Box 48 St Ives, NSW. 2075.

Mobile: 0411 608 001 Email: bradshawarborists@gmail.com

Consulting Arborist Registered Number 1286

Professional Memberships

Member of Arboriculture Australia No. 1286 (Certified Practicing Consulting Arborist)

Qualifications

2022 Tree Risk Assessment Qualification renewal (TRAQ) held since 2015.

2016-2018 Graduate Certificate in Arboriculture AQF8 at Melbourne University.

2015 Tree Risk Assessment Qualification (TRAQ)

2013-2014 Diploma of Arboriculture AQF5 at Ryde TAFE. Distinction

2012 Certificate III in Arboriculture at Ryde TAFE

2011 Certificate IV in Occupational Health and Safety

2010 Aboriginal Sites Awareness Course by Aboriginal Heritage Office

1996-1999 Bachelor of Horticultural Science at University of Sydney. Honours+

Tristan Bradshaw has been involved in the Horticultural and Arboricultural Industry since 1995. The business Bradshaw Horticultural Services was formed and incorporated Horticultural consulting work and landscaping. In 2000 Tristan undertook the Level 2 Arboriculture course at Ryde TAFE. The business progressively specialised in consulting, tree removal, pruning and stump grinding works. Extensive hands-on knowledge was developed during the climbing of trees undertaking pruning or removal and during storm events understanding the tolerances of trees.

In 2009 the new business name Bradshaw Tree Services was registered to reflect works only being undertaken in the tree industry. The business operated throughout Sydney employing up to 25 people. Tristan Bradshaw's main role was as a consultant advising clients and writing reports. In 2019 Bradshaw Tree Services ceased operations and Tristan Bradshaw began Bradshaw Consulting Arborists exclusively undertaking tree consultancy.

Tristan Bradshaw with continued education has attained a Level 8 qualification, attends every annual Arboriculture Australia conferences taking part in the seminars to broaden his knowledge.

This assessment was carried out from the ground and covers what was reasonably able to be assessed and available to this assessor at the time of inspection. No subterranean inspections were carried out. The preservation methods recommended where applicable are not a guarantee of the tree survival but are designed to reduce impacts and give the trees the best possible chance of adapting to new surroundings.

Limitations on the use of this report:

This report is to be utilised in its entirety only. Any written or verbal submission, report or presentation that includes statements taken from the findings, discussions, conclusions or recommendations made in this report, may only be used where the whole or the original report is referenced in, and directly attached to that submission, report or presentation.

Assumptions:

Care has been taken to obtain information from reliable resources. All data has been verified insofar as possible: however, Bradshaw Consulting Arborists can neither guarantee nor be responsible for the accuracy of information provided by others.

Unless stated otherwise:

- -Information contained in this report covers only the tree/s that was/were examined and reflects the condition of the tree at the time of the assessment: and
- -The inspection was limited to visual examination of the subject tree without dissection, excavation, probing or coring. There is no warranty or guarantee, expressed or implied, that problems or deficiencies of the subject tree may not arise in the future.
- -The assessment does not identify hazards and associated risk; this report is not a risk assessment.

Yours sincerely,

Tristan Bradshaw

Thu Mu

BHort Sci (USYD), Dip Arb AQF 5 (TAFE), Grad Cert AQF 8 (UMELB), TRAQ