

Our Ref: C-09-024-1

7 August 2009

The General Manager
Pittwater Council
PO Box 882
MONA VALE NSW 1660

Dear Sir or Madam,

Re: Construction Certificate (New Garage) 137 Riverview Road, Clareville Development Consent No. No.071/09

I refer to our engagement in respect of the above and enclose the Construction Certificate for such in accordance with the provisions of clause 142(2) of the Environmental Planning and Assessment Regulation 2000.

Please find enclosed a cheque for \$30.00 being the regulated registration fee for the above as detailed in Clause 263 of the Environmental Planning and Assessment Further Amendment (Quality of Construction) Regulation 2004. It would be appreciated if a receipt in this regard could be forwarded to our firm as soon as possible.

RC 7636023.

Should you require any further information please do not hesitate to contact me.

Yours faithfully,

Donohoe

Tom Donohoe

Tom Miskovich & Associates Pty Ltd

Encl.





## **Construction Certificate Mr Roger Jones**

Alterations and Additions ( New Garage)

137 Riverview Road, Clareville

Reference No: C-09-024-1

Dated: 7 August 2009

#### Construction Certificate C-09-024-1

This certificate is issued by a certifying authority (a council or a private certifier) and verifies that, if the applicant carries out the proposed work in accordance with the plans and specifications that are approved, the work will comply with the environmental planning and assessment regulation 2000 as referred to in section 81a(5) of the environmental planning and assessment act 1979

#### **Applicant**

name:

Mr Roger Jones

address:

137 Riverview Road CLAREVILLE NSW 2107

phone no:

9918 5455

fax no:

mobile:

0407 189 437

email:

rogersuejones@bigpond.com

Owner

name:

Mr Roger Jones

address:

137 Riverview Road CLAREVILLE NSW 2107

phone no:

9918 5455

fax no:

mobile:

0407 189 437

email:

rogersuejones@bigpond.com

Property details

address:

137 Riverview Road CLAREVILLE NSW 2107

lot, d.p, s.p, vol, fol:

Lot 5 DP 19402

Owner builders permit no

name:

Suellen Jones

licence no: n/a

owner builders permit: 367455P

address:

137 Riverview Road CLAREVILLE NSW 2107

phone no:

9918 5455

fax no:

mobile:

email:

Description & value of development

description of works:

Alterations and Additions (New Garage)

value of works:

\$49,500.00

**Building Code of Australia** 

bca classification:

10a

bca version

2009

applicable:

type of construction:

N/A



#### **Construction Certificate C-09-024-1**

#### Details of development consent

#### Consent authority

name:

Pittwater Council

Development consent

development consent no:

No.071/09

date of determination:

26 May 2009

#### Determination

determination:

approved

#### Certifying authority

name:

Tom Donohoe

accreditation no:

BPB0096

address:

PO Box 189 PENNANT HILLS NSW 1715

phone no:

02 9484 6999

project building surveyor

for enquires:

Tom Donohoe

certificate:

I certify that the work if completed in accordance with the documentation accompanying the application for the certificate (with such modifications verified by the certifying authority as may be shown on that documentation) will comply with the requirements of this regulation as referred to in section 81a (5) of the environmental planning and assessment act 1979

signature:

Danohoe

date of determination:

7 August 2009

#### **Attachments**

certificate application details

annexure 1

documents that form part of this certificate

annexure 2

other supporting documentation

annexure 3





#### **Annexure 2**

**Documents that form part of this Certificate** 

Construction Certificate Documentation Certificate Number C-09-024-1 Premises 137 Riverview Road, Clareville

#### Documents that form part of certificate number C-09-024-1

137 Riverview Road, Clareville

Architectural documentation & specification prepared by Warwick Werner Architect Pty Ltd.

Drawing No.	Revision	Title	Date
WD-26	Α	Site Plan	14 July 2009
WD-27	С	Floor Plans	14 July 2009
WD-28	В	North & South Elevations	14 July 2009
WD-29	В	East & West Elevations Section A-A	14 July 2009
Specification (pg 1)		General requirements	14 July 2009
Specification (pg 2)	-	General requirements	14 July 2009
Specification (pg 3)		General requirements	14 July 2009
Specification (pg 4)		General requirements	14 July 2009
Specification (pg 5)		General requirements	14 July 2009
Specification (pg 6)		General requirements	14 July 2009

#### Structural documentation & specification prepared by D'Ambrosio Consulting.

Drawing No.	Revision	Title Lower and Upper Floor Plans and Details	<b>Date</b> 15 July 2009
6.01 6.02	A	Lower and Upper Floor Sections Sheet 2	15 July 2009
6.03 7.01	A A	Lower and Upper Floor Sections Sheet 2 Roof Plan and Section	15 July 2009 15 July 2009

#### Reports, Design Statements & Other Supporting Documents

Title	Prepared by	Dated
Letter confirming compliance with various DA conditions	Warwick Werner Architect Pty Ltd	15 July 2008
Receipt for Long Service Levy payment	Long Service Payments Corporation	21 July 2009
Certificate of Structural Adequacy	D'Ambrosio Consulting	16 July 2009
Form no. 2 – Geotechnical Risk Management Policy	D'Ambrosio Consulting & Jack Hodgson Consultants	29 July 2009
Consent by Road Authority for work in Road	Pittwater Council	22 July 2009
Reserve- Driveway		
Owner Builder Permit 367455P	NSW Office of Fair Trading	5 August 2009
Record of site inspection prior to issue of Construction Certificate	Tom Donohoe/Tom Miskovich &Associates	27 July 2009





#### **Annexure 3**

Other Supporting Documentation

Construction Certificate Documentation
Certificate Number C-09-024-1
Premises 137 Riverview Road, Clareville





#### Facsimile / Email

Attention:

Company:

Pittwater Council

Fax No:

9970 7150

Date:

7 August 2009

From:

Tom Donohoe

Pages:

7

(incl this page)

Our ref:

C-09-024-1

Re: Notice to Commence Works and Appointment of Principal Certifying Authority form
Premises:137 Riverview Road, Clareville

This facsimile is confidential and intended for the named addressee (s). It may contain legally privileged information. If you receive this facsimile in error please advise us immediately.

Message:

To whom it may concern,

Please find attached the following documents associated with section 81A of the Environmental Planning and Assessment Act 1979:

- Notice to commence works form,
- Copy of application confirming nomination of PCA by person having benefit of development consent; and
- Owner-Builder permit details.

Should you need to discuss anything in this regard please do not hesitate to contact me.

Regards,

**ORIGINAL IN POST:** 

Mondoe

YES

NO

#### Notice to commence building work and appointment of a principal certifying authority

**Applicant** 

name:

Mr Roger Jones

address:

137 Riverview Road CLAREVILLE NSW 2107

phone no:

9918 5455

fax no:

mobile:

0407 189 437

email:

rogersuejones@bigpond.com

Owner

name:

Mr Roger Jones

address:

137 Riverview Road CLAREVILLE NSW 2107

phone no:

9918 5455

fax no:

mobile:

0407 189 437

email:

rogersuejones@bigpond.com

Property details

address:

137 Riverview Road CLAREVILLE NSW 2107

lot, d.p, s.p, vol, fol:

Lot 5 DP 19402

Description of works proposed

type of work proposed:

Building

description of works:

Alterations and Additions (New Garage)

**Details of approvals** 

consent no:

development

No.071/09

date of consent: 26 May 2009

consent

Pittwater Council

authority:

construction

C-09-024-1

date of

accredited

Tom Donohoe

certificate no:

certificate:

7 August 2009

certifier:

Owner builders permit no

name:

Suellen Jones

licence no: n/a

owner builders permit: 367455P

address:

137 Riverview Road CLAREVILLE NSW 2107

phone no:

9918 5455

fax no:

mobile:

email:



#### Notice to commence building work and appointment of a principal certifying authority

	Have you attached to this notice evidence that the licensed person is insured to carry out this type of work		
yes			
no	$\boxtimes$	building works are to be undertaken by a person with an owner-builders permit?	
no		then have you attached to this notice a declaration (signed by each owner of the land) that the reasonable market cost of the labour and materials to be used is less than \$12,000?	
n/a		proposed building contains a rise in stories of more than 3 and contains 2 or more separate dwellings.	
n/a		proposed works are commercial/industrial.	
Date the work will commence			
on or af	ter:	10 August 2009	

#### Principal certifying authority

I acknowledge

- that I have seen evidence that the builder is licensed and insured, or,
- that I have seen evidence that the building works are to be undertaken by a person with an owner-builders permit, or.
- that the proposal is not "residential building work" and does not require the builder to be licensed under the home building act 1989, or,
- the proposed building contains a rise in stories of more than 3 and contains 2 or more separate dwellings and are exempt from howi under the provisions of the home building amendment (insurance exemptions) regulation 2003, and that I have seen evidence that the builder is licensed.
- In accordance with section 81a of the ep & a act 1979 that I have been appointed by the applicant to carry out the role of the principal certifying authority for this development (copy of application form attached).

name: Tom Donohoe accreditation no: BPB 0096

address: po box 189 pennant hills nsw 1715

phone no: 02 9484 6999
project building surveyor for enquires: Tom Donohoe

date of determination: 7 August 2009

Signature

#### **Privacy policy**

Donohoe

The information in this notice is required under the environmental planning and assessment act 1979 if a person is going to erect a building or carry out subdivision work. The information will be held by us and by the council.



#### WARWICK WERNER ARCHITEC

PTY. LIMITED ACN 077 722 779

4 WANAWONG RD. AVALON BEACH NSW AUSTRALIA 2107 Telephone: 02 9918 5455 Facsimile: 02 9918 5462 Mobile Phone: 0402 038 109 Email: wernerdesign@avalonbeach.ney.au

15 July 2008

Ref: TM-RSJ-10-LTR.wpd

Tom Miscovich & associates P.O.Box 189 **PENNANT HILLS NSW 2120** 

Attention:

**Tom Donohoe** 

Dear Tom,

PROPOSED NEW GARAGE 137 RIVERVIEW RD CLAREVILLE Re:

Please find enclosed 3 hard copies of the following architectural drawings and specification ISSUED FOR CONSTRUCTION CERTIFICATE. Pdf copies of all documents are contained on the separate enclosed disk.

WD-26-A Site Plan WD-27-C Floor Plans WD-28-B

North & South elevations East & West Elevations, Section A-A WD-29-B

A3 Specification Pages 1-6

The issues contained in your email 2<sup>nd</sup> July 2009, to which I am responding, are addressed below.

Condition	Issue	Method of Compliance
DA Condition	s	
B3	Verification that proposed screen planting will screen 50% of built form from street	Requirement for compliance is contained in Specification 15 LANDSCAPING: 15.6 Planting - Required Planting. The plants proposed are listed in 16 SCHEDULES: 16.2 Planting Schedule - Schedule of screen planting. Evidence as to the suitability of the planting is given by the mature height verified in the Pdf document Plant List is on the enclosed disk.
B6	Proposed Native Tree canopy	Requirement for compliance is contained in Specification 15 LANDSCAPING: 15.6 Planting - Required Planting. The plants proposed are listed in 16 SCHEDULES: 16.2 Planting Schedule - Schedule of screen planting. Evidence as to the suitability of the planting is given by the mature height verified in the Pdf document Plant List is on the enclosed disk
B11	Verification that any new fencing will be passable by native wild life	No new fencing was included in the Development Application or proposed as part of this application for Construction Certificate.
B13	Verification that no white or light coloured roof materials will be used	Compliance with this condition is contained in Specification16 SCHEDULES: 16.1 Schedule of External Finishes. These are as submitted with Development application and approved. Refer Pdf document Impact Statement is on the enclosed disk.

#### General BCA requirements

3.1.3	Termite Treatment	Refer Specification 1 GENERAL REQUIREMENTS: 1.4 Termite Protection
3.4.3	Timber Framing	Refer Specification 4 TIMBER AND STEEL CONSTRUCTION: 4.1 General - Standards
3.5.1	Roof Cladding	Refer Specification 7 ROOFING: 7.3 Metal Roofing - Design and installation
3.5.2	Gutters and Downpipes	Refer Specification 7 ROOFING: 7.4 Roof Plumbing - Selection and installation of rainwater goods
3,5.3	Wall Cladding	Refer Specification 10 CLADDING :10.3 Moisture Protection - General
3.6	Glazing	Refer Specification 9 DOORS & WINDOWS: 9.2 Materials & Components - Glass
3.9.1	Stair Construction	Refer Specification 4 TIMBER & STEEL CONSTRUCTION : 4.8 Timber & Steel Stairs - General
3.9.2	Balustrades	Refer Specification 4 TIMBER & STEEL CONSTRUCTION : 4.7 Handrails & Balustrades - General & Standards

Yours faithfully,

WARWICK WERNER ARCHITECT PTY. LIMITED

WARWICK WERNER

C-09-024-TD
DEGEIVED
1 24 JUL 2009
BY:

#### 4. SHALE SLOPES (SS)

These are usually steep slopes which either occur below the Hawkesbury Sandstones, or have Narrabeen Shales and sandstones as the parent material. They generally support open forest communities

#### A. Tall Open Forests and Open Forests:

#### Trees

COMMON NAME	SCIENTIFIC NAME	CHARACTERISTIC
Black She-oak	Allocasuarina littoralis	Good screen tree. Deep fissured bark and cones cylindrical with flat apex.
Forest Oak	Allocasuarina torulosa	Good screen tree. Deep fissured bark and cones ball-like.
Sydney Red Gum/ Smooth-barked Apple	Angophora costata	Orange to salmon coloured smooth bark. Branches contort and twist.
Roughbarked Apple	Angophora floribunda	Bark is brown and fibrous on all limbs with contorted upper limbs.
NSW Christmas Bush	Ceratopetalum gummiferum	Flowers small and white. Fruits swell to an attractive bright red in summer.
Bangalay Gum	Eucalyptus botryoides	Rough reddish bark with salt resistant leaves.
Spotted Gum	Eucalyptus maculata	Tall tree with smooth spotted-skin bark.
Blueberry Ash	Elaeocarpus reticulatus	Small tree with attractive fringed and bell shaped white flowers.
Grey Gum	Eucalyptus punctata	Grey bark with large cream patches. Favoured koala food tree.
Bastard Mahogany	Eucalyptus umbra	Deep fibrous bark with leaves thick and tough.
Turpentine	Syncarpia glomulifera	Straight trunk with deep fibrous bark and flowers cream to white in clusters
Native Peach	Trema aspera	Leaves are an elegantly shaped like peach tree leaves with bisexual flowers.

#### Shrubs:

Banksia spinulosa	Banksia flower being a major food source for birds and possums.
Callistemon linearifolium	Bright red flowers providing nectar for birds.
Cassinia longifolia	Leaves flat and long with flower heads within white bracts.
Comesperma ericinum	Slender shrub with bright pink to purple clusters of matchhead-like flowers.
Dodonaea triquetra	Soft leafy shrub with thin textured leaves.
Grevillea sericea	Flowers are pink to purple tolerating dry, open areas.
Grevillea linearifolia	Graceful slender shrub with flowers a variety of white/red/pink in colour.
Jacksonia scoparia	Grey to green leafless shrub. Flowers are yellow with red markings.
Leptospermum trinervium (formerly L.attenduatum)	Stout trunk and papery-flaky bark with white flowers.
Macrozamia communis	Large tufted fern-like shrub with long spiky leaves and fleshy red seeds.
Notelaea longifolia	Leaves are olive green and fruits black olive- like.
	Callistemon linearifolium  Cassinia longifolia  Comesperma ericinum  Dodonaea triquetra Grevillea sericea  Grevillea linearifolia  Jacksonia scoparia  Leptospermum trinervium (formerly L.attenduatum) Macrozamia communis

Bleeding Heart

Omalanthus populifolius

Large heart-shaped leaves turning red before falling.

Native Holly

Oxylobium ilicifolium

Erect spikey shrub, flowers yellow with red

markings.

Flat-pea

Pultenaea

Platylobium formosum

Scrambling pea-shrub with leaves heart-

Carrot Tops Platysace linearifolia shaped and flowers yellow with red markings. White flowers in dense clusters and soft

thread-like foliage.

Elderberry Panax

Polyscias sambucifolia

Flowers green to yellow in clusters with

purple fruits.

Pultenaea elliptica

Small erect shrub with flowers rich yellow

with dark red markings.

Rapanea

Tiny pale-yellow flowers clustered on old

wood.

Wikstroemia

Leaves hairless and soft with shiny red

fruiting berries.

Wilkiea Grass Tree Wilkiea huegeliana

Stiff leathery leaves with yellow flowers. Long grass-like leaves with a tall flower spike. The rich nectar is food for birds and

Zieria smithii Zieria

#### Herbs, Climbers and Scramblers

Appleberry

Billardiera scandens

Desmodium

Desmodium rhytidophyllum

Kangaroo Grape

Cissus antarctica

False Sarsparilla/

Sweet Tea

Hardenbergia violacea

Twining Guinea Flower

Hibbertia dentata

Dusky Coral Pea

Kennedia rubicunda

Jasmine Morinda

Morinda jasminoides

Wonga-Wonga Vine

Pandorea pandorana Stephania japonica

Snake Vine

Rapanea variabilis

Wikstroemia indica

Xanthorrhoea spp.

insects.

Strong fragrant foliage with tiny pink flowers.

Slender climber or scrambler with edible purple fruits.

Scrambler with rusty felt all over leaves and

tiny pink flowers.

Robust woody climber with glossy black

edible fruit.

Attractive twiner with rich purple pea

flowers. Leaves boil to a tea.

Scrambling vine with toothed leaves and

yellow flowers.

Robust twiner with large red pea-flowers with

black markings.

Scrambling climber. Flowers cream with

orange-blossom fragrance.

Tall woody climber with white cascades of

flowers in Spring

Climber with leaves heart-shaped and fruit

shiny yellow to orange or red.

#### Ferns

Blechnum

Rasp Fern Common Maidenhair Umbrella Fern

Blechnum spp. Doodia aspera Adiantum aethiopicum Sticherus flabellatus

Fern with leathery fronds. Small erect fern with rough fronds. Delicate fern found in dense colonies. Erect fern to 1m high with fronds finely toothed.

#### B. Coastal Heaths (on Shale slopes):

#### Trees:

Lillypilly

Acmena smithii

Dense dark glossy foliage with fruit

Coastal Banksia

Banksia integrifolia

succulent and edible. Leaves are a stiff, leathery dark-green above with white hairs below.

#### BLUEBERRY ASH

Elaeocarpus reticulatus




UPRIGHT AND SLENDER, this young tree will broaden as it matures, although the crown never becomes massive.

#### FEATURES



This pretty evergreen tree is native to the sheltered coastal gullies of eastern Australia, from Tasmania north to southern Queensland. This is a good specimen tree for smaller gardens but also makes a suitable park tree, either alone or in mixed plantings. It can grow in the open and is also well suited to sheltered, shady situations. It is also adaptable to growing in large tubs.





THE DAINTY FRINGED flowers of blueberry ash come in either pale pink or white. They are reason enough for growing this small tree.

#### **Features**

In tubs blueberry ash can be kept to a height of about 3 m. It rarely grows more than 8–10 m high planted in the ground except in its natural habitat where it can reach 15 m. The crown spreads to no more than 5 m wide. The foliage is reddish when young, ageing to a dark green with a somewhat leathery texture. The bell-shaped flowers are white in the species but the palest pink in some of the cultivars. Some of the pink-flowered forms are outstanding, especially 'Prima Donna'. The flowers are reminiscent of lily-of-the-valley.

#### CONDITIONS

C1:	-
Climate	(

Grows best in warm to tropical climates but will tolerate a temperature as low as freezing.

Aspect

Tolerates full sun, but for the best results find a sheltered spot in partial shade.

Soil Soil she

Soil should be heavily enriched with organic

matter and well drained.

#### GROWING METHOD

#### Propagation

Grows from seed, but cultivars are grown from semi-hardwood cuttings taken through

summer into early autumn.

#### Watering

Keep soil moist through spring and summer and water regularly if there is no rain. A slow release fertiliser or blood and bone can

#### **Fertilising**

A slow release fettiliser or blood and bone ca be applied in early spring.

Problems Pruning No specific pest or disease problems known.

See page 14.

#### FLOWERING/FRUITING

#### Season

Sprays of delicate fringed flowers, which are occasionally used in wedding bouquets, appear from mid-spring through to early summer. After the flowers fall, small berries form. The berries ripen to a rich deep blue.

Leaves leathery, blunt-toothed edges, dark green on upper surface, paler underneath, to 20 cm (8 in) long. Orange-brown cylindrical flower spikes, to 18 cm (7 in) long, in spring. Zones 9–10.

#### Banksia speciosa SHOWY BANKSIA

- 3-5 m (10-17 ft) ↑3-6 m (10-20 ft)

Shrub from Eyre district of southern Western Australia. Leaves long, narrow, toothed to midrib, creating zigzag effect. Flower spikes to 15 cm 6 in) long, conical, woolly, pale green to light yellow, in summer—autumn. Zones 9–10.

#### Banksia sphaerocarpa

→ 2 m (7 ft) 12 m (7 ft) Widespread in southwest Western Australia. Low branching shrub, fine pine-like foliage. Unusual globular flowerheads, pinkish in bud turning bronze-yellow on maturity, year round but main flush in spring—summer. Large rounded follicles. Best suited to winter-rainfall areas. Zones 9–10.

#### Banksia spinulosa

-- 0.9-2 m (3-7 ft) ↑ 0.9-3 m (3-10 ft)

Shrub from east coast of Australia. Leaves linear, 5-8 cm (2-3 in) long, white undersides. Flower spikes cylindrical, to 12 cm (5 in) long, golden vellow with gold, red, or blackish hooked styles, in autumn-winter. Fire tolerant. Under cultivation tolerates pruning. B. s. var. collina (syn. B. collina), serrated leaf margins, paler yellow flowers. B. s. var. cunninghamii, tall plant, large yellow spikes; 'Lemon Glow', pale yellow-flowered form. B. s. 'Birthday Candles', 50 cm (20 in) high, 90 cm (36 in) wide; 'Coastal Cushion', coastal form of species, 50 cm (20 in) high, 150 cm (60 in) wide; 'Golden Candles', amber flower spikes; 'Honeypots', open-branched shrub, flowers golden, red styles, in summer-winter. Zones 9-11.

#### BAUERA

Bauera is an eastern Australian genus of just 4 species. Named by English botanist Sir Joseph Banks in honor of 2 German botanical artists, this was among the first genera of Australian plants to be described. Once included in the saxifrage (Saxifragaceae) family, these evergreen wiry-stemmed shrubs are now regarded as better placed in the family (Daniel aceas). The semi-



Banksia spinulosa



Banksia speciosa

leaves, borne in opposite pairs, are trifoliate but stalkless, their leaflets appearing like a whorl of 6 small leaves at each node. Bowl-shaped flowers arise from the leaf axils in spring and data, summer



Banksia speciosa, in the wild, Esperance, Western Australia

CULTIVATION: Bauera plants are easily grown and their requirements are undemanding. They do best in well-drained, light, sandy soil with added harmas for moisture retention.

cold, so some shade from the hattest afternoon sun is appreciated, as as shelter during winter. Occasional trimming will keep the busias of the pact. Propagate from seed or the formational outlings.

#### HOP BUSH

#### Dodonaea species



IN SUMMER. fruits of Dodonaea viscosa are a rich red-brown.
This species has a wide geographical range, adapting to most climates.



THE INFLATED winged fruits of Dodonaea triquetxa are far more decorative than its flowers, which are very insignificant.

#### FEATURES




Sun



Partial Shade

The inflated winged capsules of the hop bush were used in brewing by early European settlers, thus accounting for the common name. Most species are shrubs from 1 to 3 m high. Although many species exist, few are common in cultivation. *Dodonaea viscosa* and its purple-leaved form, var. *purpurea*, make good screening or background plants, growing 1.5–3 m high. Leaves are generally linear, shiny and sticky to the touch, but their shape can be variable. Flowers are insignificant but the winged capsules are most decorative. *D. triquetra*, 1–3 m high, is a species that rapidly colonises bare ground after bushfires.



#### CONDITIONS

Climate Hop bush is adaptable to almost any climate

and will tolerate some frost.

**Aspect** Grows in full sun or partial shade.

Soil Adapts to any reasonably well-drained soil.

#### GROWING METHOD

Propagation Grows from seed or from firm tip cuttings

taken from late spring through summer.

Watering Give regular deep waterings until well established; then it tolerates drought well.

Fertilising Responds well to light applications of blood

and bone or slow release fertiliser in spring.

**Problems** Scale insects are an occasional problem,

especially on D. triquetra.

#### FLOWERING

Season

Insignificant flowers with no petals appear in late winter through spring. The winged capsules that form after flowering become gold to reddish pink in the sun.

#### PRUNING

General

Prune regularly to keep plants compact. In frost-free areas cut back at any time.

#### BLEEDING HEART

#### Omalanthus populifolius



BLEEDING HEART is ideal for planting as a nurse tree while you establish slower growing plants. It quickly provides shelter.



THE BRIGHT RED of ageing leaves adds light to this fast-growing shrub, which is mainly grown for its foliage.

#### FEATURES




Shade



Partial Shade

Sometimes called native poplar, this fast-growing shrub or small tree often appears as a seedling in gardens. It is very attractive to birds that eat the seeds and deposit them in their droppings. Although scorned by some gardeners, it is an attractive and useful plant for its own sake and it can also be used as a nurse plant to protect other, slower growing species. It will grow from 2.5 to 5 m in height and its heart-shaped leaves have long, reddish stems or petioles. The older leaves turn a brilliant red before falling, adding a bright touch. The greenish yellow, tassel-like flowers are obvious but not very decorative. Young plants make attractive pot specimens.



#### CONDITIONS

Climate Aspect Soil Grows easily in any frost-free region.

Does well in shade or filtered sunlight.

Although tolerant of poor soil, this plant must have good drainage and does best in soils enriched with organic matter.

#### GROWING METHOD

Propagation Grows easily from ripe seed that matures

during summer to early autumn. It can also be grown from firm tip cuttings taken from late

spring through summer.

Watering Regular water during the warm months will

produce a better looking plant but this is a

great survivor that tolerates neglect.

Feeding is generally not necessary if the plant

is mulched and grown in humus-rich soil.

Not usually troubled by pests or disease.

#### FLOWERING/FRUITING

Season

Fertilising

**Problems** 

Flowers appear during summer. The fruits that follow ripen during autumn.

#### PRUNING

General

Pruning is not usually needed. Tip prune after flowering to avoid fruit set.

#### LILLY PILLY

Syzygium species



A YOUNG TREE of Syzygium wilsonii thrives in a warm sheltered corner of this lovely bush garden.



RICH SALMON PINK colour on the new leaf growth is as decorative as any flower. New pink growth is a feature of this tree group.

#### FEATURES



There are about five hundred species of lilly pilly, but few are cultivated as ornamental trees. These evergreens have glossy, dark green foliage, usually a bright pinky-red colour when young. The fluffy flowers are cream coloured in most species. After flowers fall, small, edible and decorative fleshy fruits form. They are round- or pear-shaped and grow in a range of colours, mostly pink, red or mauve. Lilly pillys create fairly heavy shade and because of their flowers and fruits are unsuitable for planting near swimming pools or along paths as droppings can be hazardous for pedestrians.

#### **Varieties**

Small-leafed lilly pilly, *S. luehmannii*, grows 6–8 m high with a rounded crown about 6 m across, but may be larger in ideal conditions. Its small, pear-shaped fruits are bright coral red when ripe. *S. paniculatum*, also known as brush cherry, has round, cerise-pink fruits and grows 15 m or more high and 10 m wide. A very large species, *S. francisii*, grows over 20 m high and wide. It is a magnificent tree for large gardens and parks and its fruit are small, round, violet berries. Small forms, such as 'Lilliput' and 'Bush Christmas', grow in tubs.

#### CONDITIONS

Climate Aspect Soil Prefers a warm subtropical to tropical climate. Needs sheltered spot in full sun or light shade. Soil must be deep, rich in organic matter and free draining.

#### GROWING METHOD

**Propagation** Grows from seed removed from ripe fruits as

they fall, usually in autumn.

Watering Needs regular, deep watering through dry

spells in spring and summer.

Fertilising A slow release fertiliser may be applied to

young trees in spring. Manure or compost mulches supply most nutrients required.

**Problems** Some are attacked by wax scales, which secrete

honeydew that allows sooty mould to grow. Spray with white oil while trees are young. New growth may be attacked by sap-sucking psyllids, which cause pimple-like blisters. Control is difficult without systemic sprays. S. luehmannii seems fairly resistant to attack.


See page 14.

Pruning

#### FLOWERING/FRUITING

Season

Most flower during spring or summer. The fruits ripen in late summer to autumn.



C-09-024-TD

SCANNED

21 July 2009

MECETWE

**ROGER JONES** 137 RIVERVIEW RD **CLAREVILLE NSW 2107** 



**Building and Construction Industry** Long Service Payments Corporation Level 1 19-21 Watt Street Gosford NSW 2250 Locked Bag 3000 Central Coast MC NSW 2252 Tel: 13 14 41 Fax: (02) 9287 5685 Email: info@lspc.nsw.gov.au www.lspc.nsw.gov.au ABN 93 646 090 808

As per your request for a copy of your receipt no. 00070957 dated 21 July 2009, the following information is provided:

Received from: (Name of person or organisation paying for levy) the amount of **ROGER JONES** \$173.00

Payment details:

Online

00571269886 \$173.00

being payment for Long Service Levy as detailed below

Levy Payment Form number 5000765

Council/Department/Authority

PITTWATER COUNCIL

C.C. Number CC-09-024

Work address 137

RIVERVIEW RD


CLAREVILLE NSW 2107

Estimated value of work \$49,650.00 Levy payable (No exemption) \$173.00

Total levy paid \$173.00

Signed:

Date



D'Ambrosio Consulting Pty Ltd
ACN 058 635 822 Structural Engineers
Suite 4/153 Victoria Road Glodesville
PO Box 251 Glodesville NSW 1675
Tel (02) 9879 5577 Fax (02) 9879 5588
Email: dambrosioconsultina@biapond.com

Ref: S4443

16 July, 2009

The General Manager
Pittwater Council
Administrative Offices
Vuko Place
Warriewood NSW 2102

Dear Sir / Madam,

Re: 137 Riverview Rd, Clareville - Certificate Of Structural Adequacy (New Garage & Driveway).

This letter is to certify to council that the structural details shown on the accompanying structural drawings S4443 – 6.01, 6.02, 6.03 & 7.01 have been designed in accordance with the structural requirements of The Building Code Of Australia and will be safe for the maximum anticipated loadings as outlined in AS1170.0, 1,2 & 4. The new structural elements will be framed out of structural steel and timber, supported off reinforced concrete piers, founded to sandstone bedrock. The structural system for the new garage is a combination of braced structural steel and portal frame action. The concrete floor and access driveway have been designed for an applied live-load of 750 kg/m2 (to allow for truck loading and storage), and the building designed for a terrain category 2.5 wind exposure (from the south). The new timber framing is to be constructed in accordance with the requirements of AS1684 – Residential Timber Framing Code, and structural steelwork is to comply with the requirements of AS4100 – Steel Structures Code.

The new driveway has been designed to comply with Pittwater Council's 21DCP Control B6.1, where the front of the garage is within 3.5 metres of the front property boundary (896mm). The access driveway crosses over "public land" and is proposed to be 4500mm in this part. The code stipulates that the driveway width can be as wide as the garage (which is 6000mm), so the driveway crossing complies in this regard. The ramp over angles and gradient of the new driveway also comply with the requirements of the standards.

It is recommended that engineers from this office make periodic inspections of the structural elements associated with this project to ensure compliance with the design intent. The concrete piers must be socketed into sandstone bedrock, and engineers from this office as well as the geotechnical engineer are to certify that the bearing under the piers is structurally sound and acceptable.

This office carries professional indemnity insurance with Lloyd Insurances, and is current to June, 2010. If council has any questions, or requires any additional information, please do not hesitate to contact me.

Yours faithfully


Angelo D'Ambrosio B.E.(Hons) MIEAust NPER3 (Structural)

D'AMBROSIO CONSULTING P/L

#### GEOTECHNICAL RISK MANAGEMENT POLICY FOR PITTWATER FORM NO. 2 – To be submitted with detailed design for construction certificate

	Development Application for ROGER JONES  Name of Applicant	
	Address of site 137 RIVERVIEW ROAD, CLAREVILLE	
Declarat	tion made by Structural or Civil Engineer in relation to the incorporation of the Geotechnical issues into the project des	ign
THE PROPERTY OF THE PROPERTY O	TNGETO DAMBRASIO on behalf of D'AMBRASIO CONSULTING PL ( (insert name) (trading or company name)	
	he 29 <sup>TR</sup> JULY, 2009	U
certify the above on at least \$	(date)  (date)	policy of
Geotech	hnical Report Details :	
	Report Title: RISK ANALYSIS & RISK MANAGEMENT FOR PROPOSED HOUSE AT 137 RIVERVIEW ROAD, CLAREVILLE	
	Report Date: 2 <sup>NO</sup> OCTOBER, 2003	
	Author: JACK HODGSON  Charleted Professional Engineer  Membership No. 29603	
	12 Aug. The Instrument of Engineers, Australia	
	Structural Documents list:	
	54443-6-01,6-02,6-03, \$ 7-01	
certification	aware that Pittwater Council relies on the processes covered by the Geotechnical Risk Management Policy, including this ion as the basis for ensuring that the geotechnical risk management aspects of the proposed development have been adequated to achieve an "Acceptable Risk Management" level for the life of the structure taken as at least 100 years unless otherwise	tely
and justif		DiGreea
_A	NGERO DAMBROSIO Tryelo DALLI (signature)	
	(name) (signature)	
Declarati	tion made by Geotechnical Engineer or Engineering Geologist in relation to Structural Drawings	
viewed the Geotechnologies I am away the basis achieve a	ed and/or technically verified the abovementioned Geotechnical Report as per Form 1 dated 2 <sup>NO</sup> OCTOBER,2003 and now cer the above listed structural documents prepared for the same development. I am satisfied that the recommendations given in to nical Report have been appropriate taken into account by the structural engineer in the preparation of these structural docume are that Pitwater Council relies on the processes covered by the Geotechnical Risk Management Policy, including this certifical for ensuring that the geotechnical risk management aspects of the proposed development have been adequately addressed an "Acceptable Risk Management" level for the life of the structure taken as at least 100 years unless otherwise stated and just and that reasonable and practical measures have been identified to remove foreseeable risk.	he ents. ation as to
	นับ กุ	
	Signature //odg/son	* * * * * * * * * * * * * * * * * * *
	Name JHODGSON (	
	Chartered Professional Status MEngSc FIEAust	
	Membership No. 149 788	
	Company Jack Hodgson Consultants Pty Ltd	





Section 139 – Roads Act 1993  1 July 2009 - 30 June 2010	WED 2009	
PLEASE PRINT Applicant: RH & SJ JONES BY:		
	Postcode: 2107	
Phone (W): 9918 9437 (M): 9918 943 ~		
Property Address: 137 RIVERVIEW RD AWALON	ni ni	
Subject to the payment of the appropriate fee, the Applicant is hereby permitted to construct the associated work) as detailed below, in strict accordance with the <b>CONDITIONS</b> overleaf.	he driveway (and/or	
I/We the undersigned agree to abide by the said conditions.		
Applicant's Signature: Date:	22.7.09	
SCANI	WED -	
FEES (includes GST)		
Consent for access driveway construction only (includes 2 site inspections) per allotment for RESIDENTIAL SINGLE/ DUAL OCCUPANCY.	\$155.00	
Consent for access driveway construction only (includes 2 site inspections) per allotment for RESIDENTIAL SINGLE/ DUAL OCCUPANCY which includes any of: major retaining structures, stairs or special landscape treatment.	\$385.00	
Consent for access driveway construction only (includes 2 site inspections) per allotment for OTHER THAN RESIDENTIAL SINGLE/DUAL OCCUPANCY.  \$180.00		
Consent for access driveway construction only (includes 2 site inspections) per allotment for OTHER THAN RESIDENTIAL SINGLE/DUAL OCCUPANCY which includes any of:  **state="1">\$510.00  **retaining structures, stairs or special landscape treatment.**		
Fee per additional site inspection as required	\$140.00	
.,		
Office Use Only:		
Approved:		
Not approved:  Comment:		
CODE: ESTR 1.7.09 - 30.6.10 Late Fee: \$650 when work commenced prior to issue of Consent For PAID: \$155 RECEIPT NO: 26232 ISSUED BY:		

#### Pittwater Council

#### OFFICIAL RECEIPT

22/07/2009 Receipt No: 262252

TO RH & SJ JONES

137 RIVERVIEW ROAD AVALON 2107

Applic. Reference Amount

GL Recei ESTR-Eng Strt \$155.00

1 X ROAD RESERVE APP

Total:	\$155.00
Amounts	Tendered
Cash	\$0.00
Cheque	\$155.00
Db/Cr Card	\$0.00
Money Order	\$0.00
Agency Rec	\$0.00
Total	\$155.00
Rounding	\$0.00
Change	\$0.00
Nett	\$155.00

Printed 22/07/2009 2:22:43 PM Cashier: ASherry



Suellen Jones 137 Riverview Rd AVALON NSW 2107 HOME BUILDING ACT 1989

OWNER BUILDER PERMIT

Permit: 367455P Receipt: 1-324358528 Issued: 5/8/2009 Amount: \$148.00\*

#### **BUILDING SITE**

137 Riverview Rd, AVALON, NSW 2107 AUSTRALIA

#### AUTHORISED BUILDING WORK

Construction of garage. 38.5 sq-m steel frame.

**Authority No** 

DA-N0071/09

Council Area

PITTWATER (S) COUNCIL

Should the property be sold within 6 years of completion of the work it will be necessary to obtain home warranty building insurance from approved insurers if the value of the work was greater than \$12,000. A certificate of insurance must be attached to any contract of sale.

You should obtain professional advice from general insurers regarding public liability and property damage cover, etc.

Note: This permit is only valid when an official receipt has been imprinted. If payment is made by cheque, the permit is conditional on the cheque being met on presentation. \*GST amount included in total fee: \$0.00

Issuing officer

Awnitter

\*\*\*\*\*\* END OF PERMIT \*\*\*\*\*\*

# Statutory Matters – Prior to issue of Construction Certificate – to be undertaken by tm-a certifier

Annexure 1 - mandatory inspection (cl143C EP&A Regs 2000)

certificate number:


premises address:


137 Riverview Road, Clareville (Garage)

C-09-024

development consent number:

Mandatory inspection as required by cl 143C EP&A Regs2000	2000	
Inspection undertaken by: Tom Donohoe	Accreditation number: BPB0096	Date: 27/7/09
issue		(office use only)  when / how issue rectified
Do plans and specification provided accompanying applica building the subject of the inspection (c1143C EP&A Regs 2000)	Do plans and specification provided accompanying application adequately and accurately depict the condition of the existing building the subject of the inspection (c143C EP&A Regs 2000)	Yes
Has the building work authorised by the relevant development consent commenced on the site (cl143C EP& A Regs 2000)	ment consent commenced on the site	No





All work to comply with the requirements of the Building Code of Australia and relevant Australian Standards Verify all dimensions on site and notify Architect of any discrepancies prior to proceeding with construction.

ORIG. issue

ISSUED FOR DEVELOPMENT APPLICATION

amendment

AMENDED TO COMPLY COUNCIL LETTER 28.04.09

13.03.09 04.05.09 14.05.09

14.07.09 date

14.07.09

ISSUED FOR CONSTRUCTION CERTIFICATE

ISSUED TO PITTWATER COUNCIL

CONSTRUCTION CERTIFICATE

Do not scale drawings.

WARWICK WERNER ARCHITECT PTY LTD Warwick Werner Architect Pty Ltd is the owner of the copyright subsisting in these drawings, plans, designs and specifications. They must not be used, reproduced or copied, in whole or in part, nor may the information, ideas and concepts therein contained be disclosed to any person without the prior written consent of that company.

WARWICK WERNER ARCHITECT CHARTERED ARCHITECTS • LANDSCAPE ARCHITECTS

4 Wanawong Road
Avalon Beach NSW 2107
T (61 2) 9918 5455
F (61 2) 9918 5462
wernerdesign@avalonbeach.net.au
Wanwick Werner Architect Pty. Ltd
ABN 43 077 722 779
NSW Architect Reg. No. 3507


project PROPOSED NEW GARAGE
137 RIVERVIEW RD CLAREVILLE


or R. & S. JONES

drawing drawing no. site plan WD-26

may 2009 \*\* project no scale 1 : 200 @ A3 02.09.01

date drawn





6000

4500

750

750

- W02 W01 92mm steel stud framing lined externally with Custom Orb colorbond steel sheeting laid horizontally and internally with 13mm plasterboard Fully sark walls and provide R2 insulation Custom Orb colour: Bushland
- Aluminium framed window with silicone jointed glass clear glazed Aluminium framing powdercoat finish Colour: Dulux Woodland

W03

Aluminium framed window
Clear glazed
Aluminium framing powdercoat finish
Colour: Dulux Woodland

W04

WARWICK WERNER ARCHITECT PTY LTD

ORIG.

amendment
ISSUED FOR DEVELOPMENT APPLICATION

AMENDED TO COMPLY COUNCIL LETTER 28.04.09

04.05.09

13.03.09

14.07.09 date

CONSTRUCTION CERTIFICATE

Do not scale drawings.

All work to comply with the requirements of the Building Code of Australia and relevant Australian Standards Verify all dimensions on site and notify Architect of any discrepancies prior to proceeding with construction.

Warwick Werner Architect Pty Ltd is the owner of the copyright subsisting in these drawings, plans, designs and specifications. They must not be used, reproduced or copied, in whole or in part, nor may the information, ideas and concepts therein contained be disclosed to any person without the prior written consent of that company.

COORDINATED WITH STRUCT. ENGINEERS DRAWINGS ISSUED FOR CONSTRUCTION CERTIFICATE

14.07.09 14.05.09 14.05.09 11.05.09

LANDSCAPING NOTES ADDED ISSUED TO PITTWATER COUNCIL ISSUED TO STRUCTURAL ENGINEER

# CONSTRUCTION NOTES

1000mm high 92mm stell stud framed lined both sides with 13mm plasterboard

## WO4

- W05 Aluminium framing powdercoat finish Colour: Dulux Woodland Aluminium framed window Clear glazed Aluminium framing powder
- 2400 high B&D "Design-a-door" garage door with clear glazed polycarbonate panels Colour: Dulux Bushland Aluminium framed glazed door Clear glazed Aluminium framing powdercoat finish Colour: Dulux Woodland

D01

R02 RO1 Custom Orb colorbond steel sheeting fully sarked and with R3 insulation Steel roof beams and timber rafters to structural engineers detail Lined internally with 6mm fibre cement sheet Custom Orb colour: Woodland Colorbond steel sheet fascia with 6mm fibre cement eaves lining Custom Orb colour: Woodland

# LANDSCAPING NOTES

tom miskovich & associates

5947 TO BOUNDARY

This is the document referred to

in certificate: 10-09

024-1 909

Dated:

NORTH

Screen planting to the area shaded to be selected so that after 3 years wi will in conjnction with the canopy planting, screen 50% of the built form when viewed from the street

The screen planting is to be maintained for the life of the development and replaced if any part should die, be destroyed or removed Plant selection to incorporate locally native species

Provide three(3) locally native canopy trees selected from Pittwater Council's schedule of plants for planting on shale slopes. Maintain trees for the life of the development or their safe natural life All natural landscape features, including rock out-crops, natural vegetation, soil and watercourses are to remain undisturbed except where affected by the works as approved by Council

Provide tree guards around all trees within 5 metres of the building works. Any excavation within the drip line of existing trees is to be carried out by hand. If tree roots are present a pier and beam method of footi construction is to be used to span the lateral roots Any vegetation planted outside the landscape zones indicated on the plan is to be consistent with:

\* species listed in the Ecological Sustainability or Bushland Management Plans

\* species from the Endangered Ecological Community

\* locally native species growing on site or listed in Pittwater Council's Native Plants for your garden

During excavation topsoil to be used in later landscape works is to be stockpiled on site and stabilised. Locate stockpiles outside drip lines of existing trees


### CHARTERED ARCHITECTS WARWICK WERNER • LANDSCAPE ARCHITECTS ARCHITEC


4 Wanawong Road
Avalon Beach NSW 2107
T (61 2) 9918 5455
F (61 2) 9918 5462
wernerdesign@avalonbeach.net.au
Wanwick Werner Architect Pty. Ltd
ABN 43 077 722 779
NSW Architect Reg. No. 3507

## project 37 PROPOSED NEW GARAGE RIVERVIEW RD CLAREVILLE FOR R. & S. JONES

drawn **WD-2** \* uly 2009 scale issue project no 1:100 @ A3 02.09.01

date drawing drawing no. floor plans





west elevation

W01

EXISTING

FO FG

STEEL BEAM TO -

RL 38.680

4

2400

引目

P

Contract of the contract of th

STEEL BEAM TO

RL 41.080

RL 41.880

HALF ROUND COLOR-BOND FAVES GUTTER

SITE BOUNDARY

STRIP AT EDGE OF BITUMEN
2400

W03

R01 R02

(W01)

W03 W01

2680

1000

RETAINING WALL OF EXISTING CARPORT

1000

RL 35.000 RL 36.000

EXISTING CARPORT SLAB

RL 36.180

STEEL BEAM TO

2680

8330

STEEL COLUMN TO
ENGRS DETAIL
10000 LITRE RAINWATER
STORAGE TANK

BASE

OF EXISTING WALL

1

RL 33.550



WARWICK WERNER ARCHITECT PTY LTD

ORIG.

amendment

CONSTRUCTION CERTIFICATE

14.07.09 date

Do not scale drawings.

All work to comply with the requirements of the Building Code of Australia and relevant Australian Standards Verify all dimensions on site and notify Architect of any discrepancies prior to proceeding with construction.

Warwick Werner Architect Pty Ltd is the owner of the copyright subsisting in these drawings, plans, designs and specifications. They must not be used, reproduced or copied, in whole or in part, nor may the information, ideas and concepts therein contained be disclosed to any person without the prior written consent of that company.

COORDINATED WITH STRUCT, ENGINEERS DRAWINGS

14.05.09 14.07.09 11.05.09 04.05.09 13.03.09

SSUED FOR CONSTRUCTION CERTIFICATE

ISSUED TO PITTWATER COUNCIL ISSUED TO STRUCTURAL ENGINEER AMENDED TO COMPLY COUNCIL LETTER 28.04.09 ISSUED FOR DEVELOPMENT APPLICATION

4 Wanawong Road
Avalon Beach NSW 2107
T (61 2) 9918 5455
F (61 2) 9918 5462
wernerdesign@avalonbeach.net.au
Warwick Werner Architect Pty. Ltd
ABN 43 077 722 779
NSW Architect Reg. No. 3507

drawn date

\*

project no

RO2 Colorbond steel sheet fascia with 6mm fibre cement eaves lining Custom Orb colour: Woodland

W05 001 W04 W03 W02 2400 high B&D "Design-a-door" garage door with clear glazed polycarbonate panels Colour: Dulux Bushland Custom Orb colorbond steel sheeting fully sarked and with R3 insulation Steel roof beams and timber rafters to structural engineers detail Lined internally with 6mm fibre cement sheet Custom Orb colour. Woodland 92mm steel stud framing lined externally with Custom Orb colorbond steel sheeting laid horizontally and internally with 13mm plasterboard Fully sark walls and provide R2 insulation Custom Orb colour: Bushland Aluminium framing powdercoat finish Colour: Dulux Woodland Aluminium framed window with silicone jointed glass - clear glazed Aluminium framing powdercoat finish Colour: Dulux Woodland Aluminium framed glazed door Clear glazed Aluminium framed window Clear glazed Aluminium framing powdercoat finish Colour: Dulux Woodland 1000mm high 92mm stell stud framed lined both sides with 13mm plasterboard

3

tom miskovich

This is the document referred to

0

7-8-09 -09-0

RO1

Dated:

PROPOSED NEW GARAGE
137 RIVERVIEW RD CLAREVILLE
for R. & S. JONES

drawing drawing no east & west elevations section A-A
WD-29 Section B july 2009 scale 1 : 100 @ A3 02.09.01

## 1.1 GENERAL

Owner:

Supply: Builder: Means the same as "principal" or "proprietor" Means the same as "contractor". Means "supply only" - do not install.

Required:

Provide:

"supply and install" Means identifiable by naming the manufacturer, supplier, installer, trade name, brand name, the local council or statutory authorities. Means required by the contract documents or by

where other editions or amendments are required which are current one month before the date of the contract except Use referenced Australian or other standards (including amendments) catalogue or reference number.

Select, store, handle and install proprietary products or systems in accordance with the current published recommendations of the

Manufacturers' or suppliers' recommendations

buildings in bushfire prone areas). **Bushfire protection** provide protection to AS 3959-1999 (Construction of

## 1.2 AUTHORITIES AND ESTABLISHMENT Prior applications and approvals

Existing services

Attend to existing services as follows:

provide permanent support for the existing service trench, or will lose support when the trench is excavated, If the service is to be continued, repair, divert or relocate as required. If such a service crosses the line of a required the service is to be abandoned, cut and seal or

Temporary services and works disconnect, and make safe.

Provide temporary toilet accommodation. Connect to the sewer main Use of existing services if required by the Local Authority.

Existing services may be used as temporary services for the

Provide a signboard displaying the owners name, the lot number and the builder's name, address and licence number.

# 1.3 EXECUTION AND COMPLETION

Preserve and maintain the owners survey marks in their true

Rectification: If the proprietor's survey marks are disturbed obliterated, immediately give notice and rectify the disturbance Hours of work 9 9

Remove temporary work services and construction plant within 10 Removal of temporary work, services and plant in accordance with the current requirements of Pittwater Council

use of temporary work and services and restore existing facilities working days after practical completion.

Rectification: Clean and repair damage caused by the installation or used during construction to original condition.

throughout. Remove rubbish and surplus material from the site and clean the work

manufacturers' warranties. Name the owner as warrantee and give the owner copies 9

Give the owner manufacturers' instruction manuals Instruction manuals

Surveyor's certificate Ensure moving parts operate safely and smoothly.

Give the owner a plan which shows the location Services layout

boundary fences, has been correctly located.

Give the owner a certificate which confirms that the work, including

FOR CON 14 JULY 2009

CONSTRUCTION CERTIFICATE

## Authorities' approvals

Give the owner evidence of approval of the local council and statutory authorities whose requirements apply to the work.

keys for each lock keyed to differ. Give the owner two keys for each set of locks keyed alike and two

# 1.4 TERMITE PROTECTION

Standard: buildings). To AS 3660.1-2000 (Termite management - New

**Graded stone barriers** Form a complete and continuous barrier under the whole extended building footprint and extending 300mm beyon perimeter of slabs on ground comprising the following: whole of beyond

Proprietary item: Granitgard Graded stone termite barrier system installed around building 400mm clearance in accordance with manufacturer's instructions. perimeter, in all footings and across subfloor areas with less than

Application: by Granitgard Pty Ltd licensed installer

Termite barrier notice

Provide a durable notice permanently fixed in a prominent location to BCA Volume 2 clause 3.1.3.2 (b) and AS 3660.1 - 2000 (Termite management - New buildings) Appendix A.

# 1.5 TIMBER GENERALLY

26 MAY 2009

likely, make allowance If unseasoned timber is provided, or variations in moisture content are for shrinkage, swelling and differential

General: Provide timbers with natural durability appropriate conditions of use, or preservative-treated timbers of equ equivalent to the

preservative treatment -Sawn and round timber) Table F2 Natural durability classification: To AS 1604.1-2000 (Specification for

Class 1: Timbers in contact with the ground.

Class 2: Timbers above ground, not in continuous contact exposed to the weather. with moisture, well ventilated, protected from moisture but

Class 3: Timbers above ground, not in continuous contact protected with a finish, and well maintained

Class 4: Timbers fully protected from moisture, indoors, above ground, and well ventilated.

treatment - Plywood). End use hazard classification: To Table A1 To AS/NZS 1604.3-2002 (Specification for preservative

(Specification for preservative treatment - Reconstituted wood-based products). wood based products: To AS/NZS 1604.2-2002

treatment - Sawn and round timber).

End use hazard classification: Sawn and round: To AS 1604.1-2000 (Specification for preservative End use hazard classification: To Table A1.

(Specification for preservative treatment - Sawn and round To AS 1604.1-2000

## 2 SITE PREPARATION

2.1 GENERAL Standard

footings - Construction) Groundworks for slabs and footings: To AS 2870-1996 (Residential slabs and footings - Construction). Ground slabs and footings: To AS 2870-1996 (Residential slabs and

with the Structural Engineer's drawings and the Specification notes contained therein. Where there is a variance with this Specification All demolition and excavation work is to be executed in accordance Structural Engineer's drawings

Interpretation

Rock: Monolithic material with volume greater than 0.5 m3 which cannot be removed until broken up by mechanical means such as the Structural Engineer's Specification shall take precedence.

rippers or percussion tools.

becomes, soft, wet or unstable. Bad ground: Ground unsuitable for the work, including fill I subsidence, ground containing cavities, faults or fissures, contaminated by harmful substances and ground which ground h is, or liable to

becomes, soft, wet or unistaute.

Line of influence: A line extending downward and outward from the

the pavement or slab is constructed.

2.6 EXCAVATION

Surplus material

Take possession of surplus material and remove it from the site.

contamination by other excavated material, weeds and building Stockpile site topsoil required for re-use. Protect stockpiles from

mmediate notice

If rock or bad ground is encountered, advise the owner immediately.

2.2 DEMOLITION

Demolition: To AS 2601-2001 (The demolition of structures)

Prior to commencement of the works make a detailed record of conditions existing within adjoining buildings, especially structural damage or other defacement. Submit copy of report including drawings, written descriptions and photographs to Superintendent

Demolition items

disconnection and / or relocation.

2.7 SURFACE PREPARATION

Grade the ground surface externally and under suspended floors to

drain ground or surface water away from buildings without ponding

with fill to the correct depth, level and bearing value.

If excavation exceeds the required depth, or deteriorates, reinstate

Reinstatement

appropriate courses if supporting masonry.

Provide even plane bearing surfaces for load-bearing elements including footings. Step for level changes. Make the steps to the

After excavation, confirm that the bearing capacity is adequate.

services, paving, and landscaping. Allow

for

compaction

Excavate to give the levels and profiles required for construction, site

Bearing surfaces

Foundations settlement.

Demolished materials

Protection of existing items Except for materials to be salvaged and retained by the owner or re-used, take possession of demolished materials and remove them from the site. Do not burn or bury demolished materials on the site.

# 2.3 TREES TO BE RETAINED

Remove the identification on completion. suitable

If excavating near trees required to be retained, use hand methods to locate, expose and cleanly

Backfill material: Excavated spoil or well graded inorganic material with maximum particle size of 75 mm.

service. Place backfill in layers. Compact each layer to a density General: Backfill service trenches as soon as possible after laying the

sufficient to minimise settlement.

Keep trench widths to the minimum consistent with the laying and bedding of the relevant service and construction of manholes and pits.

Generally, make trenches straight between manholes, inspection points and junctions, with vertical sides and uniform grades.

Trench widths

## Erosion control

and sedimentation of the site,

Keep the site free of water and prevent water flow over new work.

3.1 GENERAL

Cross reference

3 CONCRETE CONSTRUCTION

(Residential slabs and footings - Construction): Impervious In reactive clay sites classified M, H or E to AS 2870-1996 Under paved areas: Coarse sand, controlled low strength Next to services: Do not place any particles greater in size

material or fine crushed rock.

than 25 mm within 150 mm of services.

paving or

scrap, grass, vegetable matter and organic debris, scrub, trees, timber, stumps, boulders and rubble. Remove grass to a depth just Remove everything on or above the site surface, including rubbish, sufficient to include the root zone.

Wildssociates

contains substantial organic matter over the areas to be occupied by construction and paving.

Maximum depth: 100 mm.

Topsoil stockpiles

foundation material having influence on the stability or support of the footings, slab or pavement.

Subgrade: The trimmed or prepared portion of the formation on which

Do not use explosives

As indicated on the Drawings.

Inspect the site and determine and confirm the full extent of the existing site, in-ground, building and building services requiring

Take all necessary care to protect existing water and gas meters.

Restore and make good to match existing to the approval of the Superintendent damage and defacement caused to adjoining buildings by the demolition works.

2.8 SERVICE TRENCHES

Excavation

adjust the moisture content of the fill before compaction.

If necessary to achieve the required density or moisture content

Place fill in layers and compact each layer to achieve the required

achieve the required density.

Placing fill

Before placing fill, ground slabs or load-bearing elements, remove loose material, debris and organic matter and compact the ground to

Moisture content

Mark trees which are required to be retained using suitable non-injurious, easily visible and removable means of identification. Mark trees which

remove topsoil from the area within the dripline of the trees and keep this area free of construction material and debris. Protect from damage trees which are required to be retained. excavation . Do not

remove the roots on the line of excavation.

# 2.4 ENVIRONMENTAL PROTECTION

Avoid erosion, contamination, Dewatering surrounding areas, and drainage systems.

2.5 SITE CLEARING

landscaping imit clearing to areas to be occupied by construction,

Grub out or grind stumps and roots over 75 mm diameter to a minimum depth of 500 mm below subgrade under construction, and

Engineer's drawings and the Specification notes contained therein. Where there is a variance with this Specification the Structural

All concrete work is to be executed in accordance with the Structural

Engineer's Specification shall take precedence.

footings - Construction).
Structural Engineer's drawings

Ground slabs and footings: To AS 2870-1996 (Residential slabs and

Concrete structures generally: To AS

3600-2000 (Concrete

Refer to the General Requirements section for termite protection.

General: Remove the topsoil layer of the natural ground 300 mm below the finished surface in unpaved areas. Removal of topsoil

oertificate:

RIVERVIEW RD. CLAREVILLE, N.S.W

No:

2-09-024-1

# 3.2 GROUND SLAB VAPOUR BARRIER

General: Provide a proprietary vapour barrier which consists of high impact resistant polyethylene film minimum 0.2 mm thick which has been pigmented and branded by the manufacturer

not inferior to double sided butyl adhesive tape. Similarly seal around unavoidable penetrations such as service pipes. Take the underlay up vertical faces as far as the damp proof course where applicable, and before pouring concrete away from the direction of concrete pour. Seal laps with adhesive tape vertical or inclined surfaces. Patch or seal any punctures or tears fix at the top by tape sealing. Arrange to have vertical laps only on Lay over the base. Lap joints not less than 200 mm. Face the laps

## 3.3 REINFORCEMENT

Splice as follows: Minimum lap

Trench mesh: 500 mm. Mesh generally: 225 mm.

intersecting reinforcement. Bars: Greater of either 500 mm or 25 x bar diameter Strip footing intersections and corners: For full

Protected by membrane on ground: 30 mm. Inprotected by membrane on ground or external surfaces: 40 mm.

Aggressive soil or salty environment: 65 mm

Internal surfaces: 20 mm.

## 3.4 CONCRETE

Standard: To AS 1379-1997 (Specification and supply of concrete). Maximum slump: 100 mm. mixed supply

compaction process. each succeeding layer is Depth: If concrete is deeper than 350 mm, place it in layers so that Concrete placing blended into the preceding one by the

Compaction Slabs and pavements: Place concrete uniformly over the width of the slab so that the face is generally vertical and normal to the direction

may cause segregation. Vibrate concrete to remove entrapped air, but avoid over-vibration that

Method: Cure concrete by excessive hot, cold and/or windy conditions. Protect concrete from premature drying and

using a proprietary curing compound; or

 Exposed footings, beams and slabs: 7 days keeping it covered and moist for the following periods: In-ground footings: 2 days.

Remove timber formwork. Formwork removal

concrete for the following periods: Leave formwork for suspended structures in place after pouring Stripping times

Bottom surfaces: 7 days with shoring and backprops left in position for 21 days. Vertical surfaces: 2 days.

## 3.5 JOINTS

Construction joints

Dampen the surface before placing the concrete. surface, remove loose or soft material, free water and foreign matter Joint preparation: Roughen and clean the hardened concrete joint

pre-lubricated slip joints. concrete slabs are supported on masonry, provide proprietary

# 4 TIMBER AND STEEL CONSTRUCTION

## 4.1 GENERAL

Cross references

Refer to the following Sections:

General requirements, for termite protection and timber

Brick and block construction, for clearance for timber frame Concrete construction, for concrete bearer supports.

FOR CONSTRUCTION CERTIFICATE

Painting, for priming of steel and timber before fixing, and repair of zinc-coated steel after cutting and welding. Waterproofing, for waterproofing of wet areas.

timber-framed framing and flooring: To As 100-2-100-100 or construction - Simplified - Non-cyclonic) or To AS 1684.4-1999 (Residential

1720.1-1997 (Timber structures - Design methods).
Structural steelwork: To AS 4100-1998 (Steel structures) AS 3623-1993 (Domestic metal framing).
Preparation of metal surfaces: To AS 1627- Various (Metal finishing Cold-formed steel framing: Provide a proprietary system designed to

contained therein. Where there is a variance with this Specification the Structural Engineer's Specification shall take precedence. with the Structural Engineer's drawings and the Specification notes Structural Engineer's drawings All structural timber and steel work is to be executed in accordance

Preparation and pretreatment of surfaces).

# **4.2 MATERIALS AND COMPONENTS**

# Cold-formed steel framing

zinc-coated or aluminium/zinc-coated).
Corrosion protection: To BCA Volume 2 clause 3.4.2.2.
Self-drilling screws coated steel to AS 1397-2001 (Steel sheet and strip - Hot-dipped Cold-form sections from zinc-coated steel or aluminium/zinc alloy

Standard: To AS 3566.1-2002 (Self-drilling screws for the building and construction industries -General requirements and mechanical

for the building and construction industries -Corrosion resistance requirements), Table 1. Corrosion resistance: Class 2 to AS 3566.2-2002 (Self-drilling screws

# Flashings and damp-proof courses

Standard: To AS/NZS 2904-1995 (Damp-proof courses and flashings)

Metal washers: Provide washers to the heads and nuts of all bolts and

Steel straps: Zinc-coated steel to AS 1397-2001 (Steel sheet and strip - Hot-dipped zinc-coated or aluminium/zinc-coated), minimum size 25 x 1 mm or 30 x 0.8 mm.

## Galvanizing

Galvanize mild steel components (including fasteners) to AS 1214-1983 (Hot-dip galvanized coatings on threaded fasteners (ISO metric coarse thread series)) or AS/NZS 4680-1999 (Hot-dip galvanized (zinc) coatings on fabricated ferrous articles), as

embedded in masonry; or in contact with chemically treated timber

# 4.3 CONSTRUCTION GENERALLY

of steel structures).

Provide grommets to isolate piping and wiring from cold-formed steel

Remove swarf and other debris from cold-formed immediately after it is deposited steel framing

Greasing: Before placing bolts in contact with CCA-treated timber, coat the shank of the bolt in grease or a bituminous coating. Steel framing: Do not fix CCA-treated timber in contact with cold-formed steel framing. Priming steel

Before fixing, prime steel which is not galvanized or zinc-coated.

## 4.4 FLOORS

Standard: To AS 1684.4-1999 (Residential timber-framed construction

## 4.5 WALL FRAMING

Use proprietary framing system comprising cold-formed steel sections

Design: To AS 3623

exposed to weather;

Standard: To AS/NZS 1554.1-1995 (Structural steel welding - Welding

CCA (copper chrome arsenic)-treated timber

Simplified - Non-cyclonic).

Proprietary system

for wall construction

## Cold-formed steel sections MATERIAL AND COMPONENTS

Sections cold-formed from zinc-coated or aluminium/zinc-coated steel: To AS 1397/Z200 or AZ150 (minimum), as appropriate.

To AS 1163. Galvanized to AS 1650

## Wall studs

To AS 3566, corrosion resistance class

CONSTRUCTION

Provide studs in single lengths without splices. Place a stud under or not more than 40 mm from each structural load point from roof or ceiling (except for openings). Provide multiple studs at points of Nominal frame dimension

Heads to openings

(stud width): 92mm and 150mm where shown on the drawings. Maximum stud spacing: 600 mm

Use lintels consisting of either a stiffened top plate or a truffom frame members, depending on load and span. uss built up

# Adequately brace the frame to resist wind loads, by diagonal nogging or by tensioned straps. Splicing

Additional support Splice plates at ends to maintain continuity and alignmen

Provide additional support in the form of noggings, trimmers and studs

Maximum spacing of noggings: 1350 mm centres. for fixing lining, cladding, hardware, accessories, fixtures and fittings

4.6 ROOF AND CEILING FRAMING

galvanized fastenings Fixing: Fix timber wall plates to masonry, with either straps or bolts. Steel zinc-coated straps: In cavities. Build bottom end 75 mm into brickwork, 1200 mm below plate. Bend top end over plate and fix with

Coating class: Z275

Size: 25 x 1 mm or 30 x 0.8 mm.

Bolts: 10 mm diameter hot dip galvanized steel, embedded at least Nailing strips top bond beam of load-bearing hollow block external walling. 150 mm into the wall structure of solid masonry external walling or the

50 mm thick nailing strips bolted to the flange of the steel Where timber joists, rafters or purlins bear on steel members, provide 450 mm maximum centres. member at

Strutted framing

of rafters and ceiling joists supported at intermediated points by a system of underpurlins strutted off walls or strutting beams and braced by collar ties, and ceiling hanging beams. General: Construct traditional timber pitched roof framing ng consisting points by a

Beam framing

General: Construct framing for flat or pitched roofs where follows the roof line, consisting of rafters or purlins acting to support both ceiling and roof covering. the ceiling as beams

mm maximum intervals between supports. provide solid blocking between them at the support points Blocking: Where the depth of rafters or purlins is at least and at 1.8 4 x width,

triple-nailed to each rafter. Additional support

Ridge straps: Butt ends of rafters together at ridge, and pair together with 900 mm long steel strap passing over

over

strap each er the ridge,

or lining. Provide a frame member behind every joint in fibre cement sheeting

# Anti-ponding boards

underlays - Installation requirements) Standard: To AS/NZS 4200.2-1994 (Pliable building materials and

# 4.7 HANDRAILS AND BALUSTRADES

Standards Balustrades and handrails to comply with Building Code of Australia

Loading forces: To AS 1170.1

48 x 8 galvanised mild steel plate uprights at centres ad sh drawings with stainless steel wire intermediate rails space Balustrades Horizontal wire balustrading: To BCA Table 3.9.2.1 aced Bys Wciates

apart at maximum 125mm centres. Fix wires to uprights at ends of runs with shackles and turnbuckles. Splay and profile top of upright as detailed to accept 100mm long x 50mm wide galvanised mild steel plate handrail connector welded to upright.

sections onto connectors with two countersunk screws at each end on rebated to fit onto flat steel plate connectors at uprights. Fix handrail 100 x 50mm dia. round edged solid Tallowwood top rail in sections

Bolt bottom of baluster to steel beam top flanges to structural the underside of connectors.

engineer's detail. Finish

Painted galvanised steel uprights

Finished height

adjacent finished floor level or a minimum 865mm above stair nosings All balustrades and handrails to finish minimum 1000mm above

4.8 TIMBER AND STEEL STAIRS

where applicable.

Building Code of Australia Clause 3.9.1.

Balustrades and handrails are to comply with the requirements of Building Code of Australia Clause 3.9.2. Balustrade loading forces: AS 1170.1 General Stair configuration and construction comply with the requirements of

Provide timber treads: Timber type: Spotted Gum

Finished size:  $275 \times 70$ mm (min.) with 2mm pencil round edges and with bottom face rebated to accommodate steel tread fixing plate as detailed. Fix  $60(h) \times 25(t)$ mm solid timber upstand to back of tread to

Groove for riser tongue in closed riser stair. Set riser 19 mm back from project 15mm above top of tread.

Dress nosings to a pencil-round. Return nosings at cut strings.

adhesive slip resistant studs into predrilled holes spaced 50mm apart and centred 50mm from leading edge of tread. Provide non-slip finish comprising 25mm dia. Latham Asbramall

5 BRICK AND BLOCK CONSTRUCTION

## 5.1 GENERAL

Cross references
Refer to the following Sections:

General requirements, for termite protection.

Timber and steel construction, for structural steelwork.

Masonry generally: To AS 3700-2001 (Masonry structures).

Masonry units: To AS/NZS 4455-1997 (Masonry units and segmental

pavers).
Structural Engineer's drawings

All structural brick and block work is to be executed in accordance with the Structural Engineer's drawings and the Specification notes contained therein. Where there is a variance with this Specification the

Structural Engineer's Specification shall take precedence.

# 5.2 MATERIALS AND COMPONENTS

Steel components

Galvanizing: Galvanize mild steel components (including fasteners) to AS 1214-1983 (Hot-dip galvanized coatings on threaded fasteners (ISO metric coarse thread series)), or AS/NZS 4680-(Hot-dip galvanized (zinc) coatings on fabricated ferrous articles),

appropriate.

Durability requirements: To AS/NZS 2699.2 (Built-in components for masonry construction - Connectors and accessories)

Masonry units

To AS 4455

Load bearing: 400(l) x 200(h) x as shown on the

drawings(w)

Clay bricks durability

- Method 10: Determining resistance to salt attack) Appendix A (Salt Below damp-proof course: Use exposure category to AS/NZS 4456.10-1997 (Masonry units and segmental pavers - Method of test attack resistance categories)

Standard: To AS/NZS 2699.1 (Built-in components for masonry

SPECIFICATION FOR PROPOSED NEW GARAGE, 137 RIVERVIEW CLAREVILLE,

in certificate: -09-029-1

WARWICK WERNER ARCHITECT PTY LTD
ABN NSW ARCHITECTS REGISTRATION 3507
4 WANAWONG RD AVALON BEACH NSW 2106

1/ KETEKENCED DOCUMENTS	NIO	
AS 1214 1983	Hot-dip galvanized coatings on threaded	AS/NZS 1859.2 (Int) 2001 AS/NZS 1859.3 1996
AS 1231 2000	fasteners (ISO metric coarse thread series) Aluminium and aluminium alloys - Anodic	
AS 1288 1994 AS 1324	oxidation coatings Glass in buildings - Selection and installation Air filters for use in general ventilation and	AS 1900 1984
AS 1324.2 1996	airconditioning Methods of test	AS 2047 1999 AS 2049 1992
AS 1366	Rigid cellular plastics sheets for thermal insulation	2050 2159
AS 1366.4 1989 AS/NZS 1367 2000	Rigid cellular polystyrene - Extruded (RC/PS-E) Coaxial cable systems for the distribution of analogue television and sound signals in single	AS/NZS 2179 AS/NZS 2179 2(Int) 1998
1270	and multiple unit installations	AS 2185 1978
AS 1397 2001	Steel sheet and strip - Hot-dipped zinc-coated or aluminium/zinc-coated	AS/NZS 2311 2000 AS/NZS 2312 1994
AS 1417	Receiving antennas for radio and television in the frequency range 30 MHz to 1 Ghz	AS 2358 1990
AS 1417.1 1987	Construction and installation	AS/NZS 2455
AS 1417.2 1991 AS/NZS 1546	Performance	AS/NZS 2455.1 1995 AS 2461 1981
AS/NZS 1546.1 1998	Septic tanks	AS 2462 1981
AS/NZS 1546.2 2001 AS/NZS 1546.3 2001	Waterless composting toilets Aerated wastewater treatment units	AS/NZS 2588 1998 AS/NZS 2589
2000	On site domestic wastewater management	
AS/NZS 1554 AS/NZS 1554.1 2000	Velding of steel structures	AS/NZS 2589.1 1997
AS 1562	Design and installation of sheet roof and wall cladding	AS 2592 1983 AS 2601 2001
AS 1562.1 1992 AS/NZS 1562 3 1996	Metal Plastic	AS 2688 1984 AS 2689 1984
AS/NZS 1571 1995	Copper - Seamless tubes for airconditioning and refrigeration	AS/NZS 2699 AS/NZS 2699 1 2000
AS 1604 AS 1604 1 2000	Specification for preservative treatment	AS/NZS 2699 2000 AS/NZS 2728 1997
AS/NZS 1604.2 2002	Reconstituted wood-based products	
AS 1627 Various	Metal finishing - Preparation and pretreatment of	AS 2734 1984
AS 1668	The use of mechanical ventilation and	AS/NZS 2803
AS 1668.2 1991	air-conditioning in buildings  Mechanical ventilation for acceptable indoor-air	AS/NZS 2803.1 1994 AS/NZS 2803.2 1995
AS 1670	Fire detection, warning, control and intercom	AS/NZS 2804.1 1995
	systems - System design, installation, and commissioning	AS/NZS 2804.2 1996 AS 2870 1996
AS 1670.1 1995	Fire	
	Limes and limestones	AS/NZS 2908.2 2000
AS 1672.1 1997 AS 1677	Limes for building	AS 2913 2000 AS/NZS 2018 2001
AS 1677.2 1998	Safety requirements for fixed applications	
AS 1684 AS 1684 4 1000	Residential timber-framed construction	AS/NZS 2924
	Domestic oil-fired appliances - Installation	AS/NZS 2924.1 1998
	Timber structures	AS/NZS 3017 2001
AS 1720.1 1998 AS 1789 1984	Design methods  Electroplated coatings - Zinc on iron or steel	AS/NZS 3018 2001
SZN	Reconstituted wood-based panels -	AS/NZS 3086 1996
AS/NZS 1859.1 (Int) 2001	Particleboard	

<u>o</u> <u>o</u>			and	or-air	ent of	g and	wall	T iš	on in	ingle ed or	rmal S-E)	aded ) nodic on on
AS/NZS 3018 2001 AS/NZS 3086 1996	AS/NZS 2924 AS/NZS 2924.1 1998 AS/NZS 3017 2001	AS/NZS 2908 AS/NZS 2908.2 2000 AS 2913 2000 AS/NZS 2918 2001		2803.1 2803.2 2804		NZS ZN/SZN/SZN/SZN/SZN/SZN/SZN/SZN/SZN/SZN/S	AS/NZS 2589.1 1997 AS 2592 1983 AS 2601 2001 AS 2688 1984 AS 2689 1984	AS 2461 1981 AS 2462 1981 AS/NZS 2588 1998 AS/NZS 2589	AS 2358 1990 AS/NZS 2455 AS/NZS 2455.1 1995	AS/NZS 2179.2(Int) 1998 AS 2185 1978 AS/NZS 2269 1994 AS/NZS 2311 2000 AS/NZS 2312 1004	AS 2049 1992 AS 2050 1995 AS 2159 1995 AS/NZS 2179	AS/NZS 1859.2 (Int) 2001 AS/NZS 1859.3 1996 AS/NZS 1859.4 (Int) 2001 AS 1860 1998 AS 1884 1985 AS 1909 1984 AS 2047 1999
Electrical installations - Domestic installations Telecommunications installations - Integrated communications cabling systems for small office/home office premises	High pressure decorative laminates - Sheets made from thermosetting resins Classification and specifications Electrical installations - Testing and inspection guidelines	Cellulose-cement products Flat sheets Evaporative airconditioning equipment Domestic solid fuel burning appliances - Installation	Hinged Sliding Residential slabs and footings - Construction Damp-proof courses and flashings	Hinged Sliding Installation of security screen doors	uirements (ed) paving	Built in components for masonry construction Wall ties Connectors and accessories Prefinished/prepainted sheet metal products for interior/exterior building applications -	Gypsum plasterboard Gypsum plaster for building purposes The demolition of structures Timber doors Timber doorsets	Mineral wool thermal insulation - Loose fill Cellulosic fibre thermal insulation Gypsum plasterboard Gypsum linings in residential and light commercial construction - Application and finishing	exterior atmospheric corrosion Adhesives - For fixing ceramic tiles Textile floor coverings - Installation practice General	and tasteners PVC rainwater goods and accessories Fibrous plaster products Plywood - Structural Guide to the painting of buildings	Roof tiles Installation of roofing tiles Piling - Design and installation Specification for rainwater goods, accessories	Dry-processed fibreboard Decorative overlaid wood panels Wet-processed fibreboard Installation of particleboard flooring Floor coverings - Resilient sheet and tiles - Laying and maintenance practices Installation of timber doorsets Windows in buildings - Selection and installation

1256.3 1256.4 1256.4 1256.5 1386.1	AS 3947.2 1997 AS 3947.2 1997 AS 3958.1 1991 AS 3958.1 1991 AS 3958.2 1992 AS 3959 1999 AS 3972 1997 AS 3999 1992 AS 3999 1992 AS 4100 1998 AS/NZS 4200 AS/NZS 4200.1 1994	AS 3740 1994 AS 3742 1990 AS 3786 1993 AS/NZS 3823 AS/NZS 3823.1.1 1998 AS/NZS 3823.1.2 2001	AS 3566.1 2002 AS 3566.2 2002 AS 3600 2000 AS 3623 1993 AS 3660 AS 3660.1 2000 AS 3666.1 2002 AS 3700 2001 AS 3715 1989	AS/NZS 3500 AS/NZS 3500.1.2 1998 AS/NZS 3500.2.2 1996 AS/NZS 3500.3.2 1998 AS/NZS 3500.4.2 1997 AS/NZS 3500.4.2 1997 AS/NZS 3500.5 2000 AS 3566	AS/NZS 3100 1997 AS 3137 1992 AS 3439 AS 3439.1 1993 AS 3439.3 1995
Installation requirements Ductwork for air-handling systems in buildings Plastic roof and wall cladding materials Glass fibre reinforced polyester (GRP) Unplasticized polyvinyl chloride (uPVC) wall cladding boards Polycarbonate Domestic kitchen assemblies Kitchen units	Low voltage switchgear and controlgear Circuit-breakers Ceramic tiles Guide to the installation of ceramic tiles Guide to the selection of a ceramic tiling system Construction of buildings in bushfire prone areas Portland and blended cements Thermal insulation of dwellings - Bulk insulation - Installation requirements Steel structures Pliable building materials and underlays Materials	Waterproofing of wet areas within residential buildings Mineral wool thermal insulation - Batt and blanket Smoke alarms Performance of electrical appliances - Room airconditioners Testing and rating for performance Ducted airconditioners and air-to-air heat pumps - Testing and rating for performance	General requirements and mechanical properties Corrosion resistance requirements Concrete structures Domestic metal framing Termite management New buildings Air-handling and water systems of buildings - Microbial control Design, installation and commissioning Masonry structures Metal finishing - Thermoset powder coatings for	to be installed in places where unskilled persons have access for their use - Distribution National Plumbing and Drainage Water supply - Acceptable solutions Sanitary plumbing and sanitary drainage - Acceptable solutions Stormwater drainage - Acceptable solutions Hot water supply systems - Acceptable solutions Domestic installation Self-drilling screws for the building and construction industries	Approval and test specification - General requirements for electrical equipment Approval and test specification - Luminaires (lighting fittings)  Low-voltage switchgear and controlgear Type-tested and partially type-tested assemblies Particular requirements for low-voltage switchgear and controllear assemblies intended

CBPI IN 21A 1985 CBPI TN 21B 1985	
BCA 3.4.4.4	en units
BCA 3.4.2.2	carbonate estic kitchen assemblies
BCA 3.3.3.5	s fibre reinforced polyester (GRP) asticized polyvinyl chloride (uPVC) wall find boards
BCA 3.1.3.2(b)	liation requirements work for air-handling systems in buildings
AWRAP/A 202 1993	le building materials and underlays
APAS-2916 2001 ASTM C534 2001	mal insulation of dwellings - Bulk insulation allation requirements
APAS-0280/5 2001	e to the selection of a ceramic tiling system struction of buildings in bushfire prone areas
-0280/2 -0280/3	mic tiles e to the installation of ceramic tiles
-0260/4 -0280/1	uing and rating for performance voltage switchgear and controlgear int-breakers
APAS-0260/1 2001 APAS-0260/2 2001 APAS-0260/3 2001	ng and rating for performance ed airconditioners and air-to-air heat pumps
0205 20	ormance of electrical appliances - Room nditioners
APAS-0200/2 2001	nal insulation - Batt and
APAS-0200/1 2001	ings
APAS-0115 2001	- I hermo
APAS-0015/2 2001	. 5 5
APAS-0015/1 2001	bial control
AS/ACIF S008 2001 AS/ACIF S009 2001	nent
SAA MP52 2001	rete structures
SAA HB40.2 2001	eral requirements and mechanical properties usion resistance requirements
SAN 11040.1 2001	drilling screws for the building and
200 LD40 4 2004	water urainage - Acceptable solutions vater supply systems - Acceptable solutions
AS 5601 2002 SAA HB29 1998 SAA HB33 1992 SAA HB40	
AS/NZS 4600 1996 AS/NZS 4680 1999	hgear and controlgear assemblies intended installed in places where unskilled persons access for their use - Distribution
AS/NZS 4456.10 199 AS/NZS 4505 1998 AS 4508 1999	ng
AS 4440 1997 AS/NZS 4455 1997 AS/NZS 4456	oval and test specification - General rements for electrical equipment

and ents fo	AS 4440 1997 AS/NZS 4455 1997 AS/NZS 4456
nd test specification - Luminaires ngs) switchgear and controlgear and partially type-tested assemblies	AS/NZS 4456.10 1997 AS/NZS 4505 1998 AS 4508 1999
year and controlgear assemblies intended istalled in places where unskilled persons cross for their use. Distribution	AS/NZS 4600 1996 AS/NZS 4680 1999
al Plumbing and Drainage supply - Acceptable solutions y plumbing and sanitary drainage - able solutions	AS 5601 2002 SAA HB29 1998 SAA HB33 1992 SAA HB40
water drainage - Acceptable solutions ter supply systems - Acceptable solutions tic installation litting screws for the building and other industries.	SAA HB40.1 2001
la requirements and mechanical properties	SAA HB40.2 2001
te structures tic metal framing	SAA MP52 2001
management sildings	AS/ACIF S008 2001 AS/ACIF S009 2001
ial control	APAS-0015/1 2001
ry structures inishing - Thermoset powder coatings for	APAS-0015/2 2001
ctural applications roofing of wet areas within residential us	APAS-0200/1 2001
ool th	APAS-0200/2 2001
nance of electrical appliances - Room littioners	APAS-0205 2001 APAS-0260/1 2001
and rating for performance airconditioners and air-to-air heat pumps g and rating for performance tage switchgear and controlgear breakers	APAS-0280/2 2001 APAS-0260/3 2001 APAS-0260/3 2001 APAS-0260/4 2001 APAS-0280/1 2001 APAS-0280/2 2001
to the installation of ceramic tiles to the selection of a ceramic tiling system oction of buildings in bushfire prone areas	APAS-0280/3 2001 APAS-0280/5 2001
u and blended cements al insulation of dwellings - Bulk insulation lation requirements	APAS-2916 2001 ASTM C534 2001
building materials and underlays	AWRAP/A 202 1993
ition requirements ork for air-handling systems in buildings roof and wall cladding materials	BCA 3.1.3.2(b)
ibre reinforced polyester (GRP) sticized polyvinyl chloride (uPVC) wall g boards	BCA 3.3.3.5
rbonate tic kitchen assemblies	BCA 3.4.2.2
Units	BCA 3.4.4.4
	CBPI TN 21A 1985 CBPI TN 21B 1985

One pack semi gloss pigmented solvent borne paving paint for concrete
One pack full gloss pigmented solvent borne paving paint for concrete
One pack clear moisture cured finish for timber Interior gloss latex paint (buildings)

(buildings)
Lightly pigmented solvent borne ranch finish for use (buildings)
Full gloss alkyd enamel for interior use only Refrigeration and Airconditioning Applications Reduction of Emissions of Fluorocarbons in Residential Airconditioning Applications

Reduction of Emissions of Fluorocarbon Refrigerants in Commercial and Industrial

Code of Good Practice

0

Australian Refrigeration and Air n d i t i o n i n g

Domestic open fireplaces

Telecommunications Cabling Handbook

Hot-dip galvanized (zinc) coatings on fabricated ferrous articles
Gas installation code

used in building airconditioning Cold-formed steel structures

Domestic garage doors
Thermal resistance of insulation for ductwork Method 10: Determining resistance to salt attack Masonry units and segmental pavers

Masonry units and segmental pavers - Method of

Installation of nailplated timber trusses

Requirements for authorised cabling products Installation Requirements for Customer Cabling (Wiring Rules)

Full gloss alkyd enamel for exterior and interior

and drainage products

Manual of authorization procedures for plumbing

masonry walls

icts for

good

non

Semi gloss interior latex paint in MCR (buildings)
Low gloss interior latex paint in MCR (buildings)
Washable flat finish for interior use (buildings)
Gloss exterior latex paint in MCR (buildings)

Semi gloss latex paint, exterior (buildings)
Flat or low gloss exterior latex finish in MCR (buildings)
Heavily pigmented low gloss latex ranch finish for exterior timber
Organic zinc rich coating for protection of steel
Standard Specification for Preformed Flexible Elastomeric Cellular Thermal Insulation in Sheet and Tubular Form

Acceptable construction - Site preparation - Termite risk management - Installation of termite Mandatory Woolmark Specifications for building insulation material

Acceptable construction - Masonry - Masonry accessories - Lintels supporting roofs and

framing - General
Acceptable construction - Structural steel
members - Corrosion protection
The Design of Freestanding Clay-Brick Walls Brick Beam Garden Fences Acceptable construction - Framing - Steel

tom miskovich & associates


This is the document referred to in certificate:


Dated: No: C-09-024-1 7-8-09

SPECIFICATION FOR PROPOSED NEW GARAGE, 137 RIVERVIEW RD. CLAREVILLE, N.S.W.

	MEMBER SCHEDULE	ш
TAG	MEMBER SIZE	ЗЧҮТ
P1	Ø450 PILE	RC PILE
GP1-12	125 x 125 x 9.0 SHS	STEEL POST
151,2	'CRANKED' 250 PFC	STEEL STRINGER
LB1	250 PFC	STEEL BEAM
UB1-3	250 PFC	STEEL BEAM
UB4,5	250 UB 26	STEEL BEAM
UB6,7	250 UB 37	STEEL BEAM
UB8	250 UB 31	STEEL BEAM
UB9	250 PFC + 150 x 75 x 10 UA	STEEL BEAMS
UB10-12	250 UB 37	STEEL BEAM
UB13-15	250 UB 26	STEEL BEAM
UB16	300 PFC + 180 PFC	STEEL BEAM
UB17,18	250 UB 26	STEEL BEAM
UB19	250 UB 37	STEEL BEAM







PILE 'P1' DETAIL
SOCKET 100mm INTO ROCK

TYPICAL BASE PLATE DETAILS

NOTE: HOLES IN BASEPLATES TO BE OFFSET WHERE REQUIRED SO THAT ANCHORS ARE NOT CLOSER THAN 70mm TO EDGE OF CONCRETE.



 $\Phi$ 

12 BASE PLATE 2.M12 CHEMSETS


DJ - REFER TO SECTION 10, DWG 6.03

RL 35.00

RL 38.00



300 × 300 × 20 BASE PLATE -4.M20 HOLDING DOWN BOLTS (EMBED 500mm INTO PILE)



A, 69

**√**₽

00

( P

00

O AZ

@ P,

OP

(2.8)

**2**8

THICKENING AT BASE OF RAMP

DE

00

\* ~ D

00

0 A,

<u>~8</u>


=9 0 %


\*EO PI

OPITAR

SP DATE OF A

RL 33.00





GARAGE BALUSTRADE DETAIL 129

F3. Any weak or defective areas of foundation soil shall be removed and replaced with sound granular nativeral (compacted in layers, each not more than 19am, thick, to achieve a nin, dry density ratio of 98% -strandard compaction).

1516' DETAIL from miskovid	2.M% BOLT AT	Continua

'UB9' DETAIL

TYPICAL STEEL POST
TO STUD FRAMING

M12 BOLT-AT 600 CTS.

**₩** × **₩** 

M16 BOLT-AT 300 CTS.

M12 STUD AT 600 CTS.

This is the document referred to in certificate:

No: C-09-024-1

NOTE:
ALL STEELWORK TO BE HOT DIP GALVANISED INCLUDING NUTS, BOLTS AND WASHERS

REFER TO DWG.

1.01 FOR CONSTRUCTION NOTES

STRUCTURAL DRAWING

Date
JUNE 2009

54443

6.01

Title:
LOWER AND UPPER FLOOR
PLANS AND DETAILS D'AMBROSIO CONSULTING STRUCTURAL ENGINEERS

SUITE L/153 VICTORIA ROAD GLADESVILLE NSW 2111 PHONE (02) 9879 5571 FAX (02) 9879 5588 dambrosiscensulting@bigpond.com

NEW GARAGE 137 RIVERVIEW ROAD CLAREVILLE

A ISSUED FOR CONSTRUCTION CERTIFICATE IN ATT. GOSCO.

ARCHITECT

Architect

WARWICK WERNER ARCHITECT PTY. LTD.

4 WARMANONG ROAD,
CAREL BAY, N.S.W. 2007

TEL: 1023 9918 5455 FAX (02) 9918 5462

C6. Spiles in reinforcement are to be made only where shown and damping, except where written approval but been additionally except where written approval to the been additional from the engineer.

C7. LIND provide Storen arisine and large to flability and the pairs as seried before. Secretly the fabric resinforcement of all large and interrections with 1.25m block annealed wire.

BAR DIA. LAB LEXICIT BEAR DIA. LAP LENGIH RIS.

NS. 688 NS. 1989

NS. 688 NS. 1989

C. Concrete shall be madt cared for a minimum of 7 days fallowing placement of concrete. Alternative methods of configuracy to concending provided approval from the unpersing angiver has been obtained.

C. Sown joint to be completed within 15 to 24 hours of placement of concrete.

3. Bishwek or biskwerk supporting concrete or steel anabove shall be been and apparented of the beening surface by 2. Lyang to the parented of the beening surface by 2. Lyang to 1. Apparented of the beening surface by 2. Lyang to 1. Apparented between the best of the beening surface to 1. Apparented between the best of the book to be the a minimal gradual of the 2. Apparented best of the best of the

Brickwork & Biockwork

St. All verbranchip and malarials hall be in
secretare with ASYPA-Harmory Street ures Code
& BCA Part B 13 (a).

Solvitar for the measurery shall be propertiented as follows:
Generally.
Generally.

Stord: A part, Cessent:
Administer a strander dose
Brow damp proof counting and in relationing walls.
Stord: S part, Cessent: part, Line — part
Administer strander dose
Brow damp proof counting part, Line — part
Administer.

Reinforcement is to be fixed so as to achieved the tollowing clear covers:

Structural Limber

11. Accretify and verbactifith shall canaly with a first place of the structural state of structural state of the state of

5 5 32

All concrete works and materials are to be in accordance with ASSABS-Concrete Structures (ode (current edition). BCA Part BL3 (b).
Concrete compressive strength (FC), shall be as follows:

Popuraments

5.6. All steakwak, firings & boll's subnergoed under water
hall be Stainlers Steel Grade 316. Typical U.N.D.

51. All steakwak, firings & bolts in codact with ground
to be hat dop gaiversed and have 2 costs of
"Ornovald applied typ U.N.D.

53. Canastied = HOT DIPPED GALVANEED. Hin. coatling
of \$550,40. To sited hathress up to Sam. & 800g/e2
cover Sam. Noticess.


he bulder shall previde all clears and drail all holes essessary are fusing at feet-own and ensure that the tracture is kept in a stable condition along section. Tractured feet-own has been as the surfaces clean that the drail feet own and are the surfaces clean of treated as follows: International conditions are the clean AS No.274, task and provide 1 cast of a fix the phesphale primar and as Duca 25° in accordance with manufacturers repirements.

sult use/committe and anterests that the in accordance sult ASCHR at BCA Part BL3 (is extept where strated by the contract documents. 
So weder shall be form commons field, all builty polynomial Ziman domainer and all gives are galate to be films first united eitherwise.

So bit wilds where shown shall be complete poeteration but wilds.



SECTION (6.01) 120



SHOP WELD MITRE (BUTT WELD AT CRANK)

-152 BEHIND
FIX TO 'LBT' WITH
10 END PLATE & 2.M20 BOLTS

SECTION 1 120

SECTION 1a 120

SECTION 2 120

1S1 BEYOND
SITE WELD TO
UNDERSIDE OF 'UB2'

151

LB1

70 THICK KILN DRIED HARDWOOD TREADS

FIX TO 'GP6' WITH-

10 END PLATE-2.M20 BOLTS

LB1

SITE WELD ALL ROUND TO 
"GP8", TOUCH UP WITH 2

COATS OF COLD GALV.

UB2 BEYOND

-1.0mm BONDEK

UB1

70 THICK KILN DRIED HARDWOOD TREADS

SL92 MESH

-2.N12 'CAST-IN' (200 LONG)

1 GP6

GP8

tma from miskovich & associates

This is the document referred to in certificate:

No. C-09-024-1

D'AMBROSIO GLADESVILLE NSSV 2711
CONSULTING PHONE (20.2 98.79 52.75
STRUCTURAL ENGINEERS dandwsidedmul/ing/98-to-pond con

LOWER AND UPPER FLOOR SECTIONS. SHEET 2


STRUCTURAL DRAWING

6.02 A S4443

NOTE: ALL STEELWORK TO BE HOT DIP GALVANISED INCLUDING NUTS, BOLTS AND WASHERS

REFER TO DWG. 1.01 FOR CONSTRUCTION NOTES








SECTION (2) 120


	MEMBER SCHEDULE	
TAG	MEMBER SIZE	TYPE
GP1-3,8-10	REFER TO 1.01	STEEL POST
RB1,2	200 UB 30	STEEL BEAM
GB1,2,6,7	250 UB 26	STEEL OUTRIGGER
GB3	250 PFC	STEEL BEAM
GB4	200 × 100 × 5.0 RHS	STEEL BEAM
GB5,8	250 UB 26	STEEL BEAM
GB9	200 UB 18	STEEL BEAM
GB10	200 UB 30	STEEL BEAM
R1	200 x 45 (F16) HYSPAN LVL AT 600 CTS.	TIMBER RAFTERS


ROOF PLAN











Dated	
0	
:	
:	
0	
: 1	
:-	
1	
200	
3 1	
7-8-0	
-	
0	
-0	

tma tom miskovich & associates This is the document referred to in certificate: No: C-09-024-1

A ISSU
ISSUE IMPRIOR
A CAPEEL 8
IEL: (92)
Project: (92)
Pr

IBROSIO SULTING	JARAGE VERVIEW ROAD VILLE
SUITE 1/153 VICTORIA RO GLADESVILLE NSW 2111 PHONE (02) 9879 5577 FAX (02) 9879 5588 dambresiecens ulting@bigpond.co	Đ

	jobs/	.N.O.		C	PLAN	URAL
		JUNE 2009	AAB	TURAL	PLAN	URAL ENGINEERS
B.E. (Hons) M.I.EAust. NPER3 (Structural)	7.01	0 vg. No.   15504	£7775	NUCTURAL DRAWING		PHONE (02) 9879 5577 FAX (02) 9879 5588 dambrasiaconsulting@bigpond.com

REFER TO DWG. 1.01 FOR CONSTRUCTION NOTES

BAY N.S.M. 2007 9918 SLSS FAX (02) 9918 S4.62 GARAGE IVERVIEW ROAD EVILLE	DED FOR CONSTRUCTION CERTIFICATE DEBUT  T  ICK WERNER ARCHITECT P	15.07.09 CHECKED
GARAGE IVERVIEW ROAD EVILLE	ICK WERNER ARCHITECT PTY. LTD. WONG BOAD, BAY, N.S.W. 2107 9918 5455 FAX (02) 9918 5462	וץ. רום.
	GARAGE IVERVIEW ROAD EVILLE	