

4 July 2025

Northern Beaches Council  
725 Pittwater Road  
Dee Why NSW 2099

Address of the Project: **71 Wimbledon Avenue, North Narrabeen**

Description of Project: **New Dwelling**

With reference to the Development Application for the above property, please find enclosed a copy of the site Stormwater Management Plan **STORM-1** for your perusal.

The plan shows collected flows from the proposed roofed areas, along with the surrounding hardstand areas, being discharged into Narrabeen Lagoon at the rear of the site.



Note a rainwater tank has been included for non-potable domestic re-use in accordance with BASIX requirements.

Should you require any further information, please contact the undersigned.

Yours faithfully  
TAYLOR CONSULTING ENGINEERS



**D.M.Schaefer - Director**  
B.E Civil (Hons) M.I.E. Aust. N.E.R.



900 SQ. BOUNDARY PIT WITH  
OUTLET TO SANDSTONE  
BOULDER ENERGY DISSIPATION


NOTE: PLUMBER TO PERFORM WATER TESTING OF EXISTING  
PIPED SYSTEM TO DETERMINE CAPACITY AND STATE OF  
REPAIR. PLUMBER TO INSPECT & REPAIR DAMAGED SECTIONS  
OF EXISTING PIPE (INCLUDING DOWNPIPES) AS NECESSARY  
OR PROVIDE NEW DRAINAGE LINES WHERE NECESSARY  
SUBJECT TO THE APPROVAL BY THE SUPERVISING ENGINEER

PROVIDE STRAMIT 150 HALF  
ROUND EAVES GUTTERS OR  
APPROVED EQUIVALENT  
1700mm<sup>2</sup> (MIN) EAVES GUTTER

SECURE DRAINAGE LINES TO  
UNDERSIDE OF FLOOR STRUCTURE  
AS NECESSARY FOR CONNECTION  
TO RAINWATER STORAGE TANK

PROVIDE 150 WIDE GRATED  
DRAIN ACROSS DRIVE

NOTE: CHECK & LOCATE DEPTH OF EXISTING MAINS &  
SERVICES PRIOR TO CONSTRUCTION OF STORMWATER  
SYSTEM AS VARIATIONS IN POSITION OF MAINS COULD AFFECT DRAINAGE  
CONSTRUCTION DETAILS




PROVIDE SPREADER FOR DISCHARGE  
OF RUNOFF FROM UPPER TO LOWER  
ROOF AREA (TYP)

NOTE: TURN Ø100 'CHARGED'  
P.V.C. DOWNPIPES UP WALL  
SO ARE WATERTIGHT TO 1.0m  
ABOVE TOP OF RAINWATER  
STORAGE TANK

PROVIDE NEW Ø100  
DOWNPIPE (TYP)


NOTE: PROVIDE LOW POINT IN  
CHARGED LINE FOR PERIODIC  
FLUSHING AND MAINTENANCE

RAINWATER STORAGE TANK TO  
BASIX REQUIREMENTS & WITH Ø100  
HIGH LEVEL OVERFLOW OUTLET




### STORMWATER MANAGEMENT PLAN

SCALE 1:100



DETAIL A

SCALE 1:20



DETAIL B

SCALE 1:20

#### DRAINAGE NOTES

- + DENOTES EXISTING GROUND LEVEL
- FALL STORMWATER PIPES AT 1% MIN UNLESS OTHERWISE NOTED.
- SUB-SOIL DRAINAGE TO BE CONNECTED TO THE SITE DRAINAGE SYSTEM AS NECESSARY.
- SURFACE GRATES 300 SQ. UNLESS OTHERWISE NOTED
- ALL STORMWATER PIPES TO HAVE SOLVENT CEMENT WATERTIGHT JOINTS.
- CHECK & LOCATE DEPTH OF EXISTING MAINS & SERVICES PRIOR TO CONSTRUCTION OF STORMWATER SYSTEM AS VARIATIONS IN POSITION OF MAINS COULD AFFECT DRAINAGE CONSTRUCTION DETAILS.
- INSPECTIONS MUST BE UNDERTAKEN BY THIS OFFICE (BY PRIOR ARRANGEMENT WITH ENGINEER) DURING CONSTRUCTION TO ENABLE FULL CERTIFICATION UPON COMPLETION OF WORKS.
- ALL CONSTRUCTION OF COUNCIL DRAINAGE WORKS TO COMPLY WITH COUNCIL STANDARD.
- REMOVE REDUNDANT DRAINAGE PITS AND SEAL PIPES.
- PIT BENCHING TO BE HALF THE OUTGOING PIPE DIAMETER. CONCRETE FOR BENCHING TO BE 20 MPa MASS CONCRETE.
- APPROVED PRE-CAST PITS MAY BE USED.
- ALL PIPES TO BE LAID ON COMPACTED FINE CRUSHED ROCK OR SAND BEDDING 75mm THICK & PIPES BACKFILLED WITH COMPACTED SAND TO 300mm ABOVE TOP OF PIPE, ELSE ATTACHED TO UNDERSIDE OF STRUCTURE AT 600mm c/c AS NECESSARY
- PIPE ROUTES SHOWN ARE INDICATIVE ONLY AND SHOULD BE AS NECESSARY ACCORDING TO SITE CONDITIONS, TREE POSITIONS ETC. CONFIRM SIGNIFICANT CHANGES IN PIPES SYSTEM DETAILS WITH SUPERVISING ENGINEER PRIOR TO COMMENCEMENT OF DRAINAGE CONSTRUCTION WORKS.
- CONTRACTOR SHALL ENSURE THAT SERVICES TO BUILDINGS NOT AFFECTED BY THE WORKS ARE NOT DISRUPTED. CONTRACTOR SHALL CONSTRUCT TEMPORARY SERVICES TO MAINTAIN EXISTING SUPPLY TO BUILDINGS WHERE REQUIRED. ONCE WORKS ARE COMPLETE AND COMMISSIONED THE CONTRACTOR SHALL REMOVE ALL TEMPORARY SERVICES AND MAKE GOOD ALL DISTURBED AREAS.
- STORMWATER SYSTEM REQUIRES SIGNIFICANT MAINTENANCE DUE TO POTENTIAL HIGH POLLUTANT LOAD. FILTERS AND POLLUTANT TRAPS SHOULD BE CHECKED AFTER LARGE STORM EVENTS AND CLEANED EVERY 6 MONTHS.
- PLUMBING AND DRAINAGE WORKS TO COMPLY WITH AS-3500, THE NATIONAL DRAINAGE & PLUMBING CODE.
- WHERE POSSIBLE, DRAINAGE LINES SHALL BE LAID IN AREAS PREVIOUSLY DISTURBED BY OTHER SITE WORKS AND FOLLOW TOPOGRAPHICAL FEATURES TO REDUCE IMPACT AND AVOID TREE ROOTS.
- THIS STORMWATER MANAGEMENT PLAN HAS BEEN PREPARED FOR SUBMISSION TO COUNCIL/CERTIFIER AND DOES NOT NECESSARILY CONTAIN ALL APPROPRIATE INFORMATION TO ENABLE FOR ISSUE TO PLUMBER/BUILDER FOR CONSTRUCTION. CONTACT TAYLOR CONSULTING FOR MORE INFORMATION.

#### RAINWATER RE-USE NOTES AND SPECIFICATIONS



- ROOF WATER ONLY TO BE DRAINED TO THE RAINWATER STORAGE TANK.
- THE RAINWATER STORAGE TANK NEEDS TO BE CONNECTED FOR RE-USE AS REQUIRED BY THE OWNER.
- RAINWATER STORAGE TANK TO BE CONFIGURED IN ACCORDANCE WITH SYDNEY WATER SPECIFICATIONS 'GUIDELINES FOR RAINWATER TANK ON RESIDENTIAL PROPERTIES'.
- PROVIDE MAINS 'TOP-UP' SUPPLY TO RAINWATER TANK. MAINS TOP-UP ZONE TO BE BASED ON THE DAILY NON-POTABLE USAGE THAT MAY BE EXPECTED FROM THE TANK.
- PROVIDE A MECHANICAL PUMPING ARRANGEMENT (IN SOUND-PROOF HOUSING) TO PUMP SUPPLIERS SPECIFICATION TO SUIT INTENDED USAGE OF RAINWATER STORAGE. PUMPING ARRANGEMENTS MUST COMPLY WITH EPA GUIDELINES.
- INLETS TO RAINWATER TANK MUST BE SCREENED TO PREVENT THE ENTRY OF FOREIGN MATTER, ANIMALS OR INSECTS.
- A SIGN MUST BE AFFIXED TO THE RAINWATER TANK CLEARLY STATING THAT THE WATER IN THE TANK IS RAINWATER AND IS NOT TO BE USED FOR HUMAN CONSUMPTION.
- RAINWATER TANK TO BE PLACED ON A STRUCTURALLY ADEQUATE BASE IN ACCORDANCE WITH THE MANUFACTURER'S OR STRUCTURAL ENGINEER'S DETAILS.
- THE TANK MUST NOT BE INSTALLED OVER ANY MAINTENANCE STRUCTURE OR FITTINGS USED BY A PUBLIC AUTHORITY.
- RAINWATER TANK AND ASSOCIATED PLUMBING WORKS TO BE INSTALLED AND CONFIGURED BY A LICENSED PLUMBER. PUMP TO BE INSTALLED BY A LICENSED ELECTRICIAN.

#### STORMWATER SYSTEM DESIGN DATA

##### SITE DATA

SITE AREA = 632 m<sup>2</sup> (100%)  
PROPOSED IMPERVIOUS AREA = 409 m<sup>2</sup> (65%)  
PROPOSED LANDSCAPED AREA = 223 m<sup>2</sup> (35%)  
EXISTING IMPERVIOUS AREA = 372 m<sup>2</sup> (59%)  
EXISTING LANDSCAPED AREA = 260 m<sup>2</sup> (41%)

ISSUE DATE	REVISION

TITLE <b>STORMWATER MANAGEMENT PLAN</b> <b>71 WIMBLETON AVENUE, NORTH NARRABEEN</b>				 <b>TAYLOR</b>	DRAWING NO <b>STORM-1</b>
DRAWN TDR	DATE 4 JULY 2025	CHECKED 	SCALE A1 1:100 1:20 1:10		
ENGINEER RB	BE Civil (Hons) MIE Aust.				