

GROUND FLOOR LAYOUT

REFER TO SHEET 2 FOR RAINWATER TANK DETAILS. LEAF GUTTER GUARDS OR SIMILAR SCREENING RECOMMENDED TO ALL GUTTERS.

BOX GUTTERS AND RWH/S TO BE DETAILED BY SUPPLIER/INSTALLER IN ACCORDANCE WITH AS3500 U.N.O. WHSA HAZARD IDENTIFICATION:

TRENCHING—ALL PERSONS TO FOLLOW THEIR APPROVED SWMS IN RELATION TO BARRICADING DEEP TRENCHES AND WEARING APPROPRIATE CLOTHING. ANY PERSON WORKING INSIDE A TRENCH MUST BE

SUPERVISED BY ANOTHER PERSON.
DIAL BEFORE YOU DIG 1100 MUST BE CHECKED BEFORE ANY
TRENCHING COMMENCES ON SITE. ANY WORKS NEAR IDENTIFIED SERVICES TO BE CARRIED OUT IN ACCORDANCE WITH THE TRADES SWMS. INSTALLATION OF DOWNPIPES AND GUTTERING TO BE CARRIED OUT IN ACCORDANCE WITH INSTALLERS APPROVED SWMS.

(A) EASEMENT TO DRAIN WATER 1 WIDE CREATED BY DEALING AM884209

ALL GROUND LEVELS TO REMAIN UNALTERED IN ACCORDANCE WITH BMB FLOOD REPORT.
 ALL NEW FENCING TO BE OPEN STYLE FENCING TO THE 1% LEVEL TO SATISFACTION OF COUNCIL.
 ALL MATERIALS TO BE FLOOD COMPATIBLE BELOW RL. 86.70 AHD.
 ALL SERVICES BELOW THE 1% FLOOD LEVEL+FREEBOARD ARE TO BE FLOOD PROOFED.
 ALL STRUCTURES TO BE DESIGNED TO WITHSTAND FLOOD WATERS PER BMB FLOOD REPORT

MIN. GRADE

CHARGED

2%

GRATED DRAIN BY OWNER

PIPE SCHEDULE PEFER TO NOTES FOR PIPE CLAS PIPE DIA.

125x75 GAL. PIPE	2%
HALF ROUND BACK GUT (7800sqmn	

ALL OTHER SURFACE WATERS TO BE STRICTLY CONNECTED TO A SEPARATE SYSTEM BY OWNER IN ACCORDANCE WITH AS 3500:.3:2003 AND BCA PART 3.1.2.3.

TO SUPPLY GARDEN TAPS AND INTERNAL RE-USE AS PER BASIX ASSESSM

LEGEND			
	NEW REDUCED LEVEL		
(NEW FINIS	HED GROUND LEVEL)		
+ 00.00	EXISTING LEVEL		
S.L. 0.00	SURFACE LEVEL		
1.L. 0.00	INVERT LEVEL		
T.O.W.	TOP OF WALL LEVEL		
G.F.L.0.00	GARAGE FLOOR LEVEL		
	FINISHED FLOOR LEVEL		
A,B,C etc.	SEE PIPE SCHEDULE		
L1	PIPE LABEL		
PIT P1	SURFACE INLET PIT		
PIT OP1	OVERLAND FLOW PIT		
-aa-	90mm. AG. LINE		
O DP	DOWNPIPE-SIZE		
REFER TO	NOTES FOR DP SIZE		
⊕ GP	GULLY PIT		
⊕ GP	GARDEN GULLY PIT		
= 0/F	OVERFLOW-200x100		
☐ RWH/S	RAIN WATER HEAD/SUMP		
5 SP	DP WITH SPREADER		
⊕ BG	BALCONY GULLY PIT		
◎ CE	CLEANING EYE		
Δ	GROUND FALL		
))))	100 HIGH EARTH MOUNDING		

RAINWATER TANKS WITH PUMPS

<i>IENT</i>		MOUNDING			
S DRAWING IS DIAGRAMMATIC ONLY & NOT TO BE SCALED. IT IS NOT A PART 4A CERT. ER TO ARCHITECTS DRAWINGS FOR DIMENSIONS COPYRIGHT IN THIS DRAWING IS THE PFERTY OF IBRAHIM STORMWATER CONSULTANTS AND THE DRAWING SHALL NOT BE RODUCED OR COPIED, WHOLE OR IN PART, IN ANY FORM WITHOUT THE PRIOR TERN APPROVAL OF IBRAHIM STORMWATER CONSULTANTS					
REVISIONS					

AS3500 -PROVIDE OVERFLOW SPITTERS TO ALL COVERED BALCONIES/ TERRACES. NOT TO BE DIRECTED ON TO ROOF SURFACES

-RISING MAINS (PRESSURE PIPE) TO BE IN ACCORDANCE WITH AS3500.1:2.
-SUBSOIL DRAINS TO BE IN ACCORDANCE WITH AS2439.1 CLASS 100 TO BE USED ONLY IN

GRATES MAY BE USED ONLY IN LIGHT/FOOT TRAFFICABLE AREAS. U.N.O. ALL PITS TO BE BENCHED TO DISCHARGE PIPES U.N.O. GAL. STEP IRONS TO ALL PITS EXCEEDING 900 DEPTH. —COVER AND SUMP GRATES SHALL COMPLY WITH AS2733 & AS4198.

-DOWNPIPES TO BE 90 DIA IF CHARGED AND 100 x 50 BOX IF GRAVITY. U.N.O. DP'S SHALL BE INSTALLED IN ACCORDANCE WITH AS3500.3.2:4.11 & AS4198. MAX. ROOF AREA PER DOWNPIPE WITH A NOMINATED GUTTER SIZE TO BE DETERMINED USING MANUFACTURERS

SPECIFICATIONS WITH OVERFLOW PROVISIONS BY INSTALLERS.

-PIPES TO HAVE 1% MIN.GRADE U.N.O. BY PIT INVERTS. PIPES TO BE V.C. CLASS 'X' OR
U.P.V.C. CLASS STORMWATER PIPE TO AS1254,1260,1273,1477,2179.2 AND WHERE EXPOSED
TO DIRECT SUNLIGHT TO HAVE ADEQUATE PROTECTION TO U.V. RADIATION IN ACCORDANCE

WITH AS2032. SEWER GRADE/GAL. PIPES AND KERB ADAPTORS TO BE USED WHERE COUNCIL POLICY OR CONSENT REQUIRE SUCH.

-GUTTER OUTLETS SHALL BE FITTED VERTICALLY TO THE SOLE OF THE EAVE GUTTERS.

RAINHEADS/BOX GUTTER SUMPS TO HAVE AN OVERFLOW DUCT OR WEIR IN ACCORDANCE WITH

-ALL PIPE JOINTS, VALVES TO BE IN ACCORDANCE WITH AS3500.3.2:2.7 & AS3500.3.2
-EXPANSION JOINTS SHALL COMPLY WITH AS3500.3.2:TABLE 4.1 PVC JOINTS AND ACCESSORIES TO COMPLY WITH AS2179.2 & AS4198.

-ALL TRENCHES TO BE IN ACCORDANCE WITH AS3500.3.2:7.2.8—14. EMBEDMENT MATERIAL AND TRENCH FILL TO ALL PIPES & SUBSOIL, DRAINS TO BE IN ACCORDANCE WITH AS3500.3.2:7, ALL WORKS TO BE IN ACCORDANCE WITH AS1254, 1741, 2032, 2733, 2865, 3996, 1260, 1477, 2179.1 & 2,2566, 6367, 8301, ARR97 & BCA.

-IT IS THE BUILDER'S RESPONSIBILITY TO CONFIRM THAT LEVELS AND SURVEYS ARE IN ACCORDANCE WITH LEVELS ON SITE & ARE APPROVED BY COUNCIL & ARCHITECT BEFORE COMMENCING WORK.

-NO SEWER VENTS, GULLY PITS OR SIMILAR TO BE LOCATED BELOW THE MAXIMUM WATER SURFACE LEVEL IN DETENTION BASINS. ALL BASIN WALLS TO BE WATERTIGHT & STRUCTURALLY DESIGNED BY A STRUCTURAL ENGINEER.

-ALL FENCES WHICH MAY DIVERT FLOW FROM PROPOSED DIRECTION TO BE RAISED 100mm.

-BUILDER TO ENSURE ALL DRAINAGE AREAS INCLUDING EXPOSED BALCONIES TO HAVE OVERFLOW MECHANISM IN PLACE PER NCC WITH ADFOLIATE OVERFLOW SECTION THROUGH PLANTERS PARAPETS FTC. REFER TO ARCHIT FOR

PLACE PER NCC WITH ADEQUATE OVERFLOW SECTION THROUGH PLANTERS, PARAPETS ETC. REFER TO ARCHT. FOR BALCONY DRAINAGE DETAILS

-ALL EXTERIOR FINISHED GROUND LEVELS TO BE SLOPING AWAY FROM PERIMETER WALLS IN ALL CASES.
-ALL HEADROOM CLEARANCES TO BE COORDINATED BETWEEN BUILDER & ARCHITECT. NOTIFY ENGINEER FOR

APPROVAL IF ANY CHANGES OCCUR.

-ALL GULLY POSITIONS ARE DIAGRAMMATIC ONLY— BUILDER SHOULD CONSULT ARCHITECTURALS FOR DIMENSIONS TO LOCATE STORMWATER ELEMENTS U.N.O.

-FIRE RATING TO ARCHITECT'S SPECIFICATION. -ALL FINISHED FLOOR LEVELS ARE NOMINATED BY ARCHITECT.

-ALL FINISHED FLOOR LEVELS ARE NOMINATED BY ARCHITECT.

-ALL SITE SAFETY MEASURES AND WORK METHOD STATEMENTS PREPARED BY BUILDER/SUB-CONTRACTORS ARE TO BE IMPLEMENTED DURING CONSTRUCTION. NO WORK IS TO COMMENCE UNTIL ALL WORKERS CARRY OUT SITE INDUCTION, PREPARED AND CARRIED OUT BY BUILDER. ANY HAZARD IDENTIFICATION TO BE REPORTED IMMEDIATELY TO SITE SUPERVISOR TO CARRY OUT NECESSARY PROCEDURES TO ELIMINATE HAZARD, PRIOR TO PROCEEDING WITH WORK, STRUCTURAL AND GEOTECHNICAL ADVICE SHOULD BE SOUGHT IN ALL CASES.

ROOMENTS CONTRACTOR OF THE PROCEDURE SHOULD BE SOUGHT IN ALL CASES.

WORK. STRUCTURE AND EQUIZE-INICAL ADVICE SHOULD ESSUED IN ALL CASES.

—CONFINED SPACES SIGNAGE TO BE INSTALLED IN ACCESSIBLE UNDERGROUND TANKS TO WORK COVER

SPECIFICATIONS. ALL PITS EXCEEDING 600mm DEPTH TO HAVE 'U' BOLTS OR SIMILAR INSTALLED TO GRATES.

—MAINTENANCE DEVICES REQ'D BY AUTHORITIES ARE NOT TO BE ASSUMED SHOWN ON DRAWINGS.

—EARTH MOUNDING SHOWN AS TEMPORARY MEASURE UNTIL LANDSCAPING COMPLETED TO DIRECT FLOWS AS SHOWN.

ISSUE **PRINTS** ISSUED TO DATE EMAIL BUILDER/CLIENT 24-3-25 EMAIL BUILDER/CLIENT 6-7-25

SCALE(A3) 1:200, 100 u.n.o. SCALE BAR - 1m INTERVALS DATE MAR . 2025 DRAWN M./. DESIGNED M./. APPROVED

P.O. BOX 400 CHERRYBROOK NSW 2126 TELEPHONE: (02) 9980 5515 FAX: (02) 9980 6114 www.stormwater.net.au email: mail@stormwater.net.au PROPOSED RESIDENCE AT 8 RYRIE AVENUE **FORESTVILLE**

FOR MR HUANG & MS JIANG


STORMWATER LAYOUT SH.1 JOB NUMBER

Survey peg out and long section added

REVISION SHEET No. CLARENDON HOMES A

of 3

8	IBRAHII	۱
SIGULTANTS		
188		Ì
LTING		



TANK DETAILS SHOWN ARE A SUGGESTED CONFIGURATION ONLY. ANY MODIFICATIONS TO TANK VOLUME OR INLET AND OUTLET LEVELS MUST BE APPROVED BY ENGINEER PRIOR TO COMMENCEMENT OF CONSTRUCTION. TANK SHAPE, & DEVICES SHOWN ARE DIAGRAMMATIC ONLY. MINIMUM OF 450 CLEARANCE (UNLESS L.G.A. REQUIRES LARGER SETBACK) TO SIDE BOUNDARIES MUST BE MAINTAINED. CLIENT IS RESPONSIBLE TO ENSURE COMPLIANCE WITH THIS IN THE INSTALLED STATE.

Charged stormwater lines from Roof Areas ONLY to rainwater tank.


All joints to be solvent welded. All exposed pipework to be painted to withstand external elements.

First flush water diverter at tank to comply with Sydney Water and council DCP's. An approved switch system similar to 'Rainbank' to be used via mains. Pumps to manuf. specs. Rain Tank to be installed and maintainted to manufacturers specifications and to comply with all Sydney Water Guidelines.

Client to be responsible for maintenance system of charged pipelines. Debris accumulation significantly affects systems performance. Maintenance program essential. Structural details for tank base by manufacturer or others.

WHSA HAZARD IDENTIFICATION:

INSTALLATION OF RAINTANKS: PLUMBER/SITE SUPERVISOR TO ASSESS ACCESS SUITABILITY PRIOR OR POST SLAB CONSTRUCTION.
INSTALLATION OF TANKS TO BE CARRIED OUT FOLLOWING SWMS OF TANK SUPPLIER AND PLUMBER. APPROPRIATE GLOVES TO BE WORN
AT ALL TIMES WHILE HANDLING TANKS.



THIS IS AN ON-SITE STORMWATER


DETENTION SYSTEM REQUIRED BY YOUR LOCAL COUNCIL

IT IS AN OFFENSE TO REDUCE THE VOLUME OR TO INTERFERE WITH THE ORIFICE PLATE THAT CONTROLS THE OUTFLOW

THE BASE OF THE OUTLET CONTROL PIT AND DEBRIS SCREEN MUST BE CLEANED OF DEBRIS AND SEDIMENT ON A REGULAR BASIS BY THE OWNER.

THIS PLATE MUST NOT BE REMOVED

Signange to be provided adjacent tanks Size: 110 mm x 80mm



SILT ARRESTOR PIT - P1

WHSA

WITSA
ALL NEARBY SERVICES TO BE LOCATED PRIOR EXCAVATIONS.
ALL PIPES TO BE CUT FLUSH WITH PIT WALLS AND SPARGED.
PITS EXCEDING 600mm IN DEPTH TO HAVE LOCK DOWN MECHANISM.
SAFETY GEAR TO BE WORN AT ALL TIMES. INCLUDING FOOTWEAR, CLOTHING
AND CLOVES AS PER SWMS

THIS DRAWING IS DIAGRAMMATIC ONLY & NOT TO BE SCALED. IT IS NOT A PART 4A CERT. REFER TO ARCHITECTS DRAWINGS FOR DIMENSIONS COPYRIGHT IN THIS DRAWING IS THE PROPERTY OF BIRAHIMS STORMWATER CONSULTANTS AND THE DRAWING SHALL NOT BE REPRODUCED OR COPIED, WHOLE OR IN PART, IN ANY FORM WITHOUT THE PRIOR WRITTEN APPROVAL OF BIRAHIM STORMWATER CONSULTANTS.

BUILDER/CLIENT TO ENSURE THAT ALL SAFETY MEASURES ARE TAKEN DURING CONSTRUCTION, INCLUDING BUT NOT LIMITED TO, SAFETY FENCING, SIGNAGE, OBTAINING STRUCTURAL AND GEOTECHNICAL ADVICE WHERE EXCAVATIONS ARE NEAR STRUCTURES OR SERVICES, SAFETY MEASURES RECOMMENDED BY PRODUCT SUPPLIERS ETC.

·/	REVIS	SIONS
	Α	Survey peg out and long section added
_		, , , , , , , , , , , , , , , , , , ,

レー	ISSUE	PRINTS	ISSUED TO	DATE
	1	EMAIL	BUILDER/CLIENT	24-3-25
II	2	EMAIL	BUILDER/CLIENT	16-7-25
II				
L				

SCALE(A3)1:200,100 u.n.o.

SCALE BAR - 1m INTERVALS

DATE MAR . 2025

DRAWN M.I.

DESIGNED M.I.

APPROVED



IBRAHIM STORMWATER CONSULTANTS CONSULTING CIVIL ENGINEERS

P.O. BOX 400 CHERRYBROOK NSW 2126
TELEPHONE: (02) 9980 5515 FAX: (02) 9980 6114
www.stormwater.net.au email: mail@stormwater.net.au

PROJEC

PROPOSED RESIDENCE AT 8 RYRIE AVENUE FORESTVILLE FOR MR HUANG & MS JIANG THIS DRAWING

STORMWATER

DETAILS SH. 1

BUILDER


CLARENDON HOMES

C12030-17225

SHEET No.

REVISION

D



LONG SECTION OF PIPELINE

SCALE-1:100

THIS DRAWING IS DIAGRAMMATIC ONLY & NOT TO BE SCALED.

REFER TO ARCHITECTS DRAWINGS FOR DIMENSIONS COPYRIGHT IN THIS DRAWING IS THE
PROPERTY OF IBRAHIM STORMWATER ONSULTANTS AND THE DRAWING SHALL NOT BE
REPRODUCED OR COPIED. WHOLE OR IN PART, IN ANY FORMWITHOUT THE PRIOR
WRITTEN APPROVAL OF IBRAHIM STORMWATER CONSULTANTS

REVI	SIONS
Α	Survey peg out and long section added
	JOD MUMAPED

<i>"</i>	ISSUE	PRINTS	ISSUED TO	DATE
	2	EMAIL	BUILDER/CLIENT	16-7-25
\				1

D

SCALE(A3)1:200,100 u.n.o.
SCALE BAR - 1m INTERVALS
DATE MAR . 2025
DRAWN M.I.
DESIGNED M.I.
APPROVED



IBRAHIM STORMWATER CONSULTANTS CONSULTING CIVIL ENGINEERS

P.O. BOX 400 CHERRYBROOK NSW 2126
TELEPHONE: (02) 9980 5515 FAX: (02) 9980 6114
www.stormwater.net.au email: @stormwater.net.au

PROPOSED RESIDENCE AT 8 RYRIE AVENUE FORESTVILLE FOR MR HUANG & MS JIANG THIS DRAWING

STORMWATER

DETAILS SH.2

BUILDER

JOB NUMBER C12030-17225

CLARENDON HOMES SHEET No. 3 of 3

REVISION