

Qualified Arborist
Tree Removal
Hedge Trimming
Lawn Moving
Acreage
Soft Landscaping



Topiarian Shaping
Garden Maintenance
Mulch & Firewood
Garden Makeovers
Hard Landscaping
Strata Maintenance

Paul Mabbott's Tree Service

ABN 39 018 254 350

mob: 0411 082 488

paul@paulmabbott.com

tel: 02 9679 2139

fax: 02 8580 6293

Date: Monday 15 07 2013

Client: David from HUMEL Architects

Property: Old Darby & Joan site

Inspection Date: 15 July 2013

On first sight of this tree displays a good canopy but on closer inspection there were four large cases of bora evident and lateral root degradation. What this means is any works carried out in a southerly or westerly direction within 5 to 8 meters of this tree is likely to jeopardise the structural integrity of the root system. There is also a large water pipe under this tree and if it ever where to rupture this would have a huge impact on this tree and area around it.

In my opinion this tree is unsustainable and no amount of tree surgery will result in any form of sustainable recovery to full vigour. Any form of excavation work within 5m of this tree will weaken the tree ass possible root failure. This tree looks like it has no lateral roots towards the foot path and drive way it also has a large amount of bora evident in photos. My opinion is this tree should be removed and when completion of works is done a replacement blood wood of significant size should be put back in same place so as to grow within the so rounding area.





















