

					²⁰ I ₅	¹⁰⁰ / ₅	From	From	Downpipe
Eaves	Horizontal	slope		Gutter			Figure	Figure H1	From
	$Area\ A_h$	factor	Area A _c	Slope	from	from	3.5.4(A)	gutter	Table 3.5.2
Gutters		From		steeper	Council	DRAINS	gutter	size reqd	size reqd
		Fig 3.4.3.2		than	Appendix 12	mm/hr	area reqd	mm	mm
	m^2		m^2	1 in	mm/hr		mm^2		
EXDP1/RWH	37	1.05	38.9	500	201		7500		100x75 or 100dia
EXDP2/RWH	32.7	1.05	34.3	500	201		7000		100x75 or 100dia
DP3/RWH	28.3	1.05	29.7	500		267	6300	300x150	100x50 or 90dia
DP4	14.8	1.05	15.5	500	201		3500		100x50 or 90dia
DP5/RWH	36.3	1.05	38.1	500		267	7500	300x150	100x50 or 90dia
EXDP6/RWH	32.7	1.05	34.3	500	201		7000		100x75 or 100dia
EXDP7/RWH	37	1.05	38.9	500	201		7500		100x75 or 100dia
total	218.8								
New Gutters	similar to ex	isting - Half	Round		Area	9000	mm^2		
All undergrou	und Pipes to	be 100 Dia	Sewer Gra	ide PVC UI	NO				

GUTTER CALCULATIONS



OUTLET ONTO ROCK

CONCRETE SLAB -CLEAN COMPACTED SAND STORMWATER PIPE COMPACTED SAND BED ਨ ∑ 600

REFER STORMWATER NOTES

450x450 PIT DETAIL

SCALE = 1 : 20

TYPICAL TRENCHING DETAIL

SCALE = 1 : 20

NOTES:

1. ALL DIMENSIONS TO BE VERIFIED ON SITE BEFORE

5 - DOWN PIPE LOCATIONS ARE INDICATIVE ONLY. LOCATIONS TO BE

7 - ALL PITS TO BE PRECAST, PREFORMED OR HDPE, IN ACCORDANCE

8 - ALL PITS GREATER THAN 1000mm DEEP SHALL HAVE STEP IRONS

9 - ALL WORK TO BE IN ACCORDANCE WITH LOCAL COUNCIL STANDARDS

10 - PRIOR TO COMMENCING ANY SITE WORKS THE CONTRACTOR SHALL

13 - ALL EXISTING EARTHENWARE PIPES TO BE UPGRADED TO UPVC.

14 - ALL WORKS TO BE IN ACCORDANCE WITH AS 3500.3-2021 NATIONAL

IMPLEMENT EROSION CONTROL MEASURES TO EPA GUIDELINES AND COUNCIL SPECIFICATIONS. ALL MEASURES TO REMAIN IN PLACE UNTIL

12 - ENSURE THAT ALL PITS AND STORMWATER PIPES ARE LOCATED CLEAR

COMPLETION AND STABILIZATION OF THE SITE TO COUNCIL SATISFACTION.

PLUMBING DRAINAGE CODE PART 3 - STORMWATER DRAINAGE \$ NCC 2022

6 - PROVIDE CLEANING EYES AT ALL DOWNPIPES.

WITH LOCAL COUNCIL SPECIFICATIONS.

AS PER COUNCIL STANDARDS.

11 - ALL LEVELS SHOWN ARE TO AHD

FROM TREE ROOT SYSTEMS.

AND SPECIFICATIONS

CONFIRMED WITH ARCHITECT PRIOR TO COMMENCEMENT WITH WORK.

COMMENCING WITH WORK. 2. TO BE PRINTED IN COLOUR. DOCUMENT CERTIFICATION Date: NOV. 25 Bruce Lewis (Principal: Peninsula Consulting Engineers)

BE(Civil), CPEng, MIEAust., NPER.

FOR COUNCIL SUBMISSION 6-11-2025 30-10-2025 P2 DRAFT E: bruce@peninsulaconsulting.com.au A.B.N. 60 493 390 399 Amendment: Institute of Engineers Membership No. 879131

Peninsula Consulting Engineers PO Box 6186, Narraweena, NSW, 2099 Ph: 0424 253 818


All Gutters to be graded at 1 in 500 to Downpipes


PROPOSED WORKS at: 11A MONASH CRESCENT CLONTARF for: MS SMITH & MR BROOKS

The copyright of this drawing remains with Peninsula Consulting Engineers.

STORMWATER MANAGEMENT PLAN & DETAILS

Drawing No: H01 25-0508





SEDIMENT FENCE

CONSTRUCTION NOTES:

CONSTRUCT SEDIMENT FENCE AS CLOSE AS POSSIBLE TO PARALLEL TO THE CONTOURS OF THE SITE.


DRIVE 1.5 METRE LONG STAR PICKETS INTO GROUND, 3 METRES APART.

DIG A 150mm DEEP TRENCH ALONG THE UPSLOPE LINE OF THE FENCE FOR THE BOTTOM OF THE FABRIC TO BE ENTRENCHED. BACKFILL TRENCH OVER BASE OF FABRIC.

FIX SELF-SUPPORTING GEOTEXTILE TO UPSLOPE SIDE OF POSTS WITH WIRE TIES OR AS RECOMMENDED BY GEOTEXTILE MANUFACTURER. JOIN SECTIONS OF FABRIC AT A SUPPORT POST WITH A 150mm OVERLAP.

SEDIMENT CONTROL:


- 1. INSTALL SEDIMENT CONTROL STRUCTURES IN LOCATIONS INDICATED ON DRAWINGS AND AS OTHERWISE REQUIRED TO CONTROL SEDIMENT DURING ALL EXCAVATIONS AND WHILST AREAS OF THE SITE ARE EXPOSED TO EROSION.
- 2. CONTROL STRUCTURES TO BE AS DETAILED OR AS OTHERWISE REQUIRED BY CERTIFYING AUTHORITY.
- 3. REVIEW CONTROL MEASURES AND MAINTAIN STRUCTURES DURING CONSTRUCTION.
- 4. IF ADDITIONAL MEASURES ARE REQUIRED FOR EROSION CONTROL OR BY COUNCIL REQUIREMENTS REFER TO "URBAN EROSION AND SEDIMENT CONTROL" GUIDELINES PREPARED BY THE DEPARTMENT OF CONSERVATION AND LAND MANAGEMENT.




TYPICAL TEMPORARY CONSTRUCTION

ENTRY/EXIT DETAIL


- **CONSTRUCTION NOTES:**
- 1. STRIP TOPSOIL AND LEVEL SITE.
- 2. COMPACT SUBGRADE. 3. COVER AREA WITH NEEDLE-PUNCHED GEOTEXTILE.
- 4. CONSTRUCT 200mm THICK PAD OVER GEOTEXTILE USING ROADBASE or 30mm AGGREGATE. MINIMUM LENGTH 15 METRES OR TO BUILDING
- ALIGNMENT. MINIMUM WIDTH 3 METRES. 5. CONSTRUCT HUMP IMMEDIATELY WITHIN BOUNDARY TO DIVERT WATER TO A SEDIMENT FENCE or OTHER SEDIMENT TRAP.







GRAVEL KERB INLET SEDIMENT TRAP

SANDBAG KERB INLET SEDIMENT TRAP







REMOVABLE HAY BAIL DETAIL

SCALE = N.T.S.

REMOVABLE HAY BAIL DETAIL SCALE = N.T.S.

SILT FENCE DETAIL - OPTION 2 SCALE = N.T.S.

NOTES:

- 1. ALL DIMENSIONS TO BE VERIFIED ON SITE BEFORE
- COMMENCING WITH WORK. 2. TO BE PRINTED IN COLOUR.



Date: NOV. 25 Bruce Lewis (Principal : Peninsula Consulting Engineers) BE(Civil), CPEng, MIEAust., NPER. Institute of Engineers Membership No. 879131

	6-11-2025	Α	FOR COUNCIL SUBMISSION
• • •	30-10-2025	P2	DRAFT
	Date:	Rev:	Amendment:



The copyright of this drawing remains with Peninsula Consulting Engineers. PROPOSED WORKS at: 11A MONASH CRESCENT CLONTARF for: MS SMITH & MR BROOKS

Drawing Title: SEDIMENT & EROSION CONTROL PLAN & DETAILS

25-0508

Drawing No: H02