



Reference number 3578

Member of the Fire Protection Association of Australia

Lot 17, DP 8595, 121 Pacific Road, Palm Beach, NSW 2108.

Thursday, 7 October 2021

Prepared and certified by:	Matthew Willis BPAD – Level 3 Certified Practitioner Certification No: BPD-PA 09337		07/10/2021
Can this proposal comply with AS3959-2018 (inc section 7.5, 7.5.1, 7.5.2, 7.5.3, 7.5.4 (where applicable) of the Rural Fire Services document Planning for Bushfire Protection 2019)?	Yes		
What is the recommended AS 3959-2018 level of compliance?	BAL-19 and BAL-12.5		
Is referral to the RFS required?	No		
Can this development comply with the requirements of PBP?	Yes		
Plans by "Daniel Boddam" (Appendix 1) dated.	3/9/21		

© This document is copyright. It is a breach of copyright for this document to be used to support a development application or any other purpose for any persons/entities other than those for whom this document was prepared. Other than for the purpose for which this document has been prepared and subject to conditions prescribed under the Copyright Act no part of this document may in any form nor by any means be reproduced or stored in a retrieval system or transmitted without the prior written permission of the company (Bushfire Planning Services Pty Ltd ACN 115 714 826).



Bushfire Planning Services

15 Parkcrest Place

Kenthurst NSW 2156

02 96543228

0428408577

mattw@bushfireconsultants.com.au

Bushfire Risk Assessment

Thursday, 7 October 2021

Contact

Jane Cleary

Daniel Boddam Architecture and Interior Design

Po Box 1946

Potts Point NSW 2011

9660 1144

Subject Property

Lot 17, DP 8595

121 Pacific Road

Palm Beach NSW 2108

BUSHFIRE RISK ASSESSMENT CERTIFICATE

THIS FORM IS TO BE COMPLETED BY A RECOGNISED CONSULTANT IN BUSHFIRE RISK ASSESSMENT IN ACCORDANCE WITH SECTION 79BA 1(b) OF THE ENVIRONMENTAL PLANNING AND ASSESSMENT ACT 1979 NO 203

Property Address	Lot 17, DP 8595, number 121 Pacific Road Palm Beach
Description of the Proposal	Construction of a new dwelling
Plan Reference	3/9/21
BAL Rating	BAL-19 and BAL-12.5
Does the Proposal Rely on Alternate Solutions?	No

I, Matthew Willis of Bushfire Planning Services Pty Ltd have carried out a bushfire risk assessment on the above-mentioned proposal and property. A detailed Bushfire Assessment Report is attached which includes the submission requirements set out in Planning for Bushfire Protection 2019 together with recommendations as to how the relevant Specifications and requirements are to be achieved.

I hereby advise, in accordance with Section 4.14 of the Environmental Planning and Assessment Act 1979 No 203:

1. That I am a person recognised by the NSW Rural Fire Service as a qualified consultant in bushfire risk assessment; and
2. That subject to the recommendations contained in the attached Bushfire Risk Assessment Report the proposed development conforms to the relevant specifications and requirements*

*The relevant specifications and requirements being specifications and requirements of the document entitled Planning for Bush Fire Protection prepared by the NSW Rural Fire Service in co-operation with the Department of Planning and any other document as prescribed by Section 4.14 of the Environmental Planning and Assessment Act 1979 No 203.

I am aware that the Bushfire Assessment Report, prepared for the above-mentioned site is to be submitted in support of a development application for this site and will be relied upon by Northern Beaches Council as the basis for ensuring that the bushfire risk management aspects of the proposed development have been addressed in accordance with Planning for Bushfire Protection 2019.

REPORT REFERENCE	Thursday, 7 October 2021
REPORT DATE	Thursday, 7 October 2021
CERTIFICATION NO/ACCREDITED SCHEME	FPA A BPAD A BPD-PA 09337

Attachments:

- Bushfire Risk Assessment Report
- Recommendations

SIGNATURE: ---  ----- **DATE:** -----Thursday, 7 October 2021

Contents.

1	Executive Summary.	5
2	General.	6
3	Block Description.	6
4	Vegetation.	8
5	Known constraints on subject block.	10
6	Slope.	10
7	Utilities.	11
7.1	Water.	11
7.2	Electricity	11
7.3	Gas	11
8	Access/Egress.	11
9	Compliance with Planning for Bushfire Protection setbacks.	12
10	Siting.	13
11	Construction and design.	13
12	Utilities.	14
12.1	Water.	14
12.2	Electricity and Gas.	14
13	Asset Protection Zone (APZ).	14
14	Landscaping.	14
15	Constraints on the subject block.	15
16	Access/Egress.	15
17	Compliance or non compliance with the specifications and requirements for bushfire protection measures.	16
18	Conclusions.	16
19	References.	18
20	Appendix 1 - Plans .	19

1 Executive Summary.

Bushfire Planning Services has been requested by Jane Cleary from Daniel Boddam Architecture and Interior Design to supply a bushfire compliance report on lot 17, DP 8595, 121 Pacific Road, Palm Beach.

The works proposed for the subject lot are for the construction of a new dwelling, see attached plans for details.

The subject lot is on the eastern side of Pacific Road and at its closest point to the hazard the proposed new work has a separation distance to the west of approximately 96m.

The vegetation that is considered to be the hazard to this proposal is situated on land that slopes down slope away from the property at an angle of approximately 21.70°.

For the purposes of this assessment this vegetation is considered to be Forest.

The remaining vegetation within the study area is contained within the boundaries of established allotments and is managed land and of low threat to this proposal.

The calculations and assumptions outlined in this report show that the development will be required to comply with the construction requirements of AS 3959-2018 BAL-19 on its exposed western, northern and southern aspects, and BAL-12.5 on the eastern aspects and any additional construction requirements contained within section 7.5, 7.5.1, 7.5.2, 7.5.3, 7.5.4 (where applicable) of the Rural Fire Services document Planning for Bushfire Protection 2019.

The following table is a summary of the pertinent findings of this assessment.

Aspect	North	East	South	West
Vegetation type	Managed land	Managed land	Managed land	Managed land/forest
Slope	N/A	N/A	N/A	Greater than 20 degrees downslope
Setback within lot 17	N/A	N/A	N/A	24m
Setback outside lot 17	N/A	N/A	N/A	72m
Total setback	N/A	N/A	N/A	96m
Bal level	N/A	N/A	N/A	BAL-FZ

Note: The above table is a summary of the significant variables used to determine the highest BAL for this proposal. THIS TABLE IS NOT INTENDED FOR CONSTRUCTION! Only the highest BAL level is shown, aspects marked as N/A will still have a BAL. Refer to section 11 for construction requirements for these other aspects.

2 General.

This proposal relates to the construction of a new dwelling on the subject lot and its ability to comply with the rules and regulations for building in a bushfire prone area.

The methodology used on this report is based on Planning for Bushfire Protection 2019 (PBP) as published by the New South Wales Rural Fire Service.

Any wording that appears in *blue italics* is quotes from Planning for Bushfire Protection 2019. Some of the measurements used in this report have been taken from aerial photographs and as such are approximate only.

3 Block Description.


The subject block is situated on the eastern side of Pacific Road in an established area of Palm Beach.

The lot currently contains a single-level class 1 dwelling.


The lands surrounding the proposed site on the subject lot to a distance of at least 96m contain existing development or land that is otherwise not considered to be a significant bushfire hazard.

- Lot; 17
- DP; 8595.
- LGA; Northern Beaches.
- Area; 3065m².
- Address; 121 Pacific Road, Palm Beach.

This section has been left blank.



Map 1 shows the cadastral layout around the subject lot.



Map 2 is an extract from the councils' bushfire prone land map. The map shows lot 17 to be within the buffer zone of category 1 bushfire vegetation.

4 Vegetation.

The study area for the vegetation is 140m surrounding the subject block.

The vegetation within the study area for this development is considered to be largely managed land.

The major potential hazard to this development is the vegetation within an area of undeveloped land to the west.

For the purpose of this assessment and compliance with Planning for Bushfire Protection this area of undeveloped land is considered to be Forest and is the hazard to this proposal.



Photo 1 - An overview of the vegetation within the general area.

This area has been left intentionally blank.



Photo 2 is a closer view of the vegetation in the area.

Table 1 outlines the vegetation orientation and distance from the development area.

Aspect	North	East	South	West
Vegetation type	Managed land	Managed land	Managed land	Managed land/forest
Setback within lot 17	N/A	N/A	N/A	24m
Off-site setback	N/A	N/A	N/A	72m
Total setback	N/A	N/A	N/A	96m

Table 1 - Any aspect marked with "N/A" in the table above indicates that it is considered there is none or only a secondary hazard in that direction.

This area has been left intentionally blank.

5 Known constraints on subject block.

I have not been informed or know of any places of cultural or environmental significance within the boundaries of the subject block. Given the nature of the surrounding land it is considered highly unlikely that anything of significance will be affected by this development.

6 Slope.

The slope of the land beneath the hazard that is most likely to influence bushfire behaviour has been calculated by topographical map analysis to a distance of 100m from the subject lot. An extract of the topographical map for the area is shown below and the relevant slope analysis is shown in Table 2.




Table 2 shows the slope beneath the hazard.

Aspect	North	East	South	West
Slope	N/A	N/A	N/A	Greater than 20 degrees downslope


Table 2 - Any aspect marked with "N/A" in the table above indicates that it is considered there is no hazard in that direction.

7 Utilities.

7.1 Water.

The subject block will be serviced by a reticulated water supply.

The following map is an extract from Sydney waters hydrant map. Hydrants are indicated by a blue dot on a blue line. As can be seen there is at least one hydrant point indicated within close proximity of the property.



7.2 Electricity

Main's electricity is available to the block.

7.3 Gas

It is unknown if either bottled or mains gas is to be altered or installed in this proposal.

8 Access/Egress.

Access to the development site will be via a short private driveway from Pacific Road.

All roads in the vicinity are considered to be capable of carrying emergency services vehicles and pedestrian access onto the lot is also considered to be adequate.

Analysis of development and recommendation.

9 Compliance with Planning for Bushfire Protection setbacks.

Planning for Bushfire Protection gives Deemed to Satisfy (DTS) tables to calculate Bushfire Attack Levels (BAL's) for slopes up to 20 degrees downslope.

As the slope beneath the hazard for this proposal exceeds 20 degrees a performance based calculation using method 2 of AS2959-2018 is required.

This calculation, as one of its outputs, gives a "flame length" for the design fire. The RFS considers that anything within the length of this flame is within the Flame Zone of the hazard.

In this instance the flame length is approximately 83m, the available separation distance is greater than the calculated flame length, flame contact will not occur.

Given there is no flame contact the determining factor for the BAL is the projected radiant heat. As can be seen in the following table the RHF has been calculated to be 16.14kW/m² making the appropriate BAL for the fire prone aspects BAL-19.

Assessment Details				+!
Run Description:	West		Run Calc	☐ Override Slope Kataburn
Filter Vegetation Class:	PBP 2019			
Vegetation Type:	Forest (including Coastal Swamp Forest)			
Separation Distance (m):	96	Slope Unit:	Degrees	
Vegetation Slope:	22	Vegetation Slope Type:	Downslope	
Site Slope:	0	Site Slope Type:	Level	
Flame Width (m):	100	Flame Temp (K):	1090	
Elevation of Receiver (m):	Default	Note: Leave as Default to copy peak elevation.		
Heat Shield Height (m):	0	Note: Measured directly against the vegetation.		
Heat Shield Width (m):	0	Note: Measured in the centre of the vegetation.		
Short Fire Run Inputs				
Calculate Short Fire Run	☐	Fire Run (m):	0	
Forest Flame Model:	McArthur	Vegetation Height (m):	2	
Results				
Radiant Heat (kW/m ²):	16.14	Rate Of Spread (km/h):	12.05	☐ Override ROS
Flame Length (m):	82.63	Transmissivity:	0.745	☐ Override Transmissivity
Construction Level:	BAL 19	Peak Elevation of Receiver (m):	32.11	
Fire Intensity (kW/m):	224688	Flame Angle (degrees):	51	☐ Override Flame Angle
Inner Protection Area (m):	58	Maximum View Factor:	0.285	☐ Override View Factor
Outer Protection Area (m):	38	Shielded View Factor:	0	

10 Siting.

The current site provides adequate separation between the proposed building and surrounding vegetation for a compliant structure to be built.

Recommendation;

Nil.

11 Construction and design.

All new work is to be undertaken in accordance with the relevant requirements of the NCC and AS3959 2018. The following recommendations are a minimum level of construction. Constructing the proposal to a higher level than that recommended is allowable under AS3959.

Recommendation; all new work to the western, northern and southern aspects.

1. New construction on the western, northern and southern aspects shall comply with the requirements of section 3 of Australian Standard AS3959-2018 "Construction of buildings in bush fire-prone areas" and,
2. New construction on the western, northern and southern aspects shall also comply with the requirements of BAL-19 Australian Standard AS3959-2018 "Construction of buildings in bush fire-prone areas" or NASH Standard "National Standard Steel Framed Construction in Bushfire Areas" and any additional construction requirements contained within section 7.5, 7.5.1, 7.5.2, 7.5.3, 7.5.4 (where applicable) of the Rural Fire Services document Planning for Bushfire Protection 2019.

Recommendation; all new work to the eastern aspect.

3. New construction on the eastern aspects shall comply with the requirements of section 3 of Australian Standard AS3959-2018 "Construction of buildings in bush fire-prone areas" and,
4. New construction on the eastern aspects shall also comply with the requirements of and BAL-12.5 Australian Standard AS3959-2018 "Construction of buildings in bush fire-prone areas" or NASH Standard "National Standard Steel Framed Construction in Bushfire Areas" and any additional construction requirements contained within section 7.5, 7.5.1, 7.5.2, 7.5.3, 7.5.4 (where applicable) of the Rural Fire Services document Planning for Bushfire Protection 2019.
5. New roofing valleys and guttering should be fitted with a non-combustible leaf protection to stop the accumulation of debris.

AS-3959 2018 is available as PDF from;

https://infostore.saiglobal.com/en-au/standards/as-3959-2018-122340_saig_as_as_2685241/

12 Utilities.

12.1 Water.

The proposed development will have access to a reticulated water supply. There is at least one hydrant indicated within the required distance from the dwelling.

Recommendation;

Nil.

12.2 Electricity and Gas.

Recommendation;

6. Any new electricity or gas connections are to comply with the requirements of table 7.4a of Planning for Bushfire Protection.

13 Asset Protection Zone (APZ).

The Asset Protection Zone is *“An area surrounding a development managed to reduce the bushfire hazard to an acceptable level. The width of an APZ will vary with slope, vegetation and construction level”*.

Recommendation;

7. At the commencement of building works and in perpetuity the entire property shall be managed as an Asset Protection Zone in accordance with the requirements of Planning for Bushfire Protection, the RFS document Standards for Asset Protection Zones and in a manner that does not create a bushfire hazard to the property.

14 Landscaping.

Recommendation;

8. Any new fencing is to be constructed in accordance with section 7.6 of Planning for Bushfire Protection 2019.
9. Any new landscaping to the site is to comply with the principles of Appendix 4 and section 3.7 of Planning for Bush Fire Protection 2019. In this regard the following landscaping principles are, where applicable, to be incorporated into the development¹:
 - Suitable impervious areas being provided immediately surrounding the building such as courtyards, paths and driveways;

¹Refer to referenced documents for a complete description.

- Grassed areas/mowed lawns/ or ground cover plantings being provided in close proximity to the building;
- Restrict planting in the immediate vicinity of the building which may over time and if not properly maintained come in contact with the building;
- Maximum tree cover should be less than 30%, and maximum shrub cover less than 20%;
- Planting should not provide a continuous canopy to the building (i.e. trees or shrubs should be isolated or located in small clusters);
- When considering landscape species consideration needs to be given to estimated size of the plant at maturity;
- Avoid species with rough fibrous bark, or which retain/shed bark in long strips or retain dead material in their canopies;
- Use smooth bark species of trees species which generally do not carry a fire up the bark into the crown;
- Avoid planting of deciduous species that may increase fuel at surface/ ground level (i.e. leaf litter);
- Avoid climbing species to walls and pergolas;
- Locate combustible materials such as woodchips/mulch, flammable fuel stores away from the building;
- Locate combustible structures such as garden sheds, pergolas and materials such timber garden furniture way from the building; and
- Use of low flammability vegetation species.

15 Constraints on the subject block.

None known.

Recommendation;

Nil

16 Access/Egress.

All roads in the area are considered to be capable of handling emergency service vehicles. Access from the roadway onto the property is also considered to be adequate for firefighting purposes.

Recommendation

Nil

17 Compliance or non compliance with the specifications and requirements for bushfire protection measures.

APZ A defensible space is provided onsite. An APZ is provided and maintained for the life of the development.	Achievable with the implementation of the recommendations in section 13
SITING AND DESIGN: Buildings are sited and designed to minimise the risk of bush fire attack.	Achievable with the implementation of the recommendations in section 10
CONSTRUCTION STANDARDS: It is demonstrated that the proposed building can withstand bush fire attack in the form of wind, smoke, embers, radiant heat and flame contact.	Achievable with the implementation of the recommendations in section 11
ACCESS Safe, operational access is provided (and maintained) for emergency services personnel in suppressing a bush fire while residents are seeking to relocate, in advance of a bush fire, (satisfying the intent and performance criteria for access roads in sections 4.1.3 and 4.2.7).	Achievable with the implementation of the recommendations in section 16
WATER AND UTILITY SERVICES: - adequate water and electricity services are provided for firefighting operations - Gas and electricity services are located so as not to contribute to the risk of fire to a building.	Achievable with the implementation of the recommendations in section 12
LANDSCAPING: it is designed and managed to minimise flame contact and radiant heat to buildings, and the potential for wind driven embers to cause Ignitions.	Achievable with the implementation of the recommendations in section 14

18 Conclusions.

Based on the above report and with the implementation of the recommendation contained within this report the consent authority should determine that this development can comply with the requirements of AS 3959-2018 and 'Planning for Bushfire Protection' guidelines.

The recommendations contained within this report are to be implemented in their entirety. Changing one aspect may have an adverse effect on the rest of the recommendations.

Bushfires are affected by many external influences such as climactic conditions, vegetation type, moisture content of the fuel, slope of the land and human intervention to name a few and are difficult to predict.

This report does not intend to provide a guarantee that the subject property will survive if a bushfire should impact the surrounding area. The purpose of this report is to show the

developments level of compliance or in some cases non-compliance with the New South Wales legislation regarding building in bushfire prone areas.

Where non-compliance is found measures will be suggested that should make the building less susceptible to the various attack mechanisms of a bushfire and comply with the performance requirements of the Building Code of Australia.

The opinions expressed in this report are based on the writers' experience and interpretation of the relevant guidelines and standards. Notwithstanding the above, these guidelines and standards are open to interpretation. All care has been taken to ensure that the opinions expressed in this report are consistent with past successful outcomes.

Some of the information used in the compilation of this assessment has been provided by the proponent or the proponent's representatives. While we believe this information to be true and have accepted the information in good faith however this company or its representatives will not accept any responsibility if the provided information is determined to be incorrect.

This document is to assist the consenting authorities with their assessment of this proposal. The recommendations contained in this assessment reflect the normal conditions that are typically applied by the consent authority for a proposal such as this however the conditions of consent for the proposal will be supplied by the certifying authority on approval of the development and may not necessarily be the same as the recommendations of this assessment.

The recommendations in this assessment are for planning guidance only, construction details and compliance with all building requirements are the responsibility of the Architect/Designer, Builder and Certifier.

To avoid confusion, unless specifically referenced by the consenting authority, it is strongly recommended that once this proposal has been approved that this document is no longer referenced and that only the official conditions of consent as reflected in documentation by the certifying body are used for construction guidance.

If any further clarification is required for this report, please do not hesitate to contact me using the details above.

Yours Sincerely



Matthew Willis

Grad Dip Planning for Bushfire Prone Areas

Bushfire Planning Services Pty Limited

19 References.


- *Australian Building Codes Board (2019). National Construction Code Volume One - Building Code of Australia. ABCB*
- *Australian Building Codes Board (2019). National Construction Code Volume two - Building Code of Australia. ABCB.*
- *Keith, D.A. (2004). Ocean Shores to Desert Dunes: The Native Vegetation of New South Wales and the ACT. NSW Department of Environment and Conservation.*
- *National Association of Steel Framed Housing (2014). "Steel Framed Construction in Bush Fire Areas. NASH*
- *Ramsay, C and Rudolph, L (2003) "Landscape and Building Design for Bush fire Areas". CSIRO Publishing, Collingwood.*
- *Resources and Energy NSW (2016). ISSC 3 Guide for the Managing Vegetation in the Vicinity of Electrical Assets. NSW Government*
- *Rural Fire Service NSW (2005) "Standards for Asset Protection Zones"*
- *Standards Australia (2018). "AS 3959, Construction of buildings in bush fire prone areas".*
- *Standards Australia (2018). "AS/NZS 1530.8.1 Methods for fire tests on building materials, components and structures - Tests on elements of construction for buildings exposed to simulated bush fire attack - Radiant heat and small flaming sources".*
- *Standards Australia (2018). "AS/NZS 1530.8.2 Methods for fire tests on building materials, components and structures - Tests on elements of construction for buildings exposed to simulated bush fire attack - Large flaming sources".*
- *Standards Australia (2014). "AS/NZS 1596 The storage and handling of LP Gas".*




DOSE SCHEDULE						
TIME	DATE	DOSE#	DOSE	DOSE VOLUME	INCLINAC	NOTES
001	001	0000	0000			
002	001	0000	0000			
003	001	0000	0000			
004	001	0000	0000			
005	001	0000	0000			
006	001	0000	0000			
007	001	0000	0000			
008	001	0000	0000			
009	001	0000	0000			
010	001	0000	0000			
011	001	0000	0000			
012	001	0000	0000			
013	001	0000	0000			
014	001	0000	0000			
015	001	0000	0000			
016	001	0000	0000			
017	001	0000	0000			
018	001	0000	0000			
019	001	0000	0000			
020	001	0000	0000			
021	001	0000	0000			
022	001	0000	0000			
023	001	0000	0000			
024	001	0000	0000			
025	001	0000	0000			
026	001	0000	0000			
027	001	0000	0000			
028	001	0000	0000			
029	001	0000	0000			
030	001	0000	0000			
031	001	0000	0000			
032	001	0000	0000			
033	001	0000	0000			
034	001	0000	0000			
035	001	0000	0000			
036	001	0000	0000			
037	001	0000	0000			
038	001	0000	0000			
039	001	0000	0000			
040	001	0000	0000			
041	001	0000	0000			
042	001	0000	0000			
043	001	0000	0000			
044	001	0000	0000			
045	001	0000	0000			
046	001	0000	0000			
047	001	0000	0000			
048	001	0000	0000			
049	001	0000	0000			
050	001	0000	0000			
051	001	0000	0000			
052	001	0000	0000			
053	001	0000	0000			
054	001	0000	0000			
055	001	0000	0000			
056	001	0000	0000			
057	001	0000	0000			
058	001	0000	0000			
059	001	0000	0000			
060	001	0000	0000			
061	001	0000	0000			
062	001	0000	0000			
063	001	0000	0000			
064	001	0000	0000			
065	001	0000	0000			
066	001	0000	0000			
067	001	0000	0000			
068	001	0000	0000			
069	001	0000	0000			
070	001	0000	0000			
071	001	0000	0000			
072	001	0000	0000			
073	001	0000	0000			
074	001	0000	0000			
075	001	0000	0000			
076	001	0000	0000			
077	001	0000	0000			
078	001	0000	0000			
079	001	0000	0000			
080	001	0000	0000			
081	001	0000	0000			
082	001	0000	0000			
083	001	0000	0000			
084	001	0000	0000			
085	001	0000	0000			
086	001	0000	0000			
087	001	0000	0000			
088	001	0000	0000			
089	001	0000	0000			
090	001	0000	0000			
091	001	0000	0000			
092	001	0000	0000			
093	001	0000	0000			
094	001	0000	0000			
095	001	0000	0000			
096	001	0000	0000			
097	001	0000	0000			
098	001	0000	0000			
099	001	0000	0000			
100	001	0000	0000			

WINDOW SCHEDULE						
TYPE	SIZE	HEIGHT	WEIGHT	FIXED ACCESS	GLAZING	NOTES
W1	2'0" x 4'0"	4'0"	100			
W2	2'0" x 4'0"	4'0"	100			
W3	2'0" x 4'0"	4'0"	100			
W4	2'0" x 4'0"	4'0"	100			
W5	2'0" x 4'0"	4'0"	100			
W6	2'0" x 4'0"	4'0"	100			
W7	2'0" x 4'0"	4'0"	100			
W8	2'0" x 4'0"	4'0"	100			
W9	2'0" x 4'0"	4'0"	100			
W10	2'0" x 4'0"	4'0"	100			
W11	2'0" x 4'0"	4'0"	100			
W12	2'0" x 4'0"	4'0"	100			
W13	2'0" x 4'0"	4'0"	100			
W14	2'0" x 4'0"	4'0"	100			
W15	2'0" x 4'0"	4'0"	100			
W16	2'0" x 4'0"	4'0"	100			
W17	2'0" x 4'0"	4'0"	100			
W18	2'0" x 4'0"	4'0"	100			
W19	2'0" x 4'0"	4'0"	100			
W20	2'0" x 4'0"	4'0"	100			
W21	2'0" x 4'0"	4'0"	100			
W22	2'0" x 4'0"	4'0"	100			
W23	2'0" x 4'0"	4'0"	100			
W24	2'0" x 4'0"	4'0"	100			
W25	2'0" x 4'0"	4'0"	100			
W26	2'0" x 4'0"	4'0"	100			
W27	2'0" x 4'0"	4'0"	100			
W28	2'0" x 4'0"	4'0"	100			
W29	2'0" x 4'0"	4'0"	100			
W30	2'0" x 4'0"	4'0"	100			
W31	2'0" x 4'0"	4'0"	100			
W32	2'0" x 4'0"	4'0"	100			
W33	2'0" x 4'0"	4'0"	100			
W34	2'0" x 4'0"	4'0"	100			
W35	2'0" x 4'0"	4'0"	100			
W36	2'0" x 4'0"	4'0"	100			
W37	2'0" x 4'0"	4'0"	100			
W38	2'0" x 4'0"	4'0"	100			
W39	2'0" x 4'0"	4'0"	100			
W40	2'0" x 4'0"	4'0"	100			
W41	2'0" x 4'0"	4'0"	100			
W42	2'0" x 4'0"	4'0"	100			
W43	2'0" x 4'0"	4'0"	100			
W44	2'0" x 4'0"	4'0"	100			
W45	2'0" x 4'0"	4'0"	100			
W46	2'0" x 4'0"	4'0"	100			
W47	2'0" x 4'0"	4'0"	100			
W48	2'0" x 4'0"	4'0"	100			
W49	2'0" x 4'0"	4'0"	100			
W50	2'0" x 4'0"	4'0"	100			
W51	2'0" x 4'0"	4'0"	100			
W52	2'0" x 4'0"	4'0"	100			
W53	2'0" x 4'0"	4'0"	100			
W54	2'0" x 4'0"	4'0"	100			
W55	2'0" x 4'0"	4'0"	100			
W56	2'0" x 4'0"	4'0"	100			
W57	2'0" x 4'0"	4'0"	100			
W58	2'0" x 4'0"	4'0"	100			
W59	2'0" x 4'0"	4'0"	100			
W60	2'0" x 4'0"	4'0"	100			
W61	2'0" x 4'0"	4'0"	100			
W62	2'0" x 4'0"	4'0"	100			
W63	2'0" x 4'0"	4'0"	100			
W64	2'0" x 4'0"	4'0"	100			
W65	2'0" x 4'0"	4'0"	100			
W66	2'0" x 4'0"	4'0"	100			
W67	2'0" x 4'0"	4'0"	100			
W68	2'0" x 4'0"	4'0"	100			
W69	2'0" x 4'0"	4'0"	100			
W70	2'0" x 4'0"	4'0"	100			
W71	2'0" x 4'0"	4'0"	100			
W72	2'0" x 4'0"	4'0"	100			
W73	2'0" x 4'0"	4'0"	100			
W74	2'0" x 4'0"	4'0"	100			
W75	2'0" x 4'0"	4'0"	100			
W76	2'0" x 4'0"	4'0"	100			
W77	2'0" x 4'0"	4'0"	100			
W78	2'0" x 4'0"	4'0"	100			
W79	2'0" x 4'0"	4'0"	100			
W80	2'0" x 4'0"	4'0"	100			
W81	2'0" x 4'0"	4'0"	100			
W82	2'0" x 4'0"	4'0"	100			
W83	2'0" x 4'0"	4'0"	100			
W84	2'0" x 4'0"	4'0"	100			
W85	2'0" x 4'0"	4'0"	100			
W86	2'0" x 4'0"	4'0"	100			
W87	2'0" x 4'0"	4'0"	100			
W88	2'0" x 4'0"	4'0"	100			
W89	2'0" x 4'0"	4'0"	100			
W90	2'0" x 4'0"	4'0"	100			
W91	2'0" x 4'0"	4'0"	100			
W92	2'0" x 4'0"	4'0"	100			
W93	2'0" x 4'0"	4'0"	100			
W94	2'0" x 4'0"	4'0"	100			
W95	2'0" x 4'0"	4'0"	100			
W96	2'0" x 4'0"	4'0"	100			
W97	2'0" x 4'0"	4'0"	100			
W98	2'0" x 4'0"	4'0"	100			
W99	2'0" x 4'0"	4'0"	100			
W100	2'0" x 4'0"	4'0"	100			

[illegible]










NOTES:
DO NOT SCALE FROM DRAWINGS.
VERIFY ALL DIMENSIONS ON SITE BEFORE COMMENCING
WORK. COPYING OF THIS DRAWING IS STRICTLY PROHIBITED
WITHOUT THE CONSENT OF DANIEL BODDAM ARCHITECTURE
AND INTERIOR DESIGN PTY LTD.
DIMENSIONS SET OUT FROM WALLS ARE TAKEN FROM THE
FACE OF STRUCTURAL ELEMENTS. WALL LININGS AND
FINISHES ARE INCLUDED IN THE DIMENSION VALUE.

Daniel Boddam
Architecture & Interior
Design

[illegible]

PROJECT STATUS: DEVELOPMENT APPLICATION		
PROJECT: 121 PACIFIC RD PALM BEACH		
CLIENT: KEDE CARBONI		
DRAWING TITLE: LOWER GROUND		
DRAWN BY: Author	CHECKED BY: Checker	DRAWING ISSUE DATE: 21.09.03
PROJECT NO.: 0267	SCALE/GEAT	DWG NO.: DA103
		REV NO: 3



NOTES:
DO NOT SCALE FROM DRAWINGS
VERIFY ALL DIMENSIONS ON SITE BEFORE COMMENCING WORK. COPYING OF THIS DRAWING IS STRICTLY PROHIBITED WITHOUT THE CONSENT OF DANIEL BODDAM ARCHITECTURE AND INTERIOR DESIGN PTY LTD.
DIMENSIONS SET OUT FROM WALLS ARE TAKEN FROM THE FACE OF STRUCTURAL ELEMENTS. WALL FINISHES AND FINISHES ARE INCLUDED IN THE DIMENSION VALUES

REV	DATE	AMENDMENT
3	21.09.23	CONSULTANT ISSUE
2	21.08.20	CLIENT ISSUE
1	20.08.21	CLIENT ISSUE



Daniel Boddam
Architecture & Interior
Design

B

70/60-2011, 1006 Boundary Street, Crows Nest NSW 1585, Australia
Tel: 02 9550 1000 Fax: 02 9550 1001 Email: info@boddam.com.au
ABN: 68 620 620 620
VAT: 620 620 620

CLIENT TYPE:
DEVELOPMENT APPLICATION
PROJECT:
121 PACIFIC RD PALM BEACH
CLIENT:
KEDE CARBONI
BASMENT PLAN

Drawn By:	Checked By:	Drawing Issue Date:
Author	Checker	21.09.23
Project No:	Drawing No:	Rev No:
0267	DA104	3






EXTS - FRONT OF HOUSE




EXTS - REAR OF HOUSE




EXTS - SIDE OF HOUSE




5 DEMO - NORTH ELE
1:200




6 DEMO - SOUTH ELE
1:200



1 ELEVATION - EAST - A
1:100







3 ELEVATION - EAST - B
1:100



2 ELEVATION - WEST
1:100

SCALE BAR																			
NOTES: DO NOT SCALE FROM DRAWINGS VERIFY ALL DIMENSIONS ON SITE BEFORE COMMENCING WORK. COPYING OF THIS DRAWING IS STRICTLY PROHIBITED WITHOUT THE CONSENT OF DANIEL BODDAM ARCHITECTURE AND INTERIOR DESIGN PTY LTD. DIMENSIONS SET OUT FROM WALLS ARE TAKEN FROM THE FACE OF STRUCTURAL ELEMENTS. WALL LININGS AND FINISHES ARE INCLUDED IN THE DIMENSION VALUE.																			
<table border="1"> <tr> <th>REV</th> <th>DATE</th> <th>AMENDMENT</th> </tr> <tr> <td>1</td> <td>21.08.20</td> <td>ISSUE</td> </tr> <tr> <td>2</td> <td>21.08.20</td> <td>CLIENT ISSUE</td> </tr> <tr> <td>3</td> <td>20.08.21</td> <td>CLIENT ISSUE</td> </tr> <tr> <td>4</td> <td>21.11.19</td> <td>DA</td> </tr> <tr> <td>5</td> <td>20.08.19</td> <td>DA</td> </tr> </table>		REV	DATE	AMENDMENT	1	21.08.20	ISSUE	2	21.08.20	CLIENT ISSUE	3	20.08.21	CLIENT ISSUE	4	21.11.19	DA	5	20.08.19	DA
REV	DATE	AMENDMENT																	
1	21.08.20	ISSUE																	
2	21.08.20	CLIENT ISSUE																	
3	20.08.21	CLIENT ISSUE																	
4	21.11.19	DA																	
5	20.08.19	DA																	
Daniel Boddam Architecture & Interior Design 																			
121 Pacific Rd, 10th Boundary Street, Palm Beach NSW 2108, Australia PO Box 1000, Palm Beach NSW 2108, Australia 02 9371 1000 02 9371 1000 02 9371 1000																			
DEVELOPMENT APPLICATION PROJECT: 121 PACIFIC RD PALM BEACH CLIENT: KEDE CARBONI ELEVATIONS DRAWN BY: DB CHECKED BY: DB DRAWING ISSUE DATE: 21.08.20 PROJECT NO: 0267 SCALE: 1:100 DATE: 21.08.20 REV NO: 5																			



NOTES:
DO NOT SCALE FROM DRAWINGS.
VERIFY ALL DIMENSIONS ON SITE BEFORE COMMENCING
WORK. COPYING OF THIS DRAWING IS STRICTLY PROHIBITED
WITHOUT THE CONSENT OF GANESH SODDAM ARCHITECT
AND INTERIOR DESIGN PTY LTD.
DIMENSIONS SET OUT FROM WALLS ARE TAKEN FROM THE
FACE OF STRUCTURAL ELEMENTS. WALL LININGS AND
FINISHES ARE INCLUDED IN THE DIMENSION VALUE

Daniel Boddam
Architecture & Interior
Design

media. If, for boundary areas, institutions may use 20% more on the 10th, with post-tax 130% (+ 20%) 2000 + 144.

PROJECT STATUS		
DEVELOPMENT APPLICATION		
PROJECT:		
121 PACIFIC RD PALM BEACH		
CLIENT:		
KEDE CARBONI		
DRAWING TITLE		
DEMOLITION PLANS		
DRAWN BY:	CHECKED BY:	DRAWING ISSUE DATE:
Author	Checker	21.09.03
PROJECT NO:	SCALE 1/4" = 1'-0"	DWG NO:
0267		DA105
		REV NO:
		1

